

Name of Work: Restoration of Road in the Southern Avenue Road at South Phase of TANSIDCO Industrial Estate, Ambattur in Chennai District						
EMD - Rs.52,000/-				Date of Tender : 13.04.2022		
SCHEDULE OF QUANTITIES						
SL. NO	QTY	DESCRIPTION OF WORK	TNBP NO	RATE IN FIGURES AND WORDS	UNIT	AMOUNT
1	142 Cum (One Hundred and Forty Two)	<b>Providing and laying 50mm compacted thick Bituminous Macadam</b> using 0.42cum of 26.50 - 11.20 mm graded metal and 0.10cum of 11.20 - 2.80mm graded metal and 0.18cum of 2.80mm and below with 38 Kgs of bitumen for premixing 10Sqm including cost and conveyance of all materials to CMP site, heating the bitumen and aggregates to required temperature and mixing them in required temperature in central Hot mix plant 20-30 tons capacity conveying the mix by Tipper trucks to paver site, spreading the mix in required temperature for uniform thickness of 50mm with mechanical paver to the specified grades and cross sections and compaction by 8-10 T power roller to required density etc. including labour for loading bitumen into bitumen tank and metal to feeder unit, labour for attending the paver site etc. including hire charges and fuel charges for 20-30T CMP with bitumen boiler, tipper trucks, paver finisher, power rollers and all other tools and plants employed etc., complete as per clause 504 of MORTH Specification.	MORTH 501 & 504		1 Cum (One Cubic Metre)	

CONTRACTOR

NO.OF CORRECTIONS IN FIGURE:  
NO.OF CORRECTIONS IN WORDS:

SUPERINTENDING ENGINEER i/c

SL. NO	QTY	DESCRIPTION OF WORK	TNBP NO	RATE IN FIGURES AND WORDS	UNIT	AMOUNT
2	569 Cum (Five Hundred and Sixty Nine)	<b>Providing and laying 40mm compacted thick Dense Bituminous Concrete</b> using 0.10cum of 13.20mm Graded IRC HBG metal, 0.21cum of 11.20mm graded IRC HBG metal, 0.23cum of 4.75mm and below with 47.12 Kgs of bitumen for premixing per 10Sqm including cost and conveyance of all materials to CMP site, heating the bitumen and aggregates to required temperature and mixing them in required temperature in central Hot mix plant 20-30 tons capacity conveying the mix by Tipper trucks to paver site, spreading the mix in required temperature for uniform thickness of 40mm with mechanical paver to the specified grades and cross sections and compaction by 8-10 T power roller to required density etc. including labour for loading bitumen into bitumen tank and metal to feeder unit, labour for attending the paver site etc. including hire charges and fuel charges for 20-30T CMP with bitumen boiler, tipper trucks, paver finisher, power rollers and all other tools and plants required including all other incidental charges etc., complete as per clause 508 of MORTH using CMP.	MORTH 501 & 511		1 Cum (One Cubic Metre)	

CONTRACTOR

NO.OF CORRECTIONS IN FIGURE:  
NO.OF CORRECTIONS IN WORDS:

SUPERINTENDING ENGINEER i/c

SL. NO	QTY	DESCRIPTION OF WORK	TNBP NO	RATE IN FIGURES AND WORDS	UNIT	AMOUNT
3	14220 Sqm (Fourteen Thousand Two Hundred and Twenty)	<b>Providing and laying Tack Coat</b> over existing BT surface treated with priming coat using 3.00kgs of bitumen Emulson for 10 Sqm area including cost and conveyance of bituminous binder including labour charges for preparing the surface and applying the required quantity of bitumen as tack coat by bitumen sprayer etc., complete as per clause 503 of MORTH specification.	MORTH 503		1 Sqm (One Square Metre)	
<b>3 Items (Three Items Only)</b>					<b>Total in Rs.</b>	
<b>Note: The tender invited excluding GST. At the time of acceptance of the tender and signing of agreement, the applicable GST of 18% will be included for this work.</b>						

CONTRACTOR

NO.OF CORRECTIONS IN FIGURE:  
NO.OF CORRECTIONS IN WORDS:

SUPERINTENDING ENGINEER i/c