

## TENDER SCHEDULE

**Namw of work: Construction of 30000Litres capacity OHT at 2nd ward new colony in Town sentharapatty Panchayat.**

**Scheme :15th Finance commission(Tied Grand) 2021-22**

**Estimate Amount : 1,050,000.00**

Sl. No	Qty		Description of Work	Unit	Rate in		Amount
					Figures	Words	
1	63.20	M³	Earth work Excavation for Foundation in all soils and Sub Soil as per SS20B for foundation etc. complete.SS 20B	1 (One Cubic Meter )			
2	3.46	M³	Cement concrete 1:4:8 mix using 40mm ISS metal including cost and conveyance of all materials to site and all labour charges for mixing,laying and curing etc complete	1 (One Cubic Meter )			
3	0.00	0.00	Reinforced cement concrete 1:1.5:3mix using 20mm ISS metal including cost and conveyance of all materials to site and all labour charges for mixing, laying, and curing etc complete	1 (One Cubic Meter )			
0	7.58	m3	Items 1.50 m to 4.50m below GL	1 (One Cubic Meter )			
0	1.89	m3	Items 0 m to 1.50m below GL	1 (One Cubic Meter )			
0	2.83	m3	Items 0.0 to 4.50m Above GL	1 (One Cubic Meter )			
0	2.22	m3	Items Above 4.51m to 7.32 m	1 (One Cubic Meter )			
0	2.53	m3	Items Above GL 7.33m to 10.98m	1 (One Cubic Meter )			

Signature of Contractor

Sl. No	Qty		Description of Work	Unit	Rate in		Amount
					Figures	Words	
0	3.09	m3	Items 10.98 m to 14.64 m above GL	1 (One Cubic Meter )			
0	11.40	m3	14.64 m 18.30m above GL	1 (One Cubic Meter )			
4	0.00	0.00	Supplying and erecting centering shuttering including necessary supports for plane surface in foundation and basement and in all floors for R C C column footing column plinth beam, beams, roof slabs, staircase steps, bed blocks, critical pier etc using mild steel sheets of size 90 x 60 cm and 10 guage stiffened, welded with mild steel angles of size 25mmx25mmx3mm for boarding laid over silver oak (country wood) scantlings of size 10cm x 6.5cm spaced of about 90cm centre to centre and supported by casurina props of 10cm to 13cm dia spaced at 75cm centre to centre complete complying with standard specifications and as directed by departmental officers including conveyance of all materials to site and proper centering etc complete.				
0	20.76	M2	For Plan surface	1 (one Number )			
0	26.39	M2	From 0.00 -3.30m	1 (one Number )			

Signature of Contractor

Sl. No	Qty		Description of Work	Unit	Rate in		Amount
					Figures	Words	
0	11.96	M2	From 5.30m to 6.30 m	1 (one Number )			
0	11.96	M2	From 8.30m to 9.30m above G.L	1 ( One Kilo Grams )			
0	39.93	M2	From 11.30 m to 12.30m	1 (one Number )			
0	79.24	M2	Curved Surface	1 (one Number )			
0	4.80	M2	From 5.31-6.30m Height	1 (One Sequire Meter )			
0	0.00	M2	Square column	1 (One Sequire Meter )			
0	21.60	M2	Below GL	1 (One Sequire Meter )			
0	4.80	M2	3.31 to 4.30mm	1 (One Sequire Meter )			

Signature of Contractor

Sl. No	Qty		Description of Work	Unit	Rate in		Amount
					Figures	Words	
0	4.80	M2	4.31 to 5.30mm	1 (One Sequire Meter )			
0	4.08	M2	5.31 to 6.30mm	1 (One Sequire Meter )			
0	4.80	M2	6.31 to 7.30mm	1 (One Sequire Meter )			
0	4.80	M2	7.31 m to 8.30m	1 (One Sequire Meter )			
0	4.08	M2	8.31 to 9.30m ht	1 (One Sequire Meter )			
0	4.80	M2	9.31 m to 10.30m	1 (One Sequire Meter )			
0	4.80	M2	10.31 to 11.30m ht	1 (One Sequire Meter )			

Signature of Contractor

Sl. No	Qty		Description of Work	Unit	Rate in		Amount
					Figures	Words	
0	0.48	M2	11.31 m to 11.40m	1 (One Sequire Meter )			
5	160.43	m2	Painting two coats over new plastered using approved cement paint including cost and conveyance of all materials to site and all labour charges etc comoplete	1 (One Sequire Meter )			
6	2.91	MT	Supplying and Fabricating and placing in position MS steel or ribbed for steel for all reinforced cement concrete works as per the design given including cost of steel and binding wire in all floors etc, Complete complying with stanard specification.	1 (One ton )			
7	1.00	no	Supplying , Fabricating,Delivery and placing in position MS steel Ladder wide 0.45m made out of 50x50x6mm MS angle for sides and steps in 16mm MS plain rods fixed at 30cm c/c welded and Jointed etc. , Complete complying with stanard specification.	1 (one Number )			
8	1.00	no	Supplying and Fixing of RCC inner access Ladder in RCC 1:11/2:3mix etc. , Complete complying with stanard specification.	1 (one Number )			
9	2.00	no	Providing PVC ventilating arrangements mosquito proof nylon net with 110mm PVC cowl and as directed by Departmental Officers	1 (one Number )			
10	1.00	no	Providing Cut stone slab in CM 1:3 mix and as directed by Departmental Officers	1 (one Number )			

Signature of Contractor

Sl. No	Qty		Description of Work	Unit	Rate in		Amount
					Figures	Words	
11	1.00	no	Providing Manhole cover of size 0.60x0.60 m in RCC 1:11/2:3 mix with suitable reinforcement and 50x50x6mm Ms angle fixed along edges and as directed by Departmental Officers	1 (one Number )			
12	40.30	m3	Refilling in Basement with excavated Earth in layers of not more than 15cm. Thick well rammed, watered and consolidated complying with standard specifications etc., complete.	1 (One Cubic Meter )			

Signature of Contractor