

**EDAIKAZHINADU TOWN PANCHAYAT**

Date of Tender :  
 Schedule Amount :  
 Chellan No. :  
 & Date  
 Issued to Thiru/Tmt .

**TENDER SCHEDULE – TYPE "A"****SCHEDULE OF RATES APPROXIMATE QUANTITIES**

E.O.

- a) The quantities here given those the lump sum tender cost of work is based but they are subject to alterations omissions deductions as provided for in the conditions of this contract and do shown actual quantities of work top done to unit rates noted below are those covering payment extras of reductions omissions for according to the conditions of contract as set for in the preliminary specifications of the TNBPR and other conditions of contract specification of this contract.
- b) It is to be expressed immder stood that rent works is to be taken net (not withstanding any or practice to the contrary) according to the actual quantities in Balance finished according to the drawings or as may be provided from time by the Town Panchayat Engineer and the cost calculated by measurement or weight of the respective any additional charges for any necessary connected to the work. The rates quoted in site and complete in every respect.

Name of the Scheme : **O&M -(2021-2022)****Est. Amt: Rs. 1000000****Name of Work: Providing PVC pipe line @ work at Ward No 13 Kottaikadu Kasibattai Salai (2) Ward No 20 Vilambur**

**Name Of Work: (3) Ward No 2 Othiyur ECR and (4) Ward No 1 Nainarkuppam ECR Merkku (5) Ward No 12 Saibaba kovil joint to ECR**  
**, and OHT Tank joint to Kasibattai joint Road in Edaikazhinadu Town Panchayat**

Name of the Scheme : **O&M -(2021-2022)**

**Est. Amt: Rs. 1000000**

**Name of Work: Providing PVC pipe line @ work at Ward No 13 Kottaikadu Kasibattai Salai (2) Ward No 20 Vilambur**

**Name Of Work: (3) Ward No 2 Othiyur ECR and (4) Ward No 1 Nainarkuppam ECR Merkku (5) Ward No 12 Saibaba kovil joint to ECR**

**, and OHT Tank joint to Kasibattai joint Road in Edaikazhinadu Town Panchayat**

Sl. No.	Quantity	Description of Works	MDSS/SSRB	Unit in Words	Rate in		Remarks
					Figures	Words	
1	1380.00 M3	Earthwork excavation and depositing on bank with initial lead and lift all classes of soil at 100% narrow cutting for foundation works as per SS20B.(HGS) Item No. 62.		1M <sup>3</sup> (One Cubic Metre)			
2	2300.00 Mtr	Supply and Delivery of unpasted 90mm PVC pipe 6KSC PVC pipe including cost and conveyance and all other labour charges etc. complete.(TWAD SR 2021-22		1M (One Running Metre)			
3	2300.00 Mtr	Lowering the 90 mm PVC pipe 6KSC PVC Rigid pipe into trenches proper grade and alignment including cost and conveyance of all materials and all other labour charges for laying, testing etc., complete. (TWAD SR 2021-22		1M (One Running Metre)			
4	1380.00 M3	Refilling with excavated earth including all other labour charges for filling, levelling as per Standard specification etc. complete. (TWAD SR 2021-22 - P.No.80)		1M (One Running Metre)			

No. of Corrections:No. of Overwritings:

Signature of Contractor:

Name of the Scheme : **O&M -(2021-2022)**

**Est. Amt: Rs. 1000000**

**Name of Work: Providing PVC pipe line @ work at Ward No 13 Kottaikadu Kasibattai Salai (2) Ward No 20 Vilambur**

**Name Of Work: (3) Ward No 2 Othiyur ECR and (4) Ward No 1 Nainarkuppam ECR Merkkku (5) Ward No 12 Saibaba kovil joint to ECR**

**, and OHT Tank joint to Kasibattai joint Road in Edaikazhinadu Town Panchayat**

Sl. No.	Quantity	Description of Works	MDSS/SSRB	Unit in Words	Rate in		Remarks
					Figures	Words	
5	5.00 No	Supply and delivery of 50mm dia GM gate valve including cost and conveyance and all othaer labour charges etc compilete		1M <sup>3</sup> (One Cubic Metre)			
6	60.00 No	Supply and delivery of 65m dida gi pipe for encasong including cost and conyveyance and all other labour charges etc compltete		1No. (One Number)			
7	40.00 No	costand fining of PF Stand Point Including cos of Maintanance and Labour Charges Complete		1No. (One Number)			

No. of Corrections:No. of Overwritings:

Signature of Contractor: