

Riparian Tree Planting, Fencing and Instream Works on Finn River between bridge at Killygordon and bridge at Liscooley, Finn Catchment, Co. Donegal

Detailed description:

Riparian Tree Planting, Fencing and Instream Works on Finn River between bridge at Killygordon and bridge at Liscooley, Finn Catchment, Co. Donegal: The works will take place between the bridge at Killygordon and the bridge at Liscooley in the Finn River Catchment, Co. Donegal. The works will include the installation of fencing on both banks of the river between the two bridges. Fencing will be a mix of sheep wire, double strand barbed wire and double strand electrified wire (exact lengths and locations given in Spec of Works document). Tree planting will be carried out in numerous areas along the stretch in the new riparian zone and will consist of a mix of approx. 5,663 native broadleaf trees. Two areas along the southern bank of the works area will require the embankment to be re-inforced with clay/gravel mix and planted with grass and trees to stabilise. High and dry gravel beds at several locations will be regrading using a riddle bar and woody material will be pinned in the river at 6 locations across the area. Finally, a small footbridge must be removed and replaced with a new structure for use by landowners and anglers to cross a stream at one location.

Type of contract:

Services

Response deadline (Irish time):

09/05/2022 17:00:00

CPV codes:

45243510-0 Embankment works
45246200-5 Riverbank protection works
45262640-9 Environmental improvement works
45340000-2 Fencing, railing and safety equipment installation work
45342000-6 Erection of fencing
71313000-5 Environmental engineering consultancy services
71332000-4 Geotechnical engineering services
71337000-9 Corrosion engineering services
77310000-6 Planting and maintenance services of green areas
90722000-4 Environmental rehabilitation
98342000-2 Work environment services