

### **Arney River Phase 3 - Riparian works along the bank of the Arney River**

#### Detailed description:

CatchmentCARE is a five year INTERREG funded project, managed through the Special EU Programmes Body (SEUPB) taking place across Ireland and Northern Ireland. Inland Fisheries Ireland wishes to hire a suitably qualified contractor to complete the works as outlined below. A. To erect fencing along both banks of the Arney at specified areas (see maps). The overall approximate distance of fencing will be 3000m. Fencing/stiles/gate installation to be completed to the standards set out in 'Volume D – Specifications'. B. To install 18 nr. livestock drinkers (plastic), laid on hard core material and connected to water supply (mains) as specified in 'Volume D- Specifications'. Supply, bury (at a depth of no less than 300mm) and connect water pipe to drinkers. Water piping for drinkers accumulates to approximately 3100m. For locations of drinkers and waterpipe see maps in Annex 1. C. To install 20 nr. Gates (galvanised) as specified in 'Volume D- Specifications'. For locations of gates see maps in Annex 1. D. To install 1 nr. pasture pumps, to the standards set out in 'Volume D – Specifications'. For locations of pasture pumps see maps in Annex 1. Please Note: IFI expects to deliver this project in two stages in line with operational needs. To facilitate this approach, items should be priced individually in Stage A and Stage B as set out in 'Volume C- Pricing Schedule'. Project must completed no later than 19th August 2022.

#### Type of contract:

Works

#### Response deadline (Irish time):

10/06/2022 17:00:00

#### CPV codes:

34928200-0 Fences  
44161200-8 Water mains  
44162500-8 Drinking-water piping  
44221300-8 Gates  
45231300-8 Construction work for water and sewage pipelines  
45240000-1 Construction work for water projects  
45421148-3 Installation of gates