## SWS22 St Oliver Plunketts Finglas Dublin 11

## Detailed description:

This project is a School heating primary & secondary distribution system upgrade. The existing system will be isolated and removed, and a new system installed in its place. The mechanical works involve the fit-out of the following systems:

1. Heating – Demolition and removal of existing distribution system complete with all components, boilers, flues, circuits etc. (LPHW) 2. Heating – Installation of new Low pressure hot water secondary distribution system throughout the school including radiators, radiant panels, 2-port MV controls & individual room temp stats (LPHW) 3. New BMS panel & field devices 4. Associated builder's works 5. Associated electrical works

Type of contract:

Services

Response deadline (Irish time):

01/06/2022 12:00:00

CPV codes:

45350000-5 Mechanical installations

45351000-2 Mechanical engineering installation works

51100000-3 Installation services of electrical and mechanical equipment

51120000-9 Installation services of mechanical equipment