



GOVERNMENT OF PAKISTAN
PAKISTAN PUBLIC WORKS DEPARTMENT

Office of the EE, CCD-I, Pak PWD 11-Egerton Road, Lahore Phone No. 99200489

No. EE/CCD-I/LHR/Adv1/AB/ 1186
To,

Lahore 23/05/2022.

The Director,
Regional Information Office,
P.I.D., Government of Pakistan,
204/A, Garden Town,
Lahore.

SUBJECT:- REQUISITION FOR CLASSIFIED ADVERTISEMENT.

Dear Sir,

Please arrange the publication of the attached advertisement under classified column in widely circulated daily National Newspapers i.e. (one in Urdu & one in English) according to the requirements as specified below. The overall expenditures on this account may please be kept minimum and information about publication, name of newspaper and date of insertion may be intimated to this office.

1. Language:	English / Urdu
2. Region:	Lahore
3. No. of Insertions	Two insertions, (One in English and One in Urdu) in smaller letters having minimum space.
4. Date of Insertion:	27.05.2022

It is certified that necessary funds are available to meet the entire cost of the advertisement during the current financial year of 2021-22. The advertisement of Tender Notice may be restricted to two widely circulated daily National Newspapers (One in Urdu & One in English) only. The advertisement bill (in duplicate) duly verified by PID along with original newspapers may be furnished to this office for payment.


Encl:- **As Above**

(Khurshid Ahmed Mirza)

Executive Engineer
Central Civil Division No.I
Pak, P.W.D., Lahore.
Ph#042-99200489

Copy forwarded for information to:-

1. The Chief Engineer (Central Zone), Pak PWD, Lahore.
2. The Superintending Engineer, Central Civil Circle, Pak, PWD, Lahore.
3. The Divisional Accounts Officer, of this Division.
4. All Assistant Executive Engineers of this Division.
5. The Deputy Director, PPRA Cabinet Division, FBC Building near SBP, G-5/2, Islamabad with the request to advertise the Tender Notice and upload BOQ on PPRA's Website.
6. The Cashier of this Division.
7. Notice Board.


EXECUTIVE ENGINEER

GOVERNMENT OF PAKISTAN
PAKISTAN PUBLIC WORKS DEPARTMENT

Office of the EE, CCD-I, Pak PWD 11-Egerton Road, Lahore Phone No. 99200489 Fax # 99202333
No. EE/CCD-I/LHR/Adv1/AB/ 1186

Lahore 23/05/2022.

NOTICE INVITING TENDERS

Sealed tenders are invited from the contractors registered with Pakistan Engineering Council / Pak PWD under relevant category, on percentage rates based on Pak PWD Schedule of Rates 2022, who possess valid PEC / Pak PWD License / Renewal upto: 30.06.2022. Tender documents can be received from the office of the undersigned during office hours on any working day as per schedule given below:-

i. Issuance of tenders upto: **13.06.2022**.

ii. Casting & opening of tenders on **14.06.2022**

With written on company's letter Pad accompanied with attested copy of CNIC, Income tax Registration Certificate as active Tax Payer (filer), and copy of valid Registration with PEC / Pak PWD under relevant category. Tenders will be issued to the proprietors of the firm / company or their legally authorized representatives having registered power of attorney (dully attested). The tenders in sealed cover should be dropped in the tender box kept in the office of undersigned on **14.06.2022** upto: **12.00 P.M.** The respective tenders will be opened on the same day at **12.30 P.M.** in the presence of contractors or their authorized representatives, having registered Power of Attorney. BOQ of the work is also available at PPRA website (www.ppra.org.pk). Other terms & conditions can be seen in the office of the undersigned during office hours on any working day.


TERMS & CONDITIONS.

- 1). No tender will be sold / issued on the day of opening of tenders and in case of public holiday, the receipt and opening of tenders will be the next working day.
- 2). No tender will be issued through post, telegraph or E-Mail.
- 3). According to PPRA Rule-25, Bid Security @ 4% or as mentioned of estimated cost is required in the shape of bank instrument (CDR) from the firm / the company's owned account from any Scheduled Bank of Pakistan in the name of the Executive Engineer, Central Civil Division, No.I, Pak PWD, Lahore. No tender will be entertained without bid security @ 4% of bid price or less amount.
- 4). Tenders can be purchased on the prescribed cost **(Non-Refundable) in the shape of** bank instrument **(CDR)** from the firm / the company's owned account from any Scheduled Bank of Pakistan in the name of the Executive Engineer, Central Civil Division, No.I, Pak PWD, Lahore, mentioned against the below noted work from the office of the undersigned during office hours upto: **13.06.2022** before the date of opening of tenders.
- 5). No tender will be issued to the contractor without submission of **4% CDR of NIT amount (in original)** from the firm / the company's owned account and mentioning firm's name from any Scheduled Bank of Pakistan in the name of the Executive Engineer, Central Civil Division, No.I, Pak PWD, Lahore, however, difference in the cost of Bid Price, balance amount of Call at Deposit should be attached with the bid. The name of work, CDR No. date & amount should be mentioned by the contractors / firms on their applications.

- 6). **Tender Notice is also available at PPRA Website (www.ppra.org.pk).**
- 7). Under rule 33(1) of Public Procurement Rules, 2004, the undersigned reserves the right to reject all bids or proposals at any time prior to the acceptance of bid or proposal.
- 8). The submission of tenders by the contractor implies that he is fully conversant with the site of work, scope of work and terms and conditions as laid down in the tender documents.

Sr. No	Particular of works	NIT Amount (Rs.)	Earnest Money / Bid Security (Rs.)	Period of completion	Cost of Tender (Non-refundable)	Financial Limit of contractor
1.	Repair and Maintenance of Office Building Tax House Syed Mouj Darya Road, Lahore.	Rs. 5,719,924/-	04% of Bid Price	02-Months	2,000/-	Relevant Category with PEC
2.	Repair / Renovation work at the O/o the Provincial Election Commission Punjab, Lahore.	Rs. 940,498/-	04% of Bid Price	01-Month	1,000/-	Relevant Category with Pak PWD

Note:- Uncontested tenders will be sold upto: **20.06.2022** and will be received back on **21.06.2022** upto: 12.00 P.M. and will be opened at 12.30 P.M. While other Terms & Conditions will remain same.


(Khurshid Ahmed Mirza)
 Executive Engineer
 Central Civil Division No.I
 Pak, P.W.D., Lahore.
Ph#042-99200489

(7) (41)

NIT

NAME OF WORK:-

**REPAIR AND MAINTENANCE OF OFFICE BUILDING TAX HOUSE SYED MOUJ DARYA
ROAD LAHORE.**

S.No	Sub-Heads and Item of Work	Qty		Rate		Per Unit	Amount Rs.
SCHEDULE RATE ITEMS							
1	Dismantling cement tiled floor, dado or skirting in basement, plinth and ground floor including base mortar and stacking salvaged material (serviceable) and disposing of surplus stuff as directed within three chains (91.5 m)...	✓		✓		✓	
a	6th floor	2250	Sft	7,761.25	Rupees Seven Thousand Seven Hundred Sixty One and Twenty Five Paisas Only	%Sft	174,628
b	7th floor	2250	Sft	8,442.50	Rupees Eight Thousand Four Hundred Forty Two and Fifty Paisas Only	%Sft	189,956
2	Taking out door and window frames with or without hold fasts in 1st floor including cutting walls, stacking salvaged material (serviceable) and disposing of unserviceable material as directed within three chains (91.5 m).	✓		✓		✓	
a	6th floor	10	No	828.16	Rupees Eight Hundred Twenty Eight and Sixteen Paisas Only	Each	8,282
b	7th floor	10	No	868.79	Rupees Eight Hundred Sixty Eight and Seventy Nine Paisas Only	Each	8,688
3	Taking out carefully shutters of doors and windows in ground floor and stacking as directed within three chains (91.5 m).	✓		✓		✓	
a	6th floor	10	No	590.66	Rupees Five Hundred Ninety and Sixty Six Paisas Only	Each	5,906
b	7th floor	10	No	631.29	Rupees Six Hundred Thirty One and Twenty Nine Paisas Only	Each	6,313
4	Dismantling burnt brick masonry in lime or cement mortar foundation, basement, plinth and ground floor including stacking salvaged material (serviceable) and disposing of surplus material as directed within three chains (91.5 m)...	✓		✓		✓	
a	6th floor	151	Cft	7,167.50	Rupees Seven Thousand One Hundred Sixty Seven and Fifty Paisas Only	%Cft	10,823
b	7th floor	151	Cft	7,848.75	Rupees Seven Thousand Eight Hundred Forty Eight and Seventy Five Paisas Only	%Cft	11,852
5	Providing and laying first class solid burnt brick masonry set in mud mortar in straight or curved walls 4-1/2 inches (114 mm) and less in thickness including scaffolding, raking, out joints, curing etc. complete in superstructure.	✓		✓		✓	
a	6th floor	199	Cft	55,927.06	Rupees Fifty Five Thousand Nine Hundred Twenty Seven and Zero Six Paisas Only	%Cft	111,295
c	7th floor	199	Cft	57,780.56	Rupees Fifty Seven Thousand Seven Hundred Eighty and Fifty Six Paisas Only	%Cft	114,983
6	1/2" (13 mm) thick cement plaster 1:4 on walls and columns etc. in basement, plinth, mezzanine and ground floor including making edges, corners, and curing etc., complete .4th floor	✓		✓		✓	
a	6th floor	2235	Sft	5,870.59	Rupees Five Thousand Eight Hundred Seventy and Fifty Nine Paisas Only	%Sft	131,208

(43) (A)

b	7th floor	2236	Sft	6,106.84	Rupees Six Thousand One Hundred Six and Eighty Four Paisas Only	%Sft	136,488
7	Water proofing of roof slab using Bituflex @ 10 Kg per % sft in three coats, i/c cleaning /scraping the extra mortar etc. from the roof surface, and washing the surface with water and filling the depressions using Bituflex: sand mortar (1:2). Applying one primer coat, over moist surface using a mix of 50 % Bituflex and 50 % water blirded the surface with saul any floor in any light.	1208	Sft	1,243.06	Rupees One Thousand Two Hundred Forty Three and Zero Six Paisas Only	%Sft	15,016
8	Providing and laying 1:4:8 cement concrete bed under floors using graded stone ballast 1 inches and down gauge with levelling and ramming, watering and curing etc. complete..						
a	6th floor	151		22,036.75	Rupees Twenty Two Thousand Thirty Six and Seventy Five Paisas Only	%Cft	33,275
b	7th floor	151		22,036.75	Rupees Twenty Two Thousand Thirty Six and Seventy Five Paisas Only	%Cft	33,275
9	Plastering 1/2" (13 mm) thick in patches in cement and sand mortar 1:4 including curing and scraping old damaged portion in regular shape and removal of rubbish from the site etc. complete as per direction of Engineer-in-Charge in 4th floor.						
a	6th floor	66	Sft	6,859.34	Rupees Six Thousand Eight Hundred Fifty Nine and Thirty Four Paisas Only	%Sft	4,527
b	7th floor	104	Sft	7,096.84	Rupees Seven Thousand Ninety Six and Eighty Four Paisas Only	%Sft	7,381
10	Providing and fixing M.S. moulded steel door frame of 4" x 2-1/2" (102 mm x 64 mm) manufactured from mild steel sheet of 18 gauge (1.41 mm) conforming to BSS. 1245 having a single rebate size 1-1/2" x 1/2" (38 mm x 13 mm) with provision of 3 Nos. M.S. plate, section 1-1/2" x 1/4" (38 mm x 6 mm), (2 Nos. 6 inch long welded with frame at not less than 10 points and 1 No., 12 inch long welded with frame at not less than 20 points), with holes and threads for fixing steel hinges, fitted with one locking box of same sheet (point welded inside the frame), 6 Nos. 6 inches long flat iron fixing lugs, of 1-1/4" x 3/16" section, treated with special red oxide primer coat all around including cutting holes and filling the cavity with cement concrete 1:2:4 etc. in any floor at any height complete as directed by the Engineer-in-Charge	176	Rft	393.51	Rupees Three Hundred Ninety Three and Fifty One Paisas Only	P.Rft	69,258
11	Providing and fixing 1-1/2 inch (38 mm) thick best quality deodar wood shutters fully panelled with same wood, approved iron hinges and tower bolts, etc., as required..	189	Sft	1,651.66	Rupees One Thousand Six Hundred Fifty One and Sixty Six Paisas Only	P.Sft	312,164
12	Painting wood work with synthetic enamel paint of approved make and shade two coats over and including the cost of one priming coat complete at any height in any floor .	363	Sft	5,954.86	Rupees Five Thousand Nine Hundred Fifty Four and Eighty Six Paisas Only	%Sft	21,616
13	Repainting two coats with weather shield paint of (ICI) Dulux make and shade on plaster surface (External) including cleaning, sand papering the surface as directed by the Engineer-in-charge in any floor.	22656	Sft	2,546.88	Rupees Two Thousand Five Hundred Forty Six and Eighty Eight Paisas Only	%Sft	577,021
14	Repainting two coats with plastic emulsion paint of (ICI) Dulux make and shade to walls and ceiling including cleaning, and sand papering the surface as directed by the Engineer-in-charge in any floor. 4th floor	1208	Sft	2,578.13	Rupees Two Thousand Five Hundred Seventy Eight and Thirteen Paisas Only	%Sft	31,144
15	Providing and fixing best quality squatting type white glazed earthenware W.C Pan, Pakistani (of not less than 18 inches clear opening as measured between flushing rims) complete with and including the cost of 13.6 litre best quality low level plastic flushing cistern with internal fittings complete, P.V.C. flushing pipe suitable for squatting type with extra bends and length with fittings, C.I. trap 4 inches (100mm) dia and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1:2:4..	10	No	12,802.50	Rupees Twelve Thousand Six Hundred Two and Fifty Paisas Only	Each	126,025

(41) (45)

16	Providing and fixing best quality whit glazed earthen ware one piece toilet (commode) coupled with flush tank (Porta) complete with and i/c cost of plastic seat with buffers, with internal fittings complete as per direction of the Engineer incharge.	9	No	47,750.00	Rupees Forty Seven Thousand Seven Hundred Fifty Only	Each	429,750
17	Providing laying fixing PPRC pipe PN-20 with special , and clamp etc, i/c cutting and fitting complete with and i/c the cost of breaking through walls and roof and making good etc. after cleaning the pipe and cartage within 10 miles 25mm dia.	120	Rft	215.32	Rupees Two Hundred Fifteen and Thirty Two Paisas Only	P.Rft	25,838
a	40 mm dia	36	Rft	433.66	Rupees Four Hundred Thirty Three and Sixty Six Paisas Only	P.Rft	15,612
18	Providing and fixing un plasticized polyvinyl chloride pipe (u.P.V.C) "E" class with specials and clamps etc., including cutting and fitting, complete with and including the cost of breaking through walls and roof and making good etc.; after cleaning the pipe and cartage within 10 miles (16.09 km) (working pressure 12 kg/cm ²) 3/4 inch (20 mm) dia.						
a	1-1/2" (40mm) dia	20	Rft	146.74	Rupees One Hundred Forty Six and Seventy Four Paisas Only	P.Rft	2,935
b	3" (80mm) dia	40	Rft	520.97	Rupees Five Hundred Twenty and Ninety Seven Paisas Only	P.Rft	20,839
c	4" (100mm) dia	40	Rft	719.12	Rupees Seven Hundred Nineteen and Twelve Paisas Only	P.Rft	28,765
d	6" (150mm) dia	60	Rft	867.31	Rupees Eight Hundred Sixty Seven and Thirty One Paisas Only	P.Rft	52,039
19	Providing and fixing C.P. Bib cock 1/2 inch dia.	18	No	1,130.40	Rupees One Thousand One Hundred Thirty and Forty Paisas Only	Each	20,347
20	Providing and fixing bath room accessories of set of 6 pieces consist of one shelf, one towel rod with bracket, one towel ring, one soap dish, one tooth Brush holder with glass, one tissue paper holder one double hook etc complete of approved quality as per direction of Engineer in-charge.	10	No	10,405.25	Rupees Ten Thousand Four Hundred Five and Twenty Five Paisas Only	Each	104,053
21	Providing and fixing uPVC Multi floor trap of sizes with gratings i/c cutting and making the requisite number of holes in walls plinth and floors and making good in CC 1:2:4.	12	No	1,459.43	Rupees One Thousand Four Hundred Fifty Nine and Forty Three Paisas Only	Each	17,513
22	Providing and fixing floor waste 6"x6" (stainless steel) jali etc complete.	12	No	2,023.58	Rupees Two Thousand Twenty Three and Fifty Eight Paisas Only	Each	24,283
23	Providing and fixing C.P. Muslim Bib-cock with Muslim Shower of approved quality.	18	No	3,381.75	Rupees Three Thousand Three Hundred Eighty One and Seventy Five Paisas Only	Each	60,872
24	Providing and fixing best quality earthen ware glazed vanity basin (Porta) standard size (white/light colour) and i/c cost of 1-1/4" dia brass waste 1-1/4" rubber plug and cp brass chain PVC waste pipe 1-1/4" dia approved pattern etc. complete.	10	No	16,420.63	Rupees Sixteen Thousand Four Hundred Twenty and Sixty Three Paisas Only	Each	164,206
25	Providing and fixing 1-1/4"(32mm) dia C.P. brass bottle trap of approved quality.	10	No	2,646.60	Rupees Two Thousand Six Hundred Forty Six and Sixty Paisas Only	Each	26,466
26	Providing & laying light colour, glazed/ non skid vitrified Porcelain tiles (Polished) exceeding 1800 Sq. cm (Pak made) on walls & floors in any floor, laid with dry bond (tile bond) over a base of 1" thick cement mortar (1:3) including jointing to tiles with joint filler of approved quality as per direction of the Engineer incharge.	4500	Sft	38,016.99	Rupees Thirty Six Thousand Sixteen and Ninety Nine Paisas Only	%Sft	1,620,765
27	Providing and fixing PVC board 2' x 2' tiles plain ceiling including Aluminum T & L angle 1"x 1" i.c hanger clips jointing clips and G.I Wire etc complete as required in any floor.	4500	Sft	192.42	Rupees One Hundred Ninety Two and Forty Two Paisas Only	P.Sft	865,890

(47) ✓ (13)

28	Providing and fixing with brass screws door Alpha lock with handle of approved design (Taiwan make), cutting wood etc., to required shape and size with two operating keys as per direction of the Engineer-in-Charge.	24	No	3,149.38	Rupees Three Thousand One Hundred Forty Nine and Thirty Eight Paises Only	Each	75,585
29	Providing and laying 1st class burnt clay tiles of 9" X 4-1/2" X 1-1/2" size grouted with 1:3 cement mortar over 4" thick (avg) puddled earth compacted and smooth finished to slope mixed with bhoosa at the rate of one seer of bhoosa for one cft. of puddled earth in ground floor including flush pointing on tiles works with 1:3 cement mortar and curing complete.	94	Sft	15,377.75	Rupees Fifteen Thousand Three Hundred Seventy Seven and Seventy Five Paises Only	%Sft	14,455
30	Cartage of Sand, Bajri, lime, surki, murum, manure, earth building rubbish i/c loading, unloading and stacking at site lead of 10-miles.	785	Cft	1,122.74	Rupees One Thousand One Hundred Twenty Two and Seventy Four Paises Only	%Cft	8,589
TOTAL							5,719,924

Shahid
 Assistant Executive Engineer
 Central Civil Division No. I
 Pak PWD, Lahore


[Signature]
 Executive Engineer
 Central Civil Division No.
 Pak PWD, Lahore


GENERAL ABSTRACT OF COST

NAME OF WORK:-

REPAIR / RENOVATION WORK AT THE O/O THE
PROVINCIAL ELECTION COMMISSION PUNJAB.

BUILDING (SCHEDULE ITEMS)	Rs.	601,236
BUILDING (NON-SCHEDULE ITEMS)	Rs.	199,008
W/S & S/I (SCHEDULE ITEMS)	Rs.	103,390
W/S & S/I (NON-SCHEDULE ITEMS)	Rs.	36,864
Total	Rs.	940,498


Assistant Executive Engineer
Central Civil Division No.I
Pak PWD, Lahore.


Executive Engineer
Central Civil Division No.I
Pak PWD, Lahore.

NIT

NAME OF WORK:-

REPAIR / RENOVATION WORK AT THE O/O THE PROVINCIAL ELECTION COMMISSION PUNJAB.

PUNJAB.							
Sr. No.	Item of work	Qty		Rate		Unit	Amount
	BULIDING SCHEDULE ITEMS						
1	Taking out door and window frames with or without hold fasts in ground floor including cutting walls, stacking salvaged material (serviceable) and disposing of unservice-able material as directed within three chains (91.5 m).						
	a) Ground Floor	2	No	584.38	Rupees Five Hundred Eighty Four and Thirty Eight Paisas Only	Each	1169
2	Taking out carefully shutters of doors and windows in ground floor and stacking as directed within three chains (91.5 m).						
	a) Ground Floor	2	No	346.88	Rupees Three Hundred Forty Six and Eighty Eight Paisas Only	Each	694
3	Dismantling burnt brick masonry in lime or cement mortar foundation, basement, plinth and ground floor including stacking salvaged material (serviceable) and disposing of surplus material as directed within three chains (91.5 m).						
	a) Ground Floor	153	Cft	3006.25	Rupees Three Thousand Six and Twenty Five Paisas Only	%Cft	4600
4	Dismantling cement tiled floor, dado or skirting in basement, plinth and ground floor including base mortar and stacking salvaged material (serviceable) and disposing of surplus stuff as directed within three chains (91.5 m).						
	a) Ground Floor	300	Sft	2605.63	Rupees Two Thousand Six Hundred Five and Sixty Three Paisas Only	%Sft	7817
5	Dismantling C.C. floor upto 2" (51 mm) thick in basement, plinth and ground floor including disposing off the material as directed within three chains (91.5 m).	99	Cft	1503.13	Rupees One Thousand Five Hundred Three and Thirteen Paisas Only	%Cft	1488
6	Excavation for foundation trenches and drains in all kinds of soil (except gravelly and murum soil, wet silt, clay or mud conglomeration of gravel and boulders, soft, sandy or disintegrated sandy and hard rock) and back filling the excavated material in foundation, plinth or under floor including breaking clods, watering, consolidation by ramming in layers not exceeding 9 inches (229 mm) in depth to full compaction, dressing and disposal of surplus excavated stuff as directed, lead upto one chain (30.5 R.m) and lift upto 5 feet (1.52 m).	75	Cft	1624.63	Rupees One Thousand Six Hundred Twenty Four and Sixty Three Paisas Only	%Cft	1218

7	Providing and laying 1:4:8 (1 cement 4 sand and 8 coarse aggregate) cement concrete using graded stone ballast 2 inches (51 mm) and down gauge in foundation including levelling, compacting and curing etc. complete.	13	Cft	21744.25	Rupees Twenty One Thousand Seven Hundred Forty Four and Twenty Five Paisas Only	%Cft	2827
8	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls more than 13-1/2 inches (343 mm) thick including scaffolding, raking out Joints and curing etc. Complete in foundation, basement and plinth (foundation and basement masonry upto 5 feet (1.52 Ru.m.) depth and plinth upto 4 feet (1.2 Ru.m.) height from ground level) .	28	Cft	36129.72	Rupees Thirty Six Thousand One Hundred Twenty Nine and Seventy Two Paisas Only	%Cft	10116
9	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9" to 13-1/2 inches (228 mm to 343 mm) thick including scaffolding, raking out Joints and curing etc. complete in foundation, basement and plinth (foundation and basement masonry upto 5 feet (1.52 Ru.m.) depth and plinth upto 4 feet (1.2 Ru.m.) height from ground level) .	23	Cft	38582.85	Rupees Thirty Eight Thousand Five Hundred Eighty Two and Eighty Five Paisas Only	%Cft	8874
10	Providing and laying 2 inches (51 mm) thick damp proof course with cement concrete 1:2:4 cast in situ using graded screened bajri of 3/4 inch (19 mm) and down gauge including compacting, curing, form work and its removal etc. complete with applying a coat of hot bitumen (maxphalt 80/100 or equivalent) using 35 Lbs. per hundred square feet (1.71 Kg/sm) on damp proof course after complete drying and cleaning the surface .	11	Sft	8526.80	Rupees Eight Thousand Five Hundred Twenty Six and Eighty Paisas Only	%Sft	938
11	Providing and laying double layer of polythene sheet of 500 gauge (0.005 or 0.13 mm thick) under floors for water proofing laid as per specifications and instructions of the Engineer-in-Charge in ground floor.	11	Sft.	1880.63	Rupees One Thousand Eight Hundred Eighty and Sixty Three Paisas Only	%Sft	207
12	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9 to 13-1/2 inches (229 mm to 343 mm) thick including scaffolding, raking, out joints and curing etc. complete in ground floor superstructure .	74	Cft.	41260.97	Rupees Forty One Thousand Two Hundred Sixty and Ninety Seven Paisas Only	%Cft	30533
13	1/2" (13 mm) thick cement plaster 1:4 on walls and columns etc. in basement, plinth, mezzanine and ground floor including making edges, corners, and curing etc., complete .	2328	Sft	4381.84	Rupees Four Thousand Three Hundred Eighty One and Eighty Four Paisas Only	%Sft	102009
14	Painting with (ICI) Dulux plastic emulsion paint VIP of approved shade two coats over and including the cost of one priming coat complete over plastered surface at any height in any floor .	2599	Sft.	6737.38	Rupees Six Thousand Seven Hundred Thirty Seven and Thirty Eight Paisas Only	%Sft	100309

15	Distempering with vinyl distemper (ICI) Dulux Paintex of approved make and shade in two coats over and including the cost of one priming coat of lime wash including sand papering, dusting, and filling the holes, cracks and inequalities, if any, at any height in any floor.	460	Sq. ft.	3401.25	Rupees Three Thousand Four Hundred One and Twenty Five Paisas Only	%Sft	15646
16	Providing and fixing solid core 1st class deodar wood veneered flush door shutter 1-1/2 inches (38 mm) thickness with and including the cost of commercial veneer facing of not less than 1 mm thickness on either side, cross band of standard specification with solid fully laminated core, 2 inches (51 mm) wide best quality deodar wood outer faces alround as commercially produced by standard manufacturers under power driven hydraulic press as approved by Engineer-in-charge including iron fittings etc., complete but excluding the cost of handles and locking arrangement.	39	Sft	2164.85	Rupees Two Thousand One Hundred Sixty Four and Eighty Five Paisas Only	P.Rft	84429
17	Painting wood work with synthetic enamel paint of approved make and shade two coats over and including the cost of one priming coat complete at any height in any floor .	280	Sft	5954.86	Rupees Five Thousand Nine Hundred Fifty Four and Eighty Six Paisas Only	%Sft	16674
18	Providing and fixing fully glazed Silver anodized aluminium Sliding windows as per British standard manufactured by Lucky,Alcop, Krudson, Pakistan cable and A.C.P. (fixing through their approved fabricators), Deluxe model box section 95mm x 30mm and 1.6mm thick including the cost of aluminium netting ,fittings, with all accessories cutting hole etc. and making good damages to walls etc. complete as required in any floor as per direction of engineer-in-charge, but excluding the cost of glass pane.	6	Sft	1717.19	Rupees One Thousand Seven Hundred Seventeen and Nineteen Paisas Only	P.Sft	10303
19	Providing and laying floor of 6mm (approx: 1/4") thick coloured glazed tiles more than 1 square feet upto 2 square feet of master make (Pakistani) first grade in ground floor laid over 1" (25mm) thick cement mortar 1:2 (1 cement and 2 sand) including jointing and washing the tiles with white cement slurry a matching colour (by using pigment in white cement) and curing etc. complete.	80	Sft	42108.61	Rupees Forty Two Thousand One Hundred Eight and Sixty One Paisas Only	%Sft	33687
20	Providing and fixing 1/4"(6mm approx.) thick of Pakistani make first grade coloured glazed tiles 8"x 10" (203mm x 254mm) size in dado and skirting in ground floor over 1/2" (13mm) thick base of cement mortar 1:3 setting of tiles in slurry of grey cement over mortar base including filling the joint with white cement slurry to matching the colour and washing the tile, curing and cleaning etc. complete	252	Sft	26546.93	Rupees Twenty Six Thousand Five Hundred Forty Six and Ninety Three Paisas Only	%Sft	66898
21	Providing and fixing Plaster of Paris tiles size (2' x 2' x 3/4") for falls ceiling l/c Aluminum T and L angle 1" x 1" i.c hanger clips jointing clips and g.I. Wire etc complete as required in any floor.	410	Sft	244.92	Rupees Two Hundred Forty Four and Ninety Two Paisas Only	P.Sft	100417

22	Providing rolled steel Joists and channels including hoisting and fixing in position in cement concrete in ground floor but excluding cost of cement concrete.	88	Kg	280.98	Rupees Two Hundred Eighty and Ninety Eight Paisas Only	P.Kg	24726
23	Providing and fixing Tinted glass panes 5mm thick to M.S. Box pipe / Aluminium doors, windows and ventilators etc including the cost of labour but excluding the cost of M.S. square pipe beading, rubber packing and screw in any floor at any height.	6	Sft	297.02	Rupees Two Hundred Ninety Seven and Zero Two Paisas Only	P.Sft	1782
				Total	601236		

BULIDING NON-SCHEDULE ITEMS

Sr. No.	Item of work	Qty	Rate	Unit	Amount
1	Providing and fixing Floor of wood colour sheets 3/8" inch thick best quality MDF sheets fixed on floor with glue ,screws,and necessary fitting level smooth finish etc complete. etc., in all respect as per directed by the Engineer incharge.	465	378.97	P.Sft	176221
2	Supply and Fixing roller blinds vertical of approved shade quality and design i/c the cost of all accessories etc as per direction of Engineer-in-charge.	100	227.87	P.Sft	22787
				Total	199008


W/S & S/I (SCHEDULE ITEMS)


Sr. No.	Item of work	Qty	Rate	Unit	Amount
1	Providing and fixing bath room accessories of set of 6 pieces consist of one shelf, one towel rod with bracket, one towel ring, one soap dish, one tooth Brush holder with glass, one tissue paper holder one double hook etc complete of approved quality as per direction of Engineer in-charge.	1	11812.50	Each	11813
2	Providing and fixing best quality squatting type white glazed earthenware W.C Pan, Pakistani (of not less than 18 Inches clear opening as measured between flushing rims) complete with and including the cost of 13.6 litre best quality low level plastic flushing cistern with internal fittings complete, P.V.C. flushing pipe suitable for squatting type with extra bends and length with fittings, C.I. trap 4 inches (100mm) dia and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1:2:4	1	12602.50	Each	12603

3	Providing and fixing 25 inches x 18 inches (635 mm x 457 mm) lavatory basin in white glazed earthenware (Pakistani) complete with and including the cost of Brass oxidized bolts kit built into wall 1/2 inch (15 mm) dia. Chrome plated mixer 1-1/4" inches (32mm) rubber plug and chrome plated brass chain, 1-1/4 inches (32 mm) dia brass waste of approved pattern, 1-1/4 inches (32 mm) dia. Malleable iron or C.P. brass traps malleable iron or brass unions and making requisite number of holes in walls plinth and floor for pipe connections and making god in cement concrete 1:2:4 and providing and fixing best available (Pakistani make) white glazed earthenware pedestal..	1	No	18181.25	Rupees Eighteen Thousand One Hundred Eighty One and Twenty Five Paisas Only	Each	18181
4	Providing and fixing 24 inches x 18 inches (610 mm x 457 mm) looking mirror of Imported glass 5 mm thick fixing with CP clamps and screws	6	No	2173.98	Rupees Two Thousand One Hundred Seventy Three and Ninety Eight Paisas Only	Each	13044
5	Providing and fixing China make (Porta or equivalent) best quality colour glazed European style couple set W.C pan i/c the cost of plastic sheet cover and buffers etc. complete and making requisite no. of holes in walls plinth and floor for pipe connection and making in cement concrete 1:2:4 etc. complete.	1	No	47750.00	Rupees Forty Seven Thousand Seven Hundred Fifty Only	Each	47750
Total							103390

W/S & S/I (NON-SCHEDULE ITEMS)

Sr. No.	Item of work	Qty		Rate		Unit	Amount
1	P/F standaing wall shower set complete Master or its equivalent complete i/c the cost of standing shower 03 Nos. t.stop cock, 01-No, 1/2" dia of basin mixture couplin etc. as per direction of the Engineer in charge.	1	Nos	24891.00	Rupees Twenty Four Thousand Eight Hundred Ninety One Only	Each	24891
2	Providing and fixing UPVC Floor Trape 4" dia inlet and 4" dia outlet of the approved self cleaning design making requistire numbers of holes in walls and floor for pipe connection and making good in CC 1:2:4.	3	No	3211.00	Rupees Three Thousand Two Hundred Eleven Only	Each	9633
3	Providing and fixing 6" x 6" size stainless steel floor trap jali fixing in tile flooring as per direction of the Engineer iincharge.	3	Nos	750.00	Rupees Seven Hundred Fifty Only	Each	2250
Total							36864


 Assistant Executive Engineer
 Central Civil Division-I,
 Pak. PWD; Lahore


 Executive Engineer
 Central Civil Division-I,
 Pak. PWD; Lahore