

Notes on Elevation 1

• The entire facade inside and outside wall including damaged structural members to be replaced ro engineer's/ Architect's approval

to manufacture same, no additional time or cost will be entertained

- contractor to measure and record photographic evidence of existing window and door details. Once approval given same to be manufactured with 6 mm clear glass
- The finish colour shall be to Architect's approval
- Treated and dry kiln balao wood or equivalent approved by architect to be used
- General cleaning up to external facade, cleaning, primed and repainted 2 coats finish as appropriate

REFURBISHMENT WORKS AT SSR MEMORIAL MUSEUM SSR STREET PORT-LOUIS

tle

ELEVATION 1 (PROPOSED)

Project Coordinator	R. Canhyee		
Architect/S.Architect	J. Rojoa		
Engineer/S.Engineer	R. Harah		
Electrical/S.Elect.Eng.	S. Boodoo		
Quantity Surveyor	H. Rambhojun		
Technical Officer	R. Ramsurrun		
Tech. Desn. Officer	Y.P. Vythelingum		
Scale: 1 : 50 Date: 02		02.2022	
MINISTRY OF NATIONAL INFRASTRUCTURE & COMMUNITY DEVELOPMENT PHOENIX			Comp. No.
DRG. No. RFW/08			Revision