

**INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL**

| Item No | | Quantity | Rate | Amount |
|------------|--|----------|------|--------|
| | <u>SECTION NO. 1</u> | | | |
| | <u>BILL NO. 1</u> | | | |
| | <u>PRELIMINARIES</u> | | | |
| | <u>BUILDING AGREEMENT AND PRELIMINARIES</u> | | | |
| | The JBCC Series 2000 Edition 4.1 Code 2101 March 2005 Edition prepared by the Joint Building Contracts Committee, shall be the agreement, amended as hereinafter described | | | |
| | The Preliminaries for use with the JBCC Series 2000 Principal Building Agreement (March 2005 Edition) prepared by the Joint Building Contracts Committee, shall be deemed to be incorporated in these bills of quantities | | | |
| | Contractors are referred to the above-mentioned documents for the full intent and meaning of each clause thereof | | | |
| | These clauses are hereinafter referred to by clause number and heading only. Where standard clauses or alternatives are not entirely applicable to this contract such modifications, corrections or supplements as will apply are given under each relevant clause heading and such modifications, corrections or supplements shall take precedence notwithstanding anything contrary contained in the above-mentioned documents | | | |
| | Where any item is not relevant to this specific contract such item is marked N/A, signifying "not applicable" | | | |
| | Notwithstanding anything to the contrary contained in any of the contract documents including the Principal Building Agreement and the Preliminaries, the provision of the "Preliminaries" as hereinafter set forth shall prevail and shall take precedence | | | |
| | Carried Forward | | R | |
| | PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| | | | |
|--|---|------|--|
| Brought Forward | | R | |
| <u>PREAMBLES FOR TRADES</u> | | | |
| <p>The Model Preambles for Trades (1999 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claim arising from brevity of description of items fully described in the said Model Preambles for Trades will be entertained</p> | | | |
| <p>Supplementary preambles to the Model Preambles covering clauses of a general nature, clauses pertaining to specific materials and amendments to clauses in the Model Preambles are incorporated in these bills of quantities to satisfy the requirements of this project</p> | | | |
| <p>The contractor's prices for all items throughout these bills of quantities must take account of and include for all of the obligations, requirements and specifications given in the Model Preambles and in any supplementary preambles</p> | | | |
| <u>GENERAL</u> | | | |
| <p>If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries each item priced is to be allocated to one or more of the three categories "F", "T" or "V" as the case may be below such item, where "F" denotes a fixed amount (amount not to be varied), "T" denotes an amount variable in proportion to time and "V" denotes an amount variable in proportion to value</p> | | | |
| <u>SECTION A - PRINCIPAL BUILDING AGREEMENT</u> | | | |
| <u>Definitions (A1)</u> | | | |
| 1 | <p>Definitions and interpretation (clause 1)</p> <p>F:..... V:..... T:.....</p> | Item | |
| | | | |
| Carried Forward | | R | |
| <p>PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS</p> | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R | |
|---|--|------|--|
| <u>Objective and Preparation (A2 to A14)</u> | | | |
| 2 | Offer acceptance and performance (clause 2) F:..... V:..... T:..... | Item | |
| 3 | Documents (clause 3) F:..... V:..... T:..... | Item | |
| 4 | Design responsibility (clause 4) F:..... V:..... T:..... | Item | |
| 5 | Employer's agents (clause 5) F:..... V:..... T:..... | Item | |
| The principal agent shall: | | | |
| <ul style="list-style-type: none"> - monitor and control progress and scheduling - monitor all contract conditions, and - coordinate the efforts of the employer's agents, the contractor and subcontractors | | | |
| The powers conferred on the principal agent in terms of this clause and/or the exercising of these powers shall not be construed as removing or diminishing any of the obligations of the Contractor in terms of the Principal Building Agreement, whether financial, contractual or otherwise, nor shall the exercising of these powers create any privity of contract as between the Employer or his agents on the one part and the Contractor or subcontractors or suppliers on the other part | | | |
| Carried Forward | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

**INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL**

| Brought Forward | | | R |
|--|---|------|---|
| | The principal agent reserves the right to attend and participate in all contractor/subcontractor's meetings, to invite other employer's agents to attend such meetings at his discretion and to converse and chair any such meetings if the contractor is derelict in his duty in arranging such meetings to the degree of frequency and comprehensiveness dictated in the opinion of the project manager by the circumstances and exigencies of the construction process | | |
| 6 | Site representative (clause 6) F:..... V:..... T:..... | Item | |
| 7 | Compliance with regulations (clause 7) F:..... V:..... T:..... | Item | |
| 8 | Works risk (clause 8) F:..... V:..... T:..... | Item | |
| 9 | Indemnities (clause 9) F:..... V:..... T:..... | Item | |
| 10 | Works insurances (clause 10) F:..... V:..... T:..... | Item | |
| 11 | Liability insurances (clause 11) F:..... V:..... T:..... | Item | |
| 12 | Effecting insurance (clause 12) F:..... V:..... T:..... | Item | |
| Carried Forward | | | R |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R | |
|--|--|------|---|--|
| 13 | NO CLAUSE | N/A | | |
| 14 | Security (clause 14) F:..... V:..... T:..... | Item | | |
| <u>Execution (A15-A23)</u> | | | | |
| 15 | Preparation for and execution of the works (clause 15) F:..... V:..... T:..... | Item | | |
| 16 | Access to the works (clause 16) F:..... V:..... T:..... | Item | | |
| 17 | Contract instructions (clause 17) F:..... V:..... T:..... | Item | | |
| 18 | Setting out of the works (clause 18) F:..... V:..... T:..... The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc exist in order that the necessary arrangements may be made for the rectification of any such encroachments | Item | | |
| 19 | Assignment (clause 19) F:..... V:..... T:..... The contractor shall not cede his rights or delegate his obligations in terms of this agreement unless specifically called for by the employer | Item | | |
| Carried Forward | | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R | |
|---|--|------|--|
| 20 | Nominated subcontractors (clause 20) F:..... V:..... T:..... | Item | |
| 21 | Selected subcontractors (clause 21) F:..... V:..... T:..... Written proof is required from subcontract tenderers at tendering that they can meet the JBCC Selected Subcontract Agreement or other tender agreements and provide security in terms of the agreement. If the above is not provided the tender may not be accepted All amounts allowed under Provisional Amounts are intended to be awarded to Selected Subcontractors | Item | |
| 22 | Employer's Direct Contractors (clause 22) F:..... V:..... T:..... | Item | |
| 23 | Contractor's Domestic Sub-Contractors (Clause 23) F:..... V:..... T:..... | Item | |
| <u>Completion (A24-A30)</u> | | | |
| 24 | Practical completion (clause 24) F:..... V:..... T:..... | Item | |
| 25 | Works completion (clause 25) F:..... V:..... T:..... | Item | |
| Carried Forward | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R | |
|---|--|------|---|--|
| 26 | Final completion (clause 26) F:..... V:..... T:..... | Item | | |
| 27 | Latent defects liability period (clause 27) F:..... V:..... T:..... | Item | | |
| 28 | Sectional completion (clause 28) F:..... V:..... T:..... | Item | | |
| 29 | Revision of date of practical completion (clause 29) F:..... V:..... T:..... The removal and replacement of materials and/or workmanship that do not conform to specification or drawings shall not constitute grounds for an extension of the construction period nor for an adjustment to the contract sum (clause 29.3) | Item | | |
| 30 | Penalty for non-completion (clause 30) F:..... V:..... T:..... | Item | | |
| <u>Payment (A31 - A35)</u> | | | | |
| 31 | Interim payment to the contractor (clause 31) F:..... V:..... T:..... | Item | | |
| 32 | Adjustment to the contract value (clause 32) F:..... V:..... T:..... | Item | | |
| Carried Forward | | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | | |

**INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL**

| Brought Forward | | | R |
|--|---|------|---|
| | Where prices are submitted by the contractor or nominated/selected subcontractors during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing | | |
| 33 | Recovery of expense and loss (clause 33) F:..... V:..... T:..... | Item | |
| 34 | Final account and final payment (clause 34) F:..... V:..... T:..... | Item | |
| | The employer shall not pay any interest on amounts payable to the contractor for one hundred and forty two (142) days after the date of issue of the certificate of practical completion | | |
| | The employer shall, however, pay interest to the contractor at the rate stipulated in clause 34.11 on any amounts payable to the contractor more than one hundred and forty two (142) days after the date of issue of the certificate of practical completion but only for such period as the settlement of the final account is delayed by the non-performance of the principal agent or the employer or his agents. In evaluating non-performance for purposes of this clause a reasonable time shall be allowed to the employer or his agents to respond to any matter brought to his/their attention and which may affect the settlement of the final account | | |
| 35 | Payment to other parties (clause 35) F:..... V:..... T:..... | Item | |
| Carried Forward | | | R |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R |
|--|--|------|
| <u>Cancellation (A36-A39)</u> | | |
| 36 | Cancellation by employer - contractor's default (clause 36) F:..... V:..... T:..... | Item |
| 37 | Cancellation by employer - loss and damage (clause 37) F:..... V:..... T:..... | Item |
| 38 | Cancellation by contractor - employer's default (clause 38) F:..... V:..... T:..... | Item |
| 39 | Cancellation - cessation of the works (clause 39) F:..... V:..... T:..... | Item |
| <u>Dispute (A40)</u> | | |
| 40 | Dispute Settlement (clause 40) F:..... V:..... T:..... | Item |
| <u>Substitute Provisions (A41)</u> | | |
| 41 | State clauses (Clause 41) F:..... V:..... T:..... | Item |
| Information necessary for the completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder | | |
| Carried Forward | | R |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| | | | | |
|----|--|------|---|--|
| | Brought Forward | | R | |
| | <u>THE SCHEDULE</u> | | | |
| | Information necessary for completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder | | | |
| 42 | Pre-tender information (clause 42) | | | |
| | F:..... V:..... T:..... | Item | | |
| | <u>42.1 CONTRACTING AND OTHER PARTIES</u> | | | |
| | 42.1.1 Employer: INDEPENDENT DEVELOPMENT TRUST (IDT) | | | |
| | 42.1.2 Principal Agent: BTKM QUANTITY SURVEYORS | | | |
| | <u>42.2 CONTRACT DETAILS</u> | | | |
| | 42.2.1 Works Description: Construction of sanitation facilities | | | |
| | 42.2.2 Site Description: as per the information on the tender data | | | |
| | 42.2.3 Work or installations by direct contractors: | | | |
| | N/A | | | |
| | 42.2.4 This agreement is for a government contract where there are specific options that are applicable to a State organ only | | | |
| | Yes | | | |
| | Carried Forward | | R | |
| | PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| | |
|---|---|
| | R |
| <p>Brought Forward</p> | |
| <p>42.2.5 Date on which possession of the site is intended to be given:</p> <p>As per the information provided in the Tender Data</p> | |
| <p>42.2.6 Period for the commencement of the works after the contractor takes possession of site:</p> <p>7 DAYS</p> | |
| <p>42.2.7 For the works as a whole. Intended date of practical completion and the penalty per calendar day</p> <p>Intended Date of Practical Completion: <i>As per the information provided in the Tender Data</i></p> <p>Penalty Amount: <i>The penalty per calendar day shall be 0.05 per R100 of the Contract Value (inclusive of value added tax)</i></p> | |
| <p>42.2.8 For the works in sections: Intended date of practical completion and the penalty per calendar day</p> <p>N/A</p> | |
| <p>42.2.9 The law applicable to this agreement shall be that of</p> <p><i>South Africa (country)</i></p> | |
| | |
| <p>Carried Forward</p> | R |
| <p>PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS</p> | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| | | |
|---|---|--|
| Brought Forward | R | |
| <u>42.3 INSURANCES</u> | | |
| 42.3.1 Contract works insurance to be effected by: | | |
| <i>Contractor:</i> | | |
| <i>For the Sum of R Contract Amount + 20.00 %</i> | | |
| <i>With a deductible of - to be determined by the contractor</i> | | |
| 42.3.2 Supplementary insurance is required | | |
| Yes | | |
| 42.3.3 Public liability insurance to be effected by: | | |
| <i>Contractor:</i> | | |
| <i>For the Sum of R 10 000 000-00</i> | | |
| <i>With a deductible of - to be determined by the contractor</i> | | |
| <u>42.4 DOCUMENTS</u> | | |
| 42.4.1 Waivers of contractors lien or right of continuing possession is required | | |
| Yes | | |
| 42.4.2 Number of construction document copies to be supplied to the contractor free of charge: | | |
| 3 Number of | | |
| 42.4.3 Bills of Quantities/Lump sum document schedule of rates drawn up in accordance with: | | |
| "Standard System of Measuring Builders' Work" | | |
| Carried Forward | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| | | | | |
|----|--|------|---|--|
| | Brought Forward | | R | |
| | 42.4.4 On acceptance of the tender the bills of quantities/lump sum document is to be submitted within 5 working days <i>The priced bills of quantities must be handed in with the tender</i> | | | |
| | 42.4.5 JBCC Engineering General Conditions are to be included in the contract documents : <i>No</i> | | | |
| | 42.4.6 The contract value is to be adjusted using escalation adjustment indices <i>No</i> Where JBCC CPAP is to be used <i>Base Month N/A</i> | | | |
| | 42.4.7 Details of changes made to the provision of JBCC standard documentation: Part 1 - Contract Data completed by Employer | | | |
| | <u>SECTION B: PRELIMINARIES</u> | | | |
| | <u>Definitions and interpretation (B1)</u> | | | |
| 43 | Definition and interpretation (B1.1 - B1.4.6) F:..... V:..... T:..... | Item | | |
| | <u>Documents (B2)</u> | | | |
| 44 | Checking of documents (B2.1) F:..... V:..... T:..... | Item | | |
| | Carried Forward | | R | |
| | PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R | |
|---|--|------|--|
| 45 | Provisional bills of quantities (B2.2) F:..... V:..... T:..... | N/A | |
| 46 | Availability of construction documentation (B2.3) F:..... V:..... T:..... | Item | |
| 47 | Interests of agents (B2.4) F:..... V:..... T:..... | Item | |
| 48 | Priced documents (B2.5) F:..... V:..... T:..... | Item | |
| 49 | Tender submission (B2.6) F:..... V:..... T:..... | Item | |
| 50 | Defined works area (B3.1) F:..... V:..... T:..... | Item | |
| <u>The site (B3)</u> | | | |
| 51 | Geotechnical investigation (B3.2) F:..... V:..... T:..... | Item | |
| 52 | Inspection of the site (B3.3) F:..... V:..... T:..... | Item | |
| Carried Forward | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R | |
|---|--------------------------------|------|--|
| Existing premises occupied (B3.4) | | | |
| F:..... V:..... T:..... | | | |
| Specific requirements: | | | |
| The contractor shall also comply with the additional requirements with regard to the Coronavirus pandemic in terms of all Covid-19 legislation, regulations and guidelines. | | | |
| Previous work - dimensional accuracy (B3.5) | | | |
| F:..... V:..... T:..... | | | |
| Previous work - defects (B3.6) | | | |
| F:..... V:..... T:..... | | | |
| 53 | Services - known (B3.7) | | |
| | F:..... V:..... T:..... | Item | |
| 54 | Services - unknown (B3.8) | | |
| | F:..... V:..... T:..... | Item | |
| 55 | Protection of trees etc (B3.9) | | |
| | F:..... V:..... T:..... | Item | |
| 56 | Articles of value (B3.10) | | |
| | F:..... V:..... T:..... | Item | |
| Carried Forward | | R | |
| PRELIMINARIES | | | |
| Ps & Gs | | | |
| BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R | |
|---|---|------|--|
| <u>Management of contract (B4)</u> | | | |
| 57 | Inspection of adjoining properties etc (B3.11) F:..... V:..... T:..... | Item | |
| 58 | Management of the works (B4.1) F:..... V:..... T:..... | Item | |
| 59 | Programme for the works (B4.2) F:..... V:..... T:..... | Item | |
| 60 | Progress meetings (B4.3) F:..... V:..... T:..... | Item | |
| 61 | Technical meetings (B4.4) F:..... V:..... T:..... | Item | |
| 62 | Labour and Plant records (B4.5) F:..... V:..... T:..... | Item | |
| <u>Samples, Shop Drawings and Manufacturer's Instructions (B5)</u> | | | |
| 63 | Samples of materials (B5.1) F:..... V:..... T:..... | Item | |
| 64 | Workmanship samples (B5.2) F:..... V:..... T:..... | Item | |
| Carried Forward | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R | |
|---|---|------|---|--|
| 65 | Shop drawings (B5.3) F:..... V:..... T:..... | Item | | |
| 66 | Compliance with Manufacturer's Instructions (B5.4) F:..... V:..... T:..... | Item | | |
| <u>Temporary works and plant (B6)</u> | | | | |
| 67 | Deposits and fees (B6.1) F:..... V:..... T:..... | Item | | |
| 68 | Enclosure of the works (B6.2) F:..... V:..... T:..... | Item | | |
| 69 | Advertising (B6.3) F:..... V:..... T:..... | Item | | |
| 70 | Plant, equipment, sheds and offices (B6.4) F:..... V:..... T:..... | Item | | |
| 71 | Main notice board (B6.5) F:..... V:..... T:..... | Item | | |
| 72 | Subcontractors' notice board (B6.6) F:..... V:..... T:..... | N/A | | |
| Carried Forward | | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| | | | | |
|----|--|------|---|--|
| | Brought Forward | | R | |
| | <u>Temporary services (B7)</u> | | | |
| 73 | Location (B7.1) F:..... V:..... T:..... | Item | | |
| 74 | Water (B7.2) Option [A] shall apply F:..... V:..... T:..... | Item | | |
| 75 | Electricity (B7.3) Option [A] shall apply F:..... V:..... T:..... | Item | | |
| 76 | Telecommunication facilities (B7.4) F:..... V:..... T:..... | Item | | |
| 77 | Ablution facilities (B7.5) Option [A] shall apply F:..... V:..... T:..... | Item | | |
| | <u>Prime cost amounts (B8)</u> | | | |
| 78 | Responsibility for prime cost amounts (B8.1) F:..... V:..... T:..... | Item | | |
| | Carried Forward | | R | |
| | PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| | | | | |
|----|---|------|---|--|
| | Brought Forward | | R | |
| | <u>Attendance on N/S Subcontractors (B9)</u> | | | |
| 79 | General attendance (B9.1) F:..... V:..... T:..... | Item | | |
| 80 | Special attendance (B9.2) F:..... V:..... T:..... | Item | | |
| 81 | Commissioning - Fuel, water and power (B9.3) F:..... V:..... T:..... | Item | | |
| | <u>Financial aspects (B10)</u> | | | |
| | Statutory taxes, duties and levies (B10.1) F:..... V:..... T:..... | Item | | |
| 82 | Payment of preliminaries (B10.2) Option [B] shall apply F:..... V:..... T:..... | Item | | |
| 83 | Adjustment of preliminaries (B10.3) Option [A] shall apply F:..... V:..... T:..... | Item | | |
| 84 | Payment certificate cash flow (B10.4) F:..... V:..... T:..... | Item | | |
| | Carried Forward | | R | |
| | PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R | |
|--|--|------|--|
| <u>General (B11)</u> | | | |
| 85 | Protection of works (B11.1) F:..... V:..... T:..... | Item | |
| 86 | Protection/isolation of existing/sectionally occupied works (B11.2) F:..... V:..... T:..... | Item | |
| 87 | Security of the Works (B11.3) F:..... V:..... T:..... | Item | |
| 88 | Notice before covering work (B11.4) F:..... V:..... T:..... | Item | |
| 89 | Disturbance (B11.5) F:..... V:..... T:..... | Item | |
| 90 | Environmental Disturbance (B11.6) F:..... V:..... T:..... | Item | |
| 91 | Works cleaning and clearing (B11.7) F:..... V:..... T:..... | Item | |
| 92 | Vermin (B11.8) F:..... V:..... T:..... | Item | |
| Carried Forward | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R | |
|---|---|------|--|
| 93 | Overhand work (B11.9) F:..... V:..... T:..... | Item | |
| 94 | Instruction manuals and guarantees (B11.10) F:..... V:..... T:..... | Item | |
| 95 | As built information (B11.11) F:..... V:..... T:..... | Item | |
| 96 | Tenant Installations (B11.12) F:..... V:..... T:..... | Item | |
| <u>Schedule of variables (B12)</u> | | | |
| 97 | Pre-tender information (B12.1) F:..... V:..... T:..... | Item | |
| 12.1.1 | Provisional bills of quantities (B2.2) The quantities are provisional: No | | |
| 12.1.2 | Availability of construction documentation (B2.3) Construction documentation is not complete No | | |
| 12.1.3 | Interest of agents (B2.4) | | |
| 12.1.4 | Defined works area (B3.1) | | |
| Carried Forward | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

**INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL**

| | | |
|---|---|--|
| Brought Forward | R | |
| <p>12.1.5 Geotechnical investigation (B3.2)</p> <p>N/A</p> | | |
| 12.1.6 Existing premises occupied (B3.4) | | |
| 12.1.7 Previous work - dimensional accuracy (B3.4) | | |
| 12.1.8 Previous work - defects (B3.5) | | |
| 12.1.9 Services - known (B3.7) | | |
| <p>12.1.10 Protection of trees (B3.9)</p> <p>All trees should be protected and only on instruction of the Principal Agent may any trees be removed</p> | | |
| <p>12.1.11 Inspection of adjoining properties (B3.11)</p> | | |
| 12.1.12 Enclosure of the works (B6.2) | | |
| <p>12.1.13 Offices (B6.4.3)</p> <p>Specific requirements:</p> <p>The contractor shall provide, maintain and remove, on completion of the works, an office for the exclusive use of the principal agent, minimum size 4 x 3 x 3m high internally, suitably insulated and ventilated, provided with electric lighting and fitted with boarded floor, desk, chair, drawing stool, drawing board and lock-up drawers for drawings. The office shall be kept clean and fit for use at all times.</p> | | |
| Carried Forward | R | |
| <p>PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS</p> | | |

**INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL**

| | | | |
|---|--|---|--|
| Brought Forward | | R | |
| 12.1.14 Main notice board (B6.5) YES | | | |
| 12.1.15 Subcontractors notice board (B6.6) A notice board is required Yes | | | |
| 12.1.16 Water (B7.2) Alternative Selected: A | | | |
| 12.1.17 Electricity (B7.3) Alternative selected: A | | | |
| 12.1.18 Telecommunications (B7.4) | | | |
| 12.1.19 Ablution facilities (B7.5) Alternative selected: A | | | |
| 12.1.20 Protection of existing/sectionally occupied works (B11.2) | | | |
| 12.1.21 Special attendance (B9.2) Subcontractor (1) details: N/A | | | |
| 12.1.22 Protection of the works (B11.1) N/A | | | |
| 12.1.23 Disturbance (B11.5) N/A | | | |
| 12.1.24 Environmental Disturbance (B11.6) N/A | | | |
| Carried Forward | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

| | | | |
|---|--|------|--|
| | | R | |
| Brought Forward | | | |
| <u>Post tender information (B12.2)</u> | | | |
| 12.2.1 | Payment of preliminaries Alternative selected: B | | |
| 12.2.2 | Adjustment of preliminaries Alternative selected: A | | |
| 12.2.3 | Additional agreed preliminaries items N/A | | |
| <u>SECTION C: SPECIFIC PRELIMINARIES</u> | | | |
| Any special items to meet the particular circumstances of a specific project are embodied in this section. Where required for an aspect of the works to be executed according to a design by a consulting engineer, a recital of the headings to the individual clauses of the JBCC Engineering General Conditions are included | | | |
| 98 | Site instructions Instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the contractor F:..... V:..... T:..... | Item | |
| 99 | Black economic empowerment and training F:..... V:..... T:..... | Item | |
| 100 | Proprietary branded products F:..... V:..... T:..... | Item | |
| | | R | |
| Carried Forward | | | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| | | | | |
|-----|--|------|---|--|
| | Brought Forward | | R | |
| 101 | Testing of flat roof waterproofing for watertightness Flat roof waterproof areas shall be prepared with small sand dykes around them of a size and enclosing an area approved by the principal agent, flooded with water and kept "ponded" for at least 36 hours as a test to ensure the watertightness of the waterproofing and before any further construction work is carried out above the waterproofing F:..... V:..... T:..... The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturers' instructions after consultation with the manufacturer's authorised representative | Item | | |
| 102 | Contract instructions F:..... V:..... T:..... Contract instructions issued on site are to be recorded in triplicate in a contract instruction book which is to be supplied and maintained on site by the contractor | Item | | |
| 103 | Labour record F:..... V:..... T:..... At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and descriptions of tradesmen and labourers employed by him and all subcontractors on the works each day of that week | Item | | |
| 104 | Plant record F:..... V:..... T:..... | Item | | |
| | Carried Forward | | R | |
| | PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| | | | | |
|-----|---|------|---|--|
| | Brought Forward | | R | |
| | At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools used on the works each day of that week | | | |
| 105 | Guarantees | | | |
| | F:..... V:..... T:..... | Item | | |
| | Where guarantees are called for, the contractor shall obtain a written guarantee, addressed to the employer, from the firm supplying the materials and/or doing the work and shall deliver same to the principal agent on the certified completion of the contract. The guarantee shall state that workmanship, materials and installation are guaranteed for a specified period from the date of certified completion of the contract, and that any defects that may arise during the specified period shall be made good at the expense of the firm supplying the materials and/or doing the work, upon written notice from the principal agent to do so. This guarantee will not be enforced if the work is damaged by defects in the construction of the building in which case the responsibility for replacement shall rest entirely with the contractor. The principal agent shall be the sole judge of the cause responsible for defects in the work and his decision shall be final and binding in terms of clause 40.2 of the agreement | | | |
| 106 | Overtime | | | |
| | F:..... V:..... T:..... | Item | | |
| | Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised, in writing, prior to execution thereof, that costs for such overtime are to be borne by the employer | | | |
| | Carried Forward | | R | |
| | PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R | |
|---|--|------|--|
| 107 | Co-operation of contractor for cost management F:..... V:..... T:..... It is specifically agreed that the contractor accepts the obligation of assisting the professional consultants in implementing proper cost management. The contractor will be advised by the principal agent of all cost management procedures which will be implemented to ensure that the final building cost does not exceed the budget. The quantity surveyor undertakes to make available to the contractor all budgetary allowances and cost assessments/reports to enable the proper procedures to be implemented and the contractor will attend all cost plan review and cost management meetings. The contractor undertakes to extend these procedures in regard to all subcontractors | Item | |
| 108 | Occupational Health and Safety Specification F:..... V:..... T:..... | Item | |
| Carried Forward | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

**INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL**

| | | | |
|--|--|---|--|
| <p style="text-align: center;">Brought Forward</p> <p>The contractor shall comply with all the requirements set out in the Construction Regulations, 2003 issued under the Occupational Health and Safety Act, 1993 (Act No 85 of 1993)</p> <p>It is required of the contractor to thoroughly study the Health and Safety Specification that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document.</p> <p>The contractor must take note that compliance with the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment.</p> <p>Provision for pricing of the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is made under this clause, as well as the clauses that follow hereafter and it is explicitly pointed out that all requirements of the aforementioned are deemed to be priced under these clauses and no additional claims in this regard shall be entertained.</p> <p>The contractor shall also comply with the additional requirements with regard to the Coronavirus pandemic in terms of all Covid-19 legislation, regulations and guidelines. It is explicitly pointed out that all requirements of the aforementioned are deemed to be priced under this clause and the specific related clauses hereafter and no additional claims in this regard shall be entertained.</p> | | R | |
| <p style="text-align: center;">Carried Forward</p> <p>PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS</p> | | R | |

**INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL**

| Brought Forward | | | R |
|--|--|------|---|
| 109 | Occupational Health and Safety Specification F:..... V:..... T:..... Preparation of contractor's site specific health and safety plan, including compliance with Covid-19 legislation, regulations and guidelines | Item | |
| 110 | Occupational Health and Safety Specification F:..... V:..... T:..... Principal contractor's initial obligations in respect of the Health and Safety Act, Construction Regulations and Covid-19 regulations, etc | Item | |
| 111 | Occupational Health and Safety Specification F:..... V:..... T:..... Principal contractor's time related obligations in respect of the Health and Safety Act, Construction Regulations and Covid-19 regulations, etc | Item | |
| 112 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of reflective vests | Item | |
| 113 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of hard hats | Item | |
| Carried Forward | | | R |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R | |
|---|---|------|--|
| 114 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of protective footwear | Item | |
| 115 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of earplugs | Item | |
| 116 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of dust masks | Item | |
| 117 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of gloves | Item | |
| 118 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... Provision of high visibility overalls to SARTSM Chapter 13 Level 3 | Item | |
| Carried Forward | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R | |
|--|---|------|--|
| 119 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Provision of SANS approved ear defenders | | |
| 120 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Provision of face masks (Covid -19) | | |
| 121 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Provision of face shields (Covid -19) | | |
| 122 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Provision of gloves (Covid -19) | | |
| 123 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Provision of hand sanitiser (min 70% alchohol), foot press stands and paper towels (Covid -19) | | |
| 124 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| Carried Forward | | R | |
| PRELIMINARIES Ps & Gs BTM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R | |
|---|--|------|--|
| | Provision of covered refuse bins and refuse bags and waste (including hazardous) management (Covid -19) | | |
| 125 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Provision of digital infrared non-contact body thermometer (Covid -19, minimum of two per site entrance) | | |
| 126 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Provision of perspex screens for office staff (Covid -19, minimum size 600 x 500mm) | | |
| 127 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Provision of signage, including Covid -19 related signage | | |
| 128 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Provision of full time construction health and safety officer (SACPCMP Registered) | | |
| 129 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| Carried Forward | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R | |
|---|---|------|--|
| | Medical certificates and medical surveillance including initial (baseline) medical examinations, periodic examinations, and exit examinations | | |
| 130 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Medical screenings, examinations, etc in terms of Covid-19 regulations | | |
| 131 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Induction training, including Covid-19 training | | |
| 132 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Provision of first aid boxes to GSR requirements | | |
| 133 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Noise monitoring including establishment of noise zones (plant), audiograms (personnel), etc | | |
| 134 | Provision of personal protective equipment (PPE) F:..... V:..... T:..... | Item | |
| | Submission of health and safety file | | |
| Carried Forward | | R | |
| PRELIMINARIES Ps & Gs BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | R | |
|--------------------------|---|------|--|
| 135 | <p>HIV/AIDS Awareness</p> <p>F:..... V:..... T:.....</p> <p>It is required of the contractor to thoroughly study the HIV/AIDS Specification (PW 1544) of the Department that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document. Provision for pricing of HIV/AIDS awareness is made under items C11.1 to C11.5 hereafter and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder, as the said items represent the only method of measurement and no additional items or extras to the contract in this regard shall be entertained.</p> <p>The contractor must take note that compliance with the HIV/AIDS Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A 31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment.</p> <p><u>SUMMARY OF CATEGORIES</u></p> <p>Category : Fixed R.....</p> <p>Category : Value R.....</p> <p>Category : Time R.....</p> | Item | |
| Carried to Final Summary | | R | |
| PRELIMINARIES | | | |
| Ps & Gs | | | |
| BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 2</u> | | | |
| | <u>BILL NO. 1</u> | | | |
| | <u>ALTERATIONS</u> | | | |
| | <u>Supplementary Preambles:</u> | | | |
| | <u>View site</u> | | | |
| | Before submitting his tender the contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained. | | | |
| | <u>Explosives</u> | | | |
| | No explosives whatsoever may be used for demolition. | | | |
| | <u>General</u> | | | |
| | The contractor shall carry out the whole of the works with as little mess and noise as possible and with a minimum of disturbance to adjoining premises and their tenants. He shall provide proper protection and provide, erect and remove when directed, any temporary tarpaulins that may be necessary during the progress of the works, all to the satisfaction of the principal agent. | | | |
| | Water supply pipes and other piping that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings, to the satisfaction of the principal agent. | | | |
| | Doors, fanlights, fittings, frames, linings, etc which are to be re-used shall be thoroughly overhauled before refixing including taking off, easing and rehanging, | | | |
| | Carried Forward | | R | |
| | ALTERATIONS DEMOLITIONS & REFURBISHMENT BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|---|---|----|----|
| <p>cramping up, re-wedging as required and making good cramps, dowels, etc, and easing, oiling, adjusting and repairing ironmongery as necessary, replacing any glass damaged in removal or subsequently and stopping up all nail and screw holes with tinted plastic wood to match timber, unless otherwise described. Re-painting or re-varnishing is given separately.</p> <p>Prices for taking out of doors, windows, etc shall include for removal of all beads, architraves, ironmongery, etc.</p> <p>Prices for taking out and removing doors and frames shall include for removing door stops, cabin hooks, etc and making good floor and wall finishes to match existing.</p> <p>With regard to building up of openings in existing walls, cement screeds and pavings, granolithic, tops of walls, etc, shall be levelled and prepared for raising of brickwork.</p> <p>Making good of finishes shall include making good of the brick and concrete surfaces onto which the new finishes are applied, where necessary.</p> <p>The contractor will be required to take all dimensions affecting the existing buildings on the site and he will be held solely responsible for the accuracy of all such dimensions where used in the manufacture of new items (doors, windows, fittings, etc).</p> | | | |
| <u>DEMOLITIONS OF EXISTING STRUCTURES</u> | | | |
| 1 | Demolitions of existing pit toilet structures including foundations and surface beds, doors, windows and door frames, ironmongery and plumbing fittings complete. All pits are to be filled and compacted according to the Engineer's specification. | No | 14 |
| 2 | Carefully demolish existing ground slab (Max. strength and size, 25MPa and 15m ² respectively) with mesh reinforcement and remove Enviro Loo Industrial 1040 Top Unit, Drying Plate and door frames to be used elsewhere. All pits are to be filled and compacted according to the Engineer's specification. | No | 4 |
| Carried Forward | | | R |
| <p>ALTERATIONS DEMOLITIONS & REFURBISHMENT BTKM QUANTITY SURVEYORS</p> | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|--|---|------|----|
| 3 | Demolitions of existing concrete aprons around enviro loo toilet blocks | m2 | 18 |
| REMOVAL OF EXISTING WORK | | | |
| <u>Taking out and removing doors, etc including removing all ironmongery and making good frames and preparing frames to receive new doors (new doors and ironmongery elsewhere):</u> | | | |
| 4 | Timber single door 813 x 2032mm high. | No | 2 |
| PREPARATORY WORK TO EXISTING SURFACES | | | |
| 5 | Hacking faces of existing face brickwork to receive plaster | m2 | 42 |
| PREPARATORY WORK, MAKING GOOD, ETC TO EXISTING | | | |
| 6 | Remedial work to the existing surface bed/concrete slab in accordance with the Engineer's detail for ONE ENVIRO LOO BLOCK (refer to drawing C-200) | Item | |
| 7 | <u>Clean surfaces with high pressure water jet and approved chemicals to remove marks, add hoop iron wall ties as specified by the Architect and apply two coats of bitumen emulsion waterproof coating to hacked brick walls</u> | m2 | 42 |
| 8 | Examining IBR steel roof coverings, including ridge cappings and securing loose roofing screws, replacing missing or defective screws and/or washers with 8 x 120mm galvanised steel drive screws and 'Everseal' combination galvanised cup and PVC washers, making good bolt holes with approved sealant to render watertight, and sealing all overlapping of sheeting with approved sealant. | m2 | 18 |
| 9 | Installation of missing hurricane clips to the roof rafters including replacement of nails and installation of bolts and nuts where directed by the Architect | m2 | 18 |
| Carried Forward | | | R |
| ALTERATIONS DEMOLITIONS & REFURBISHMENT BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R | |
|---|---|----|----|--|
| 10 | Replace damaged, cracked, loose or untidy putty to existing glazing | m2 | 4 | |
| <u>CLEANING FLOORS</u> | | | | |
| 11 | Clean up all enviro loo blocks internal floors | m2 | 4 | |
| <u>CONCRETE, FORMWORK AND REINFORCEMENT</u> | | | | |
| <u>Supplementary Preambles:</u> | | | | |
| For preambles see "Specifications of materials and methods to be used - PW 371" | | | | |
| <u>UNREINFORCED CONCRETE, ETC</u> | | | | |
| <u>25Mpa/19mm Concrete</u> | | | | |
| 12 | 2Aprons cast in panels | m3 | 6 | |
| 13 | Ramp | m3 | 2 | |
| 14 | Thickening down apron on edge 110mm deep x 200mm wide | m | 32 | |
| <u>CONCRETE SUNDRIES</u> | | | | |
| <u>Finishing top surfaces of concrete smooth with a wood float</u> | | | | |
| 15 | Aprons and pavings to falls | m2 | 36 | |
| <u>TEST CUBES</u> | | | | |
| 16 | Allow for preparing a set of three test cubes each size 150x150x150mm, sending them to an approved testing laboratory for testing and paying all charges in connection therewith. | No | 2 | |
| Carried Forward | | | R | |
| ALTERATIONS DEMOLITIONS & REFURBISHMENT BTKM QUANTITY SURVEYORS | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|--|--|----|----|
| <u>FORMWORK</u> | | | |
| <u>Rough formwork to sides:</u> | | | |
| 17 | Edges, risers, ends and reveals not exceeding 300mm high or wide | m | 32 |
| <u>ROOF COVERINGS</u> | | | |
| <u>Supplementary Preambles:</u> | | | |
| For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| NOTE : Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No. 124 for CPAP formula purposes | | | |
| <u>PROFIED METAL SHEETING AND ACCESSORIES</u> | | | |
| <u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u> | | | |
| 18 | Roof covering with pitch not exceeding 25 degrees | m2 | 19 |
| <u>Sundries</u> | | | |
| 19 | 12" Thermal resistance sisalation laid on purlins | m2 | 19 |
| <u>RAINWATER DISPOSAL</u> | | | |
| <u>Aluzink seamless metal gutters:</u> | | | |
| 20 | 100 x 100 x 0.6mm Standard rainwater gutters fixed with gutters brackets | m | 4 |
| 21 | 75 x 100 x 0.6mm Thick galvanised rainwater downpipes fixed to wall | m | 2 |
| 22 | Extra over rainwater pipe for eaves offset | No | 2 |
| Carried Forward | | | R |
| ALTERATIONS DEMOLITIONS & REFURBISHMENT BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| | Brought Forward | | | R | |
|--|---|----|----|---|--|
| 23 | Extra over for closed ends | No | 2 | | |
| 24 | Ditto ,for shoe | No | 2 | | |
| <u>CARPENTRY AND JOINERY</u> | | | | | |
| <u>Supplementary Preambles:</u> | | | | | |
| <u>Joinery:</u> | | | | | |
| <u>Descriptions of hardwood joinery shall be deemed to include punching nail heads and filling with matching wood filler and sinking and pelleting heads and nuts of bolts.</u> | | | | | |
| <u>Fixing:</u> | | | | | |
| <u>Items described as nailed shall be deemed to be fixed with hardened steel nails or shot pins to brickwork or concrete.</u> | | | | | |
| <u>Items described as plugged shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres.</u> | | | | | |
| <u>ROOFS, ETC.</u> | | | | | |
| <u>Sawn softwood</u> | | | | | |
| 25 | 38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m | m | 50 | | |
| 26 | 50 x 76mm Purlins in lengths exceeding 3,9m and not exceeding 6,6m | m | 65 | | |
| 27 | 76 x 38mm Wall plates | m | 8 | | |
| <u>Sundries</u> | | | | | |
| 28 | Two coats creosote on sawn timbers | m2 | 48 | | |
| Carried Forward | | | | R | |
| ALTERATIONS DEMOLITIONS & REFURBISHMENT BTKM QUANTITY SURVEYORS | | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|---|---|----|----|
| 29 | 6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together | No | 26 |
| 30 | Hurricane clips | No | 50 |
| <u>EAVES, VERGES, ETC.</u> | | | |
| <u>Pressed fibre-cement</u> | | | |
| 31 | 15 x 230mm Fascias and barge boards including galvanised steel H-profile jointing strips | m | 30 |
| <u>DOORS, ETC</u> | | | |
| <u>Wrought meranti framed doors:</u> | | | |
| 32 | 44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard (D1) | No | 4 |
| 33 | 44mm Purpose made Framed batten door 813 x 1882mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed (door raised by 120mm from bottom) (D2) | No | 4 |
| <u>IRONMONGERY</u> | | | |
| <u>Supplementary Preambles:</u> | | | |
| <u>Finishes to ironmongery:</u> | | | |
| <u>Where applicable finishes to ironmongery are indicated by suffixes in accordance with the following list: BS Satin bronze lacquered : CH Chromium plated : SC Satin chromium plated : SE Silver enamelled : GE Grey enamelled : AS Anodised silver : AB Anodised bronze : AG Anodised gold : ABL Anodised black : PB Polished brass : PL Polished and lacquered : PT Epoxy coated.</u> | | | |
| Carried Forward | | | R |
| ALTERATIONS DEMOLITIONS & REFURBISHMENT BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R | |
|--|--|----|----|--|
| Descriptions: | | | | |
| <u>Descriptions of ironmongery shall be deemed to include for fixing to wood, aluminium and steel.</u> | | | | |
| <u>CATCHES, CABIN, HOOKS, ETC</u> | | | | |
| <u>Approved</u> | | | | |
| 34 | 150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged | No | 8 | |
| <u>LOCKS, ETC</u> | | | | |
| <u>Approved</u> | | | | |
| 35 | Three lever mortice lockset | No | 4 | |
| 36 | Two lever mortice lockset | No | 4 | |
| <u>HANDLES</u> | | | | |
| <u>Aluminium Pull Handle</u> | | | | |
| 37 | Set of two, 300mm pull handles fixed back to back on doors | No | 4 | |
| <u>DOORSTOPS</u> | | | | |
| <u>Approved</u> | | | | |
| 38 | 38mm Diameter rubber door stop plugged | No | 12 | |
| <u>LETTERS, NAMEPLATES, ETC.</u> | | | | |
| <u>"Union" or similar approved</u> | | | | |
| 39 | 75 x 150mm Natural anodised aluminium plate with male or female symbol | No | 4 | |
| Carried Forward | | | R | |
| ALTERATIONS DEMOLITIONS & REFURBISHMENT BTKM QUANTITY SURVEYORS | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|---|---|----|---|
| | <u>"Vaal Paragon" or similar approved</u> | | |
| 40 | 32mm Type 9 back grab rail 800mm long plugged | No | 1 |
| 41 | 32mm Type 8 side grab rail 900mm girth plugged | No | 1 |
| <u>BATHROOM FITTINGS</u> | | | |
| | <u>"Kimberley-Clark" or Simlilar</u> | | |
| 42 | "Kimberly Clark" SQ2 code 405607B white lockable toilet roll holder | No | 8 |
| | <u>Stainless steel</u> | | |
| 43 | Stainless steel mirror size 350 x 400m plugged to wall with chrome plated screws. | No | 1 |
| | <u>Sundries</u> | | |
| 44 | Female SHE BIN plugged to walls including purpose-made steel protective cage | No | 3 |
| <u>METALWORK</u> | | | |
| <u>Supplementary Preambles:</u> | | | |
| For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| <u>WELDED SCREENS, GATES, ETC</u> | | | |
| | <u>Steel gates and frames</u> | | |
| 45 | Purpose made square hallow section mild steel security gate, size 813 x 2032mm High | No | 4 |
| <u>PLASTERING</u> | | | |
| <u>CEMENT SCREEDS TO CONCRETE</u> | | | |
| Carried Forward | | | R |
| ALTERATIONS DEMOLITIONS & REFURBISHMENT BTKM QUANTITY SURVEYORS | | | |

| | | | |
|----|--|----|---|
| | Brought Forward | | R |
| | Screeds to steel trowelled, on concrete: | | |
| 46 | 30mm thick on floors m2 | 32 | |
| | <u>INTERNAL PLASTER</u> | | |
| | Cement plaster steel trowelled on brickwork: | | |
| 47 | On walls m2 | 42 | |
| | <u>FLOOR AND WALLS SEALERS</u> | | |
| | Minimum two coats approved epoxy coat: | | |
| 48 | On screed m2 | 32 | |
| 49 | On internal textured plaster walls and floors in pit m2 | 60 | |
| | <u>PLUMBING AND DRAINAGE</u> | | |
| | <u>CLEANING, SERVICING, ETC OF EXISTING SANITARY FITTINGS, ETC</u> | | |
| | Cleaning down, removing dirt, grime, marks, etc with approved chemical solution and disinfectant (external and internal surfaces): | | |
| 50 | Enviroloo, including emptying tank. No | 8 | |
| | <u>NEW SANITARY FITTINGS</u> | | |
| | White glazed fireclay or vitreous china coupling with SABS specification 497 in | | |
| 51 | "Vaal hibiscus" wash hand basin bolted to wall including all fittings and necessary pipework No | 1 | |
| | <u>FITTINGS</u> | | |
| 52 | Elbow taps No | 1 | |
| | <u>ENVIRO LOO COMPONENTS</u> | | |
| | | | |
| | Carried Forward | | R |
| | ALTERATIONS DEMOLITIONS & REFURBISHMENT BTKM QUANTITY SURVEYORS | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|--|--|----|---|
| <u>Replace and install missing enviro loo components according to manufacturer's specification:</u> | | | |
| 53 | Toilet seat, lid & sticker Standard | No | 4 |
| 54 | Ceramic bowl - standard | No | 4 |
| 55 | Wall sign | No | 8 |
| 56 | Drying box | No | 8 |
| 57 | Vent pipe 2,800 mm including bracket, windmaster polyprop, top and bottom sections | No | 4 |
| <u>GLAZING</u> | | | |
| <u>GLAZING TO STEEL WITH PUTTY</u> | | | |
| <u>6,38mm Normal strength obscure laminated safety glass:</u> | | | |
| 58 | Panes exceeding 0,1m ² and not exceeding 0,5m ² . | m2 | 3 |
| <u>PAINTWORK</u> | | | |
| <u>Supplementary Preambles:</u> | | | |
| <u>General:</u> | | | |
| <u>All work to be executed in strict accordance with the specifications of the paint manufacturer.</u> | | | |
| <u>Primers and first coats may be thinned in accordance with the paint specifications of the paint manufacturer to aid the absorption of the paint.</u> | | | |
| <u>All surfaces must be sound, clean and have a moisture content of less than 8% for walls generally and 3% for slabs/screeds etc.</u> | | | |
| Carried Forward | | | R |
| ALTERATIONS DEMOLITIONS & REFURBISHMENT BTKM QUANTITY SURVEYORS | | | |

| | |
|---|-------------------------------------|
| <p style="text-align: right;">Brought Forward</p> <p><u>PREPARATORY WORK TO PREVIOUSLY PAINTED SURFACES</u></p> <p><u>Previously painted plastered surfaces:</u></p> <p><u>Surfaces shall be thoroughly sanded, washed down (high pressure cleaning to external surfaces), scrubbed with sugar soap to remove dirt and other contaminants, rinsed and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and edges feathered. Areas containing algae shall be treated with sodium hypochlorite solution (household bleach) thinned 1 part bleach to 2 parts water. Cracks shall be opened, filled with 'Polycell Mendall 90' or equal and approved or 'Polycell Polyfilla' or equal and approved exterior filler, and sanded smooth. Bridge repaired areas with crack bridging compound (PWC 520). In the case of previously limewashed surfaces, completely remove all limewash if possible or at least wire brush and scrape down to achieve a 'grey state' exposure of the substrate and apply filler as indicated.</u></p> <p><u>Previously painted or unpainted granolithic surfaces:</u></p> <p><u>Surfaces shall be thoroughly sanded, washed down, scrubbed with sugar soap powder solution to remove dirt and other contaminants, rinsed and allowed to dry completely before any paint is applied.</u></p> <p><u>Previously painted galvanised metal surfaces:</u></p> <p><u>Surfaces shall be washed with sugar soap, rinsed with water, cleaned down to remove dirt and other contaminants and sanded lightly to provide key for subsequent coats. Blistered or peeling paint shall be completely removed down to bare metal and edges feathered. Any rust encountered shall be removed and bare metal areas cleaned with galvanised iron cleaner and spot primed with galvogrip metal primer.</u></p> | <p style="text-align: right;">R</p> |
| <p style="text-align: right;">Carried Forward</p> <p>ALTERATIONS DEMOLITIONS & REFURBISHMENT BTKM QUANTITY SURVEYORS</p> | <p style="text-align: right;">R</p> |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|---|---------------------|----|----|
| <u>Previously painted wood surfaces:</u> | | | |
| <u>Surfaces shall be scrubbed with sugar soap to remove dirt and other contaminants, rinsed with water, thoroughly sanded and cleaned down. Blistered or peeling paint shall be completely removed and edges feathered. Cracks and crevices shall be primed, filled with wood filler and sanded smooth. In the case of previously varnished surfaces, all existing varnish must be thoroughly sanded off before new coats are applied.</u> | | | |
| <u>PAINTWORK TO NEW WORK</u> | | | |
| <u>ON FLOATED PLASTER SURFACES</u> | | | |
| <u>Prepare surfaces, spot prime with Dulux Trade Alkali Resistant Plaster Primer and apply two coats Dulux Trade 100 Low Sheen acrylic emulsion paint:</u> | | | |
| 59 | On walls | m2 | 42 |
| <u>ON FACE BRICKWORK</u> | | | |
| <u>Prepare surfaces and apply two coats Nova 1 Novabrick sealant:</u> | | | |
| 60 | On exterior walls. | m2 | 42 |
| <u>ON WOOD</u> | | | |
| <u>Undercoat and minimum 2 coat gloss enamel</u> | | | |
| 61 | On doors (External) | m2 | 15 |
| 62 | On doors (Internal) | m2 | 15 |
| <u>ON METAL SURFACES</u> | | | |
| <u>Prepare surfaces and apply three coats Dulux Woodgard Interior/Exterior Timbavarnish:</u> | | | |
| 63 | On door frames. | m2 | 17 |
| Carried Forward | | | R |
| ALTERATIONS DEMOLITIONS & REFURBISHMENT BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| | Brought Forward | | | R | |
|--|--|----|----|---|--|
| 64 | On gates (Measured over the full flat area of both sides) | m2 | 15 | | |
| 65 | On windows (both sides measured over full flat area). | m2 | 9 | | |
| <u>PAINTWORK TO PREVIOUSLY PAINTED WORK</u> | | | | | |
| <u>ON PREVIOUSLY PAINTED FIBRE-CEMENT SURFACES</u> | | | | | |
| <u>Prepare surfaces and apply one coat Dulux Trade Alkali Resistant Plaster Primer and two coats Dulux Weatherguard acrylic emulsion paint:</u> | | | | | |
| 66 | On fascias and bargeboards, including priming metal jointing strips. | m2 | 7 | | |
| <u>ON PREVIOUSLY PAINTED METAL SURFACES</u> | | | | | |
| <u>Prepare surfaces, spot prime with Dulux Trade Steel Primer and apply one coat Dulux Trade Universal Undercoat and two coats Dulux Trade Gloss Enamel paint on factory primed steel:</u> | | | | | |
| 67 | On door frames etc. | m2 | 17 | | |
| 68 | On windows (both sides measured over full flat area). | m2 | 9 | | |
| <u>ON PREVIOUSLY PAINTED WOOD SURFACES</u> | | | | | |
| <u>Prepare surfaces and apply three coats Powafix Creosote wood preservative:</u> | | | | | |
| 69 | On members of exposed roof timbers at eaves, verges, etc. | m2 | 12 | | |
| Carried to Final Summary | | | | R | |
| ALTERATIONS | | | | | |
| DEMOLITIONS & REFURBISHMENT | | | | | |
| BTKM QUANTITY SURVEYORS | | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 3</u> | | | |
| | <u>BILL NO. 1</u> | | | |
| | <u>EARTHWORKS</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>SITE CLEARANCE</u> | | | |
| 1 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush and trees not exceeding 200mm girth, etc. | m2 | 81 | |
| 2 | Stripping average 100mm thick layer of top soil and stockpiling on site | m2 | 82 | |
| | <u>EXCAVATION, FILLING, ETC</u> | | | |
| | <u>Excavation in earth not exceeding 2m deep</u> | | | |
| 3 | Trenches | m3 | 11 | |
| 4 | Pit | m3 | 26 | |
| 5 | For aprons thickening | m3 | 1 | |
| | <u>Extra over trench and hole excavations in earth for excavation:</u> | | | |
| 6 | Soft rock | m3 | 4 | |
| 7 | Hard rock | m3 | 2 | |
| | Carried Forward | | R | |
| | 3 SEATS GRADE R TOILETS EARTHWORKS BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|--|--|------|----|
| <u>Extra over all excavations for carting away:</u> | | | |
| 8 | Surplus material from excavations and/or stock piles on site to a dumping site to be allocated by the Contractor | m3 | 8 |
| <u>Risk of collapse of excavations</u> | | | |
| 9 | Sides of trench and hole excavation not exceeding 1,5m deep. | m2 | 39 |
| <u>Keeping excavations free of water.</u> | | | |
| 10 | Keeping excavations free of water other than subterranean water | Item | |
| <u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% Mod AASHTO density</u> | | | |
| 11 | Under floors, steps, pavings, etc. | m3 | 4 |
| 12 | Backfilling to trenches, holes, etc. | m3 | 31 |
| <u>Compaction of surfaces</u> | | | |
| 13 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 30 |
| 14 | Compaction of ground surface to pits etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 18 |
| Carried Forward | | | R |
| 3 SEATS GRADE R TOILETS EARTHWORKS BTKM QUANTITY SURVEYORS | | | |

3 SEATS GRADE R TOILETS
EARTHWORKS
BTKM QUANTITY SURVEYORS

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | | R |
|---|--|----|----|---|
| <u>SOIL POISONING</u> | | | | |
| <u>Soil insecticide</u> | | | | |
| 17 | Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming. | m2 | 27 | |
| 18 | To bottom of concrete aprons | m2 | 20 | |
| 19 | To bottoms and sides of trenches, etc. | m2 | 44 | |
| Carried Forward to Summary of Section No. 3 | | | | R |
| 3 SEATS GRADE R TOILETS | | | | |
| EARTHWORKS | | | | |
| BTKM QUANTITY SURVEYORS | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 3</u> | | | |
| | <u>BILL NO. 2</u> | | | |
| | <u>CONCRETE, FORMWORK AND REINFORCEMENT</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to | | | |
| | be used - PW 371" | | | |
| | <u>UNREINFORCED CONCRETE, ETC</u> | | | |
| | <u>25Mpa/19mm Concrete</u> | | | |
| 1 | Strip footings | m3 | 4 | |
| 2 | Ditto, but surface bed in pit | m3 | 2 | |
| 3 | 2Aprons cast in panels | m3 | 2 | |
| 4 | Ramp | m3 | 1 | |
| 5 | Extra over concrete in surface beds for thickening 85mm deep the bottom including all excavation, backfilling etc. | m | 20 | |
| 6 | Thickening down apron on edge 110mm deep x 200mm wide | m | 20 | |
| | <u>REINFORCED CONCRETE, ETC</u> | | | |
| | <u>25Mpa/19mm Concrete</u> | | | |
| 7 | Slabs | m3 | 3 | |
| | Carried Forward | | | |
| | 3 SEATS GRADE R TOILETS CONCRETE, FORMWORK AND REINFORCEMENT BTKM QUANTITY SURVEYORS | | | |
| | | | R | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R | |
|--|---|----|----|--|
| <u>CONCRETE SUNDRIES</u> | | | | |
| <u>Finishing top surfaces of concrete smooth with a wood float</u> | | | | |
| 8 | Aprons and pavings to falls | m2 | 20 | |
| <u>Finishing top surfaces of concrete smooth with a steel trowel</u> | | | | |
| 9 | Surface beds, slabs, etc. | m2 | 14 | |
| <u>TEST CUBES</u> | | | | |
| 10 | Allow for preparing a set of three test cubes each size 150x150x150mm, sending them to an approved testing laboratory for testing and paying all charges in connection therewith. | No | 3 | |
| <u>FORMWORK</u> | | | | |
| <u>Rough formwork to sides:</u> | | | | |
| 11 | Edges, risers, ends and reveals not exceeding 300mm high or wide | m | 22 | |
| <u>Permanent formwork to soffits:</u> | | | | |
| 12 | Slabs propped up not exceeding 1.5m high | m2 | 2 | |
| 13 | Leave or form 500mm diameter opening in top of floor slab | No | 4 | |
| <u>REINFORCEMENT</u> | | | | |
| <u>Mesh Reinforcement (measure nett)</u> | | | | |
| 14 | Mesh ref. No. 395 fabric reinforcement fixed horizontal in surface beds | m2 | 13 | |
| Carried Forward to Summary of Section No. 3 | | | R | |
| 3 SEATS GRADE R TOILETS | | | | |
| CONCRETE, FORMWORK AND REINFORCEMENT | | | | |
| BTKM QUANTITY SURVEYORS | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | Quantity | Rate | Amount |
|---|----------|------|--------|
| <u>SECTION NO. 3</u> | | | |
| <u>BILL NO. 3</u> | | | |
| <u>BRICKWORK</u> | | | |
| <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| <u>BRICKWORK</u> | | | |
| Sizes in descriptions | | | |
| Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick | | | |
| Hollow walls etc | | | |
| Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole. | | | |
| Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats "Brixal" bitumen emulsion waterproofing coating. | | | |
| User note: The above preamble generally applies for works in hot and humid coastal areas | | | |
| Face bricks | | | |
| Bricks shall be ordered timeously to obtain uniformity in size and colour | | | |
| Carried Forward | | | |
| 3 SEATS GRADE R TOILETS MASONRY BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|---|--|----|----|
| <u>Pointing</u> | | | |
| Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc | | | |
| <u>SAMPLES</u> | | | |
| Samples of all masonry building units, except those for walls units. Samples of building units to be used in walls described as "load bearing" shall consist of 30 units from every 30 000 units delivered to site described as "load bearing", shall consist of a minimum of 6 | | | |
| <u>FOUNDATIONS</u> | | | |
| <u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class I mortar</u> | | | |
| 1 | One brick walls | m2 | 13 |
| 2 | One brick walls in pit | m2 | 14 |
| 3 | Half brick corbelling in pit | m | 21 |
| <u>FACE BRICKWORK</u> | | | |
| <u>Face bricks (purchase price of R 4000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u> | | | |
| 4 | Extra over brickwork for face brickwork in foundation | m2 | 3 |
| <u>SUPERSTRUCTURE</u> | | | |
| <u>FACE BRICKWORK</u> | | | |
| <u>Face bricks (purchase price of R 4000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u> | | | |
| 5 | Half brickwork for face brick walls pointed both sides | m2 | 18 |
| Carried Forward | | | R |
| 3 SEATS GRADE R TOILETS MASONRY BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R | |
|---|---|----|-----|--|
| 6 | One brickwork for face brick walls pointed both sides | m2 | 51 | |
| 7 | Half brickwork for face brickwork in beamfilling | m2 | 5 | |
| 8 | Fair raking and cutting | m | 9 | |
| | <u>Brick-on-edge header course coping, sills, etc. of face bricks (purchase price of R 3 500.00/1000 delivered to site excluding VAT) pointed with recessed joints on all exposed faces</u> | | | |
| 9 | Extra over brickwork for brick-on-edge header course lintels pointed on two sides and 110mm soffit | m | 7 | |
| 10 | Face brick-on-edge window sill 220mm wide pointed on two side and on top and set at a angle | m | 9 | |
| 11 | Fair cutting and fitting around pipe not exceeding 100mm diameter. | No | 2 | |
| | <u>BRICKWORK SUNDRIES</u> | | | |
| | <u>Brick reinforcement</u> | | | |
| 12 | 75mm Wide reinforcement built in horizontally | m | 62 | |
| 13 | 150mm Wide reinforcement built in horizontally | m | 211 | |
| | <u>Turning pieces</u> | | | |
| 14 | 220mm Wide turning piece to lintel etc | m | 5 | |
| | <u>Galvanised wire ties etc</u> | | | |
| 15 | 6mm Diameter roof tie 2m girth bent double with one end fixed to timber and other built into brickwork | No | 22 | |
| | <u>Prestressed fabricated lintels</u> | | | |
| 16 | Pair of 110 x 75mm Lintels in lengths exceeding 3m and not exceeding 4,5m | m | 8 | |
| Carried Forward | | | R | |
| 3 SEATS GRADE R TOILETS MASONRY BTKM QUANTITY SURVEYORS | | | | |

[illegible]

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 3</u> | | | |
| | <u>BILL NO. 4</u> | | | |
| | <u>WATERPROOFING</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>DAMP-PROOFING OF WALLS AND FLOORS</u> | | | |
| | <u>One layer 375mm micron embossed damp proof course</u> | | | |
| 1 | In walls | m2 | 5 | |
| | <u>One layer of 250 micron waterproof sheeting and sealed at overlaps with pressure sensitive tape</u> | | | |
| 2 | Under surface beds | m2 | 13 | |
| | <u>FLOOR AND WALLS SEALERS</u> | | | |
| | <u>"Secomastic" non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight:</u> | | | |
| 3 | Around steel windows and door frames. | m | 9 | |
| | Carried Forward to Summary of Section No. 3 | | | |
| | | | | R |
| | 3 SEATS GRADE R TOILETS | | | |
| | WATERPROOFING | | | |
| | BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 3</u> | | | |
| | <u>BILL NO. 5</u> | | | |
| | <u>ROOF COVERINGS</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | NOTE : Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No. 124 for CPAP formula purposes | | | |
| | <u>PROFILED METAL SHEETING AND ACCESSORIES</u> | | | |
| | <u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u> | | | |
| 1 | Roof covering with pitch not exceeding 25 degrees | m2 | 30 | |
| | <u>Sundries</u> | | | |
| 2 | 12" Thermal resistance sisalition laid on purlins | m2 | 30 | |
| | <u>RAINWATER DISPOSAL</u> | | | |
| | <u>Aluzink seamless metal gutters:</u> | | | |
| 3 | 100 x 100 x 0.6mm Standard rainwater gutters fixed with gutters brackets | m | 7 | |
| 4 | 75 x 100 x 0.6mm Thick galvanised rainwater downpipes fixed to wall | m | 5 | |
| 5 | Extra over rainwater pipe for eaves offset | No | 2 | |
| | Carried Forward | | | |
| | 3 SEATS GRADE R TOILETS ROOF COVERINGS BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| | | | |
|--|-----------------|---|--|
| | Brought Forward | R | |
| | | | |
| 3 SEATS GRADE R TOILETS ROOF COVERINGS BTKM QUANTITY SURVEYORS | Carried Forward | R | |
| | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| | Brought Forward | | | R | |
|---|----------------------------|----|---|---|--|
| 6 | Extra over for closed ends | No | 2 | | |
| 7 | Ditto ,for shoe | No | 2 | | |
| Carried Forward to Summary of Section No. 3 | | | | R | |
| 3 SEATS GRADE R TOILETS | | | | | |
| ROOF COVERINGS | | | | | |
| BTKM QUANTITY SURVEYORS | | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 3</u> | | | |
| | <u>BILL NO. 6</u> | | | |
| | <u>CARPENTRY AND JOINERY</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>ROOFS, ETC.</u> | | | |
| | <u>Sawn softwood</u> | | | |
| 1 | 38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m | m | 34 | |
| 2 | 50 x 76mm Purlins in lengths exceeding 3,9m and not exceeding 6,6m | m | 38 | |
| 3 | 76 x 38mm Wall plates | m | 7 | |
| | <u>Sundries</u> | | | |
| 4 | Two coats creosote on sawn timbers | m2 | 24 | |
| 5 | 6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together | No | 14 | |
| 6 | Hurricane clips | No | 19 | |
| | <u>EAVES, VERGES, ETC.</u> | | | |
| | <u>Pressed fibre-cement</u> | | | |
| 7 | 15 x 230mm Fascias and barge boards including galvanised steel H-profile jointing strips | m | 20 | |
| | Carried Forward | | | |
| | 3 SEATS GRADE R TOILETS CARPENTRY AND JOINERY BTKM QUANTITY SURVEYORS | | R | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|---|---|----|---|
| <u>DOORS, ETC.</u> | | | |
| <u>Wrought meranti doors hung to steel frames</u> | | | |
| 8 | 44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard (D1) | No | 1 |
| 9 | 44mm Purpose made Framed batten door 813 x 1882mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed (door raised by 120mm from bottom) (D2) | No | 3 |
| Carried Forward to Summary of Section No. 3 | | | R |
| 3 SEATS GRADE R TOILETS | | | |
| CARPENTRY AND JOINERY | | | |
| BTKM QUANTITY SURVEYORS | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 3</u> | | | |
| | <u>BILL NO. 7</u> | | | |
| | <u>IRONMONGERY</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>CATCHES, CABIN, HOOKS, ETC</u> | | | |
| | <u>Approved</u> | | | |
| 1 | 150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged | No | 3 | |
| | <u>LOCKS</u> | | | |
| | <u>Approved</u> | | | |
| 2 | Three lever mortice lockset | No | 1 | |
| 3 | Indicator lockset | No | 3 | |
| | <u>HANDLES</u> | | | |
| | <u>Aluminium Pull Handle</u> | | | |
| 4 | Set of two, 300mm pull handles fixed back to back on doors | No | 3 | |
| | <u>DOORSTOPS</u> | | | |
| | <u>Approved</u> | | | |
| 5 | 38mm Diameter rubber door stop plugged | No | 4 | |
| | Carried Forward | | R | |
| | 3 SEATS GRADE R TOILETS IRONMONGERY BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|--|--|----|---|
| <u>LETTERS, NAMEPLATES, ETC.</u> | | | |
| <u>"Union" or similar approved</u> | | | |
| 6 | 75 x 150mm Natural anodised aluminium plate with male or female symbol | No | 2 |
| <u>BATHROOM FITTINGS</u> | | | |
| <u>"Kimberley-Clark" or Similar</u> | | | |
| 7 | "Kimberly Clark" SQ2 code 405607B white lockable toilet roll holder | No | 3 |
| Carried Forward to Summary of Section No. 3 | | | R |
| 3 SEATS GRADE R TOILETS | | | |
| IRONMONGERY | | | |
| BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 3</u> | | | |
| | <u>BILL NO. 8</u> | | | |
| | <u>METALWORK</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>PRESSED STEEL DOOR FRAMES</u> | | | |
| | <u>1,2mm Single rebated frames suitable for half brick walls</u> | | | |
| 1 | Frame for door 813 x 2032mm high | No | 3 | |
| | <u>1,6mm Double rebated frames suitable for one brickwalls</u> | | | |
| 2 | Frame for door 813 x 2032mm high | No | 1 | |
| | <u>STEEL WINDOWS, DOORS, ETC</u> | | | |
| 3 | Window type NE1, 533 x 654mm high including burglar bars | No | 3 | |
| 4 | Window type NE 7,1022 x 654mm high including burglar bars | No | 2 | |
| | <u>WELDED SCREENS, GATES, ETC</u> | | | |
| | <u>Steel gates and frames</u> | | | |
| 5 | Purpose made square hallow section mild steel security gate, size 813 x 2032mm High | No | 2 | |
| | Carried Forward to Summary of Section No. 3 | | R | |
| | 3 SEATS GRADE R TOILETS | | | |
| | METALWORK | | | |
| | BTKM QUANTITY SURVEYORS | | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 3</u> | | | |
| | <u>BILL NO. 9</u> | | | |
| | <u>PLASTERING</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>CEMENT SCREEDS TO CONCRETE</u> | | | |
| | <u>Screeds to steel trowelled, on concrete:</u> | | | |
| 1 | 30mm thick on floors | m2 | 13 | |
| | <u>INTERNAL PLASTER</u> | | | |
| | <u>Cement plaster on brickwork or blockwork</u> | | | |
| 2 | On pits walls | m2 | 15 | |
| | <u>FLOOR AND WALLS SEALERS</u> | | | |
| | <u>Minimum two coats approved epoxy coat:</u> | | | |
| 3 | On screed | m2 | 13 | |
| 4 | On internal textured plaster walls and floors in pit | m2 | 15 | |
| | Carried Forward to Summary of Section No. 3 | | R | |
| | 3 SEATS GRADE R TOILETS IN SITU FINISHES BTKM QUANTITY SURVEYORS | | | |

| Item No | | Quantity | Rate | Amount |
|---|---|----------|------|--------|
| <u>SECTION NO. 3</u> | | | | |
| <u>BILL NO. 10</u> | | | | |
| <u>PLUMBING AND DRAINAGE (PROVISIONAL)</u> | | | | |
| <u>SUPPLEMENTARY PREAMBLES</u> | | | | |
| For preambles see "Specifications of materials and methods to be used - PW 371" | | | | |
| <u>ENVIRO-LOO TOILET SYSTEMS</u> | | | | |
| 1 | Supply and Install "Enviro-Loo" Industrial 1040 Model, complete with Junior Ceramic Toilet Bowl as per manufacturer's specification and manufacturer's compliance inspections | No | 3 | |
| 2 | Supply and install pre-cast concrete double wash-trough, complete with all necessary pipework including soakaway size 1000 x 1000 x 1000mm covered with "bidim" | No | 2 | |
| <u>FITTINGS</u> | | | | |
| 3 | 19mm chrome plated push button taps to wash troughs | No | 2 | |
| Carried Forward to Summary of Section No. 3 | | | | R |
| 3 SEATS GRADE R TOILETS PLUMBING AND DRAINAGE BTKM QUANTITY SURVEYORS | | | | |

[illegible]

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 3</u> | | | |
| | <u>BILL NO. 12</u> | | | |
| | <u>PAINTWORK</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>ON FIBRE-CEMENT</u> | | | |
| | <u>Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint</u> | | | |
| 1 | On fascias and barge boards | m2 | 4 | |
| | <u>ON WOOD</u> | | | |
| | <u>Undercoat and minimum 2 coat gloss enamel</u> | | | |
| 2 | On doors (Internal) | m2 | 11 | |
| 3 | On doors (External) | m2 | 9 | |
| | <u>ON METAL</u> | | | |
| | <u>Undercoat and minimum 2 coat gloss enamel</u> | | | |
| 4 | On door frames | m2 | 10 | |
| 5 | On gates (Measured over the full flat area of both sides) | m2 | 9 | |
| 6 | On gutters and down pipes | m | 12 | |
| | Carried Forward | | R | |
| | 3 SEATS GRADE R TOILETS PAINTWORK BTKM QUANTITY SURVEYORS | | | |

| Brought Forward | | | R |
|---|---|----|---|
| | <u>Spot prining defects in prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP, golden brown gloss enamel paint on steel</u> | | |
| 7 | On windows | m2 | 5 |
| <p>Carried Forward to Summary of Section No. 3</p> <p>3 SEATS GRADE R TOILETS PAINTWORK BTKM QUANTITY SURVEYORS</p> | | | R |

[illegible]

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 4</u> | | | |
| | <u>BILL NO. 1</u> | | | |
| | <u>EARTHWORKS</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>SITE CLEARANCE</u> | | | |
| 1 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush and trees not exceeding 200mm girth, etc. | m2 | 81 | |
| 2 | Stripping average 100mm thick layer of top soil and stockpiling on site | m2 | 82 | |
| | <u>EXCAVATION, FILLING, ETC</u> | | | |
| | <u>Excavation in earth not exceeding 2m deep</u> | | | |
| 3 | Trenches | m3 | 11 | |
| 4 | Pit | m3 | 26 | |
| 5 | For aprons thickening | m3 | 1 | |
| | <u>Extra over trench and hole excavations in earth for excavation:</u> | | | |
| 6 | Soft rock | m3 | 4 | |
| 7 | Hard rock | m3 | 2 | |
| | Carried Forward | | R | |
| | 3 SEATS GIRLS TOILETS EARTHWORKS BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|---|--|------|----|
| <u>Extra over all excavations for carting away:</u> | | | |
| 8 | Surplus material from excavations and/or stock piles on site to a dumping site to be allocated by the Contractor | m3 | 8 |
| <u>Risk of collapse of excavations</u> | | | |
| 9 | Sides of trench and hole excavation not exceeding 1,5m deep. | m2 | 39 |
| <u>Keeping excavations free of water.</u> | | | |
| 10 | Keeping excavations free of water other than subterranean water | Item | |
| <u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% Mod</u> | | | |
| <u>AASHTO density</u> | | | |
| 11 | Under floors, steps, pavings, etc. | m3 | 4 |
| 12 | Backfilling to trenches, holes, etc. | m3 | 31 |
| <u>Compaction of surfaces</u> | | | |
| 13 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 30 |
| 14 | Compaction of ground surface to pits etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 18 |
| Carried Forward | | | R |
| 3 SEATS GIRLS TOILETS EARTHWORKS BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | | R |
|---|---|----|----|---|
| 15 | Compaction of ground surface to aprons etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 22 | |
| | <u>Prescribed density tests on filling</u> | | | |
| 16 | Modified AASHTO Density tests | No | 3 | |
| Carried Forward | | | | R |
| 3 SEATS GIRLS TOILETS EARTHWORKS BTKM QUANTITY SURVEYORS | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | | R |
|---|--|----|----|---|
| <u>SOIL POISONING</u> | | | | |
| <u>Soil insecticide</u> | | | | |
| 17 | Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming. | m2 | 27 | |
| 18 | To bottom of concrete aprons | m2 | 20 | |
| 19 | To bottoms and sides of trenches, etc. | m2 | 44 | |
| Carried Forward to Summary of Section No. 4 | | | | R |
| 3 SEATS GIRLS TOILETS | | | | |
| EARTHWORKS | | | | |
| BTKM QUANTITY SURVEYORS | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 4</u> | | | |
| | <u>BILL NO. 2</u> | | | |
| | <u>CONCRETE, FORMWORK AND REINFORCEMENT</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to | | | |
| | be used - PW 371" | | | |
| | <u>UNREINFORCED CONCRETE, ETC</u> | | | |
| | <u>25Mpa/19mm Concrete</u> | | | |
| 1 | Strip footings | m3 | 4 | |
| 2 | Ditto, but surface bed in pit | m3 | 2 | |
| 3 | 2Aprons cast in panels | m3 | 2 | |
| 4 | Ramp | m3 | 1 | |
| 5 | Extra over concrete in surface beds for thickening 85mm deep the bottom including all excavation, backfilling etc. | m | 20 | |
| 6 | Thickening down apron on edge 110mm deep x 200mm wide | m | 20 | |
| | <u>REINFORCED CONCRETE, ETC</u> | | | |
| | <u>25Mpa/19mm Concrete</u> | | | |
| 7 | Slabs | m3 | 3 | |
| | Carried Forward | | | |
| | 3 SEATS GIRLS TOILETS CONCRETE, FORMWORK AND REINFORCEMENT BTKM QUANTITY SURVEYORS | | | |
| | | | R | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R | |
|--|---|----|----|--|
| <u>CONCRETE SUNDRIES</u> | | | | |
| <u>Finishing top surfaces of concrete smooth with a wood float</u> | | | | |
| 8 | Aprons and pavings to falls | m2 | 20 | |
| <u>Finishing top surfaces of concrete smooth with a steel trowel</u> | | | | |
| 9 | Surface beds, slabs, etc. | m2 | 14 | |
| <u>TEST CUBES</u> | | | | |
| 10 | Allow for preparing a set of three test cubes each size 150x150x150mm, sending them to an approved testing laboratory for testing and paying all charges in connection therewith. | No | 3 | |
| <u>FORMWORK</u> | | | | |
| <u>Rough formwork to sides:</u> | | | | |
| 11 | Edges, risers, ends and reveals not exceeding 300mm high or wide | m | 22 | |
| <u>Permanent formwork to soffits:</u> | | | | |
| 12 | Slabs propped up not exceeding 1.5m high | m2 | 2 | |
| 13 | Leave or form 500mm diameter opening in top of floor slab | No | 4 | |
| <u>REINFORCEMENT</u> | | | | |
| <u>Mesh Reinforcement (measure nett)</u> | | | | |
| 14 | Mesh ref. No. 395 fabric reinforcement fixed horizontal in surface beds | m2 | 13 | |
| Carried Forward to Summary of Section No. 4 | | | R | |
| 3 SEATS GIRLS TOILETS | | | | |
| CONCRETE, FORMWORK AND REINFORCEMENT | | | | |
| BTKM QUANTITY SURVEYORS | | | | |

| Item No | Quantity | Rate | Amount |
|---|----------|------|--------|
| <u>SECTION NO. 4</u> | | | |
| <u>BILL NO. 3</u> | | | |
| <u>BRICKWORK</u> | | | |
| <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| <u>BRICKWORK</u> | | | |
| Sizes in descriptions | | | |
| Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick | | | |
| Hollow walls etc | | | |
| Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole. | | | |
| Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats "Brixel" bitumen emulsion waterproofing coating. | | | |
| User note: The above preamble generally applies for works in hot and humid coastal areas | | | |
| Face bricks | | | |
| Bricks shall be ordered timeously to obtain uniformity in size and colour | | | |
| Carried Forward | | | R |
| 3 SEATS GIRLS TOILETS MASONRY BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|---|--|----|----|
| <u>Pointing</u> | | | |
| Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc | | | |
| <u>SAMPLES</u> | | | |
| Samples of all masonry building units, except those for walls units. Samples of building units to be used in walls described as "load bearing" shall consist of 30 units from every 30 000 units delivered to site described as "load bearing", shall consist of a minimum of 6 | | | |
| <u>FOUNDATIONS</u> | | | |
| <u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class I mortar</u> | | | |
| 1 | One brick walls | m2 | 13 |
| 2 | One brick walls in pit | m2 | 14 |
| 3 | Half brick corbelling in pit | m | 21 |
| <u>FACE BRICKWORK</u> | | | |
| <u>Face bricks (purchase price of R 4000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u> | | | |
| 4 | Extra over brickwork for face brickwork in foundation | m2 | 3 |
| <u>SUPERSTRUCTURE</u> | | | |
| <u>FACE BRICKWORK</u> | | | |
| <u>Face bricks (purchase price of R 4000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u> | | | |
| 5 | Half brickwork for face brick walls pointed both sides | m2 | 18 |
| Carried Forward | | | R |
| 3 SEATS GIRLS TOILETS MASONRY BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R | |
|-----------------|---|----|-----|---|
| 6 | One brickwork for face brick walls pointed both sides | m2 | 51 | |
| 7 | Half brickwork for face brickwork in beamfilling | m2 | 5 | |
| 8 | Fair raking and cutting | m | 9 | |
| | <u>Brick-on-edge header course coping, sills, etc. of face bricks (purchase price of R 3 500.00/1000 delivered to site excluding VAT) pointed with recessed joints on all exposed faces</u> | | | |
| 9 | Extra over brickwork for brick-on-edge header course lintels pointed on two sides and 110mm soffit | m | 7 | |
| 10 | Face brick-on-edge window sill 220mm wide pointed on two side and on top and set at a angle | m | 9 | |
| 11 | Fair cutting and fitting around pipe not exceeding 100mm diameter. | No | 2 | |
| | <u>BRICKWORK SUNDRIES</u> | | | |
| | <u>Brick reinforcement</u> | | | |
| 12 | 75mm Wide reinforcement built in horizontally | m | 62 | |
| 13 | 150mm Wide reinforcement built in horizontally | m | 211 | |
| | <u>Turning pieces</u> | | | |
| 14 | 220mm Wide turning piece to lintel etc | m | 5 | |
| | <u>Galvanised wire ties etc</u> | | | |
| 15 | 6mm Diameter roof tie 2m girth bent double with one end fixed to timber and other built into brickwork | No | 22 | |
| | <u>Prestressed fabricated lintels</u> | | | |
| 16 | Pair of 110 x 75mm Lintels in lengths exceeding 3m and not exceeding 4,5m | m | 8 | |
| | Carried Forward | | | R |
| | 3 SEATS GIRLS TOILETS MASONRY BTKM QUANTITY SURVEYORS | | | |

[illegible]

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 4</u> | | | |
| | <u>BILL NO. 4</u> | | | |
| | <u>WATERPROOFING</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>DAMP-PROOFING OF WALLS AND FLOORS</u> | | | |
| | <u>One layer 375mm micron embossed damp proof course</u> | | | |
| 1 | In walls | m2 | 5 | |
| | <u>One layer of 250 micron waterproof sheeting and sealed at overlaps with pressure sensitive tape</u> | | | |
| 2 | Under surface beds | m2 | 13 | |
| | <u>FLOOR AND WALLS SEALERS</u> | | | |
| | <u>"Secomastic" non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight:</u> | | | |
| 3 | Around steel windows and door frames. | m | 9 | |
| | Carried Forward to Summary of Section No. 4 | | R | |
| | 3 SEATS GIRLS TOILETS | | | |
| | WATERPROOFING | | | |
| | BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 4</u> | | | |
| | <u>BILL NO. 5</u> | | | |
| | <u>ROOF COVERINGS</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | NOTE : Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No. 124 for CPAP formula purposes | | | |
| | <u>PROFILED METAL SHEETING AND ACCESSORIES</u> | | | |
| | <u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u> | | | |
| 1 | Roof covering with pitch not exceeding 25 degrees | m2 | 30 | |
| | <u>Sundries</u> | | | |
| 2 | 12" Thermal resistance sisalition laid on purlins | m2 | 30 | |
| | <u>RAINWATER DISPOSAL</u> | | | |
| | <u>Aluzink seamless metal gutters:</u> | | | |
| 3 | 100 x 100 x 0.6mm Standard rainwater gutters fixed with gutters brackets | m | 7 | |
| 4 | 75 x 100 x 0.6mm Thick galvanised rainwater downpipes fixed to wall | m | 5 | |
| 5 | Extra over rainwater pipe for eaves offset | No | 2 | |
| | Carried Forward | | | |
| | 3 SEATS GIRLS TOILETS | | | |
| | ROOF COVERINGS | | | |
| | BTKM QUANTITY SURVEYORS | | | |

R

R

3 SEATS GIRLS TOILETS
ROOF COVERINGS
BTKM QUANTITY SURVEYORS

| | Brought Forward | | R |
|---|----------------------------|----|---|
| 6 | Extra over for closed ends | No | 2 |
| 7 | Ditto ,for shoe | No | 2 |
| Carried Forward to Summary of Section No. 4 | | | R |
| 3 SEATS GIRLS TOILETS ROOF COVERINGS BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 4</u> | | | |
| | <u>BILL NO. 6</u> | | | |
| | <u>CARPENTRY AND JOINERY</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>ROOFS, ETC.</u> | | | |
| | <u>Sawn softwood</u> | | | |
| 1 | 38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m | m | 34 | |
| 2 | 50 x 76mm Purlins in lengths exceeding 3,9m and not exceeding 6,6m | m | 38 | |
| 3 | 76 x 38mm Wall plates | m | 7 | |
| | <u>Sundries</u> | | | |
| 4 | Two coats creosote on sawn timbers | m2 | 24 | |
| 5 | 6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together | No | 14 | |
| 6 | Hurricane clips | No | 19 | |
| | <u>EAVES, VERGES, ETC.</u> | | | |
| | <u>Pressed fibre-cement</u> | | | |
| 7 | 15 x 230mm Fascias and barge boards including galvanised steel H-profile jointing strips | m | 20 | |
| | Carried Forward | | R | |
| | 3 SEATS GIRLS TOILETS CARPENTRY AND JOINERY BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|---|---|----|---|
| <u>DOORS, ETC.</u> | | | |
| <u>Wrought meranti doors hung to steel frames</u> | | | |
| 8 | 44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard (D1) | No | 2 |
| 9 | 44mm Purpose made Framed batten door 813 x 1882mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed (door raised by 120mm from bottom) (D2) | No | 3 |
| Carried Forward to Summary of Section No. 4 | | | R |
| 3 SEATS GIRLS TOILETS | | | |
| CARPENTRY AND JOINERY | | | |
| BTKM QUANTITY SURVEYORS | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 4</u> | | | |
| | <u>BILL NO. 7</u> | | | |
| | <u>IRONMONGERY</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>CATCHES, CABIN, HOOKS, ETC</u> | | | |
| | <u>Approved</u> | | | |
| 1 | 150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged | No | 3 | |
| | <u>LOCKS</u> | | | |
| | <u>Approved</u> | | | |
| 2 | Three lever mortice lockset | No | 2 | |
| 3 | Indicator lockset | No | 3 | |
| | <u>HANDLES</u> | | | |
| | <u>Aluminium Pull Handle</u> | | | |
| 4 | Set of two, 300mm pull handles fixed back to back on doors | No | 3 | |
| | <u>DOORSTOPS</u> | | | |
| | <u>Approved</u> | | | |
| 5 | 38mm Diameter rubber door stop plugged | No | 3 | |
| | Carried Forward | | R | |
| | 3 SEATS GIRLS TOILETS IRONMONGERY BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|--|--|----|---|
| <u>LETTERS, NAMEPLATES, ETC.</u> | | | |
| <u>"Union" or similar approved</u> | | | |
| 6 | 75 x 150mm Natural anodised aluminium plate with male or female symbol | No | 2 |
| <u>BATHROOM FITTINGS</u> | | | |
| <u>"Kimberley-Clark" or Similar</u> | | | |
| 7 | "Kimberly Clark" SQ2 code 405607B white lockable toilet roll holder | No | 3 |
| Carried Forward to Summary of Section No. 4 | | | R |
| 3 SEATS GIRLS TOILETS | | | |
| IRONMONGERY | | | |
| BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 4</u> | | | |
| | <u>BILL NO. 8</u> | | | |
| | <u>METALWORK</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>PRESSED STEEL DOOR FRAMES</u> | | | |
| | <u>1,2mm Single rebated frames suitable for half brick walls</u> | | | |
| 1 | Frame for door 813 x 2032mm high | No | 3 | |
| | <u>1,6mm Double rebated frames suitable for one brickwalls</u> | | | |
| 2 | Frame for door 813 x 2032mm high | No | 2 | |
| | <u>STEEL WINDOWS, DOORS, ETC</u> | | | |
| 3 | Window type NE1, 533 x 654mm high including burglar bars | No | 3 | |
| 4 | Window type NE 7,1022 x 654mm high including burglar bars | No | 2 | |
| | <u>WELDED SCREENS, GATES, ETC</u> | | | |
| | <u>Steel gates and frames</u> | | | |
| 5 | Purpose made square hallow section mild steel security gate, size 813 x 2032mm High | No | 2 | |
| | Carried Forward to Summary of Section No. 4 | | R | |
| | 3 SEATS GIRLS TOILETS | | | |
| | METALWORK | | | |
| | BTKM QUANTITY SURVEYORS | | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 4</u> | | | |
| | <u>BILL NO. 9</u> | | | |
| | <u>PLASTERING</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>CEMENT SCREEDS TO CONCRETE</u> | | | |
| | <u>Screeds to steel trowelled, on concrete:</u> | | | |
| 1 | 30mm thick on floors | m2 | 13 | |
| | <u>INTERNAL PLASTER</u> | | | |
| | <u>Cement plaster on brickwork or blockwork</u> | | | |
| 2 | On pits walls | m2 | 15 | |
| | <u>FLOOR AND WALLS SEALERS</u> | | | |
| | <u>Minimum two coats approved epoxy coat:</u> | | | |
| 3 | On screed | m2 | 13 | |
| 4 | On internal textured plaster walls and floors in pit | m2 | 15 | |
| | Carried Forward to Summary of Section No. 4 | | R | |
| | 3 SEATS GIRLS TOILETS IN SITU FINISHES BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 4</u> | | | |
| | <u>BILL NO. 10</u> | | | |
| | <u>PLUMBING AND DRAINAGE (PROVISIONAL)</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>ENVIRO-LOO TOILET SYSTEMS</u> | | | |
| 1 | Install "Enviro-Loo" Industrial 1040 Model, complete with Standard Ceramic Toilet Bowl as per manufacturer's specification and manufacturer's compliance inspections (Components from elsewhere) | No | 3 | |
| 2 | Supply and install pre-cast concrete double wash-trough, complete with all necessary pipework including soakaway size 1000 x 1000 x 1000mm covered with "bidim" | No | 2 | |
| | <u>FITTINGS</u> | | | |
| 3 | 19mm chrome plated push button taps to wash troughs | No | 2 | |
| | <u>Sundires</u> | | | |
| 4 | Stainless-steel SHE-BIN plugged to walls including purpose-made steel protective cage | No | 1 | |
| | Carried Forward to Summary of Section No. 4 | | | R |
| | 3 SEATS GIRLS TOILETS | | | |
| | PLUMBING AND DRAINAGE | | | |
| | BTKM QUANTITY SURVEYORS | | | |

| Item No | Quantity | Rate | Amount |
|---|----------------------------|------|--------|
| <u>SECTION NO. 4</u> | | | |
| <u>BILL NO. 11</u> | | | |
| <u>GLAZING</u> | | | |
| <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| <u>GLAZING TO STEEL WITH PUTTY</u> | | | |
| <u>4mm Obscure safety glass</u> | | | |
| 1 | Panes not exceeding 0,1 m2 | m2 | 2 |
| Carried Forward to Summary of Section No. 4 | | | R |
| 3 SEATS GIRLS TOILETS | | | |
| GLAZING | | | |
| BTKM QUANTITY SURVEYORS | | | |

| Item No | Quantity | Rate | Amount |
|---|---|------|--------|
| <u>SECTION NO. 4</u> | | | |
| <u>BILL NO. 12</u> | | | |
| <u>PAINTWORK</u> | | | |
| <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| <u>ON FIBRE-CEMENT</u> | | | |
| <u>Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint</u> | | | |
| 1 | On fascias and barge boards | m2 | 4 |
| <u>ON WOOD</u> | | | |
| <u>Undercoat and minimum 2 coat gloss enamel</u> | | | |
| 2 | On doors (External) | m2 | 9 |
| 3 | On doors (Internal) | m2 | 11 |
| <u>ON METAL</u> | | | |
| <u>Undercoat and minimum 2 coat gloss enamel</u> | | | |
| 4 | On door frames | m2 | 10 |
| 5 | On gates (Measured over the full flat area of both sides) | m2 | 9 |
| 6 | On gutters and down pipes | m | 12 |
| Carried Forward | | | R |
| 3 SEATS GIRLS TOILETS PAINTWORK BTKM QUANTITY SURVEYORS | | | |

| Brought Forward | | | R |
|---|---|----|---|
| 7 | <u>Spot prining defects in prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP, golden brown gloss enamel paint on steel</u> On windows | m2 | 5 |
| <p>Carried Forward to Summary of Section No. 4</p> <p>3 SEATS GIRLS TOILETS PAINTWORK BTKM QUANTITY SURVEYORS</p> | | | R |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

Section No. 4

3 SEATS GIRLS TOILETS

SECTION SUMMARY - 3 SEATS GIRLS TOILETS

| Bill No | | Page No | Amount |
|--|--------------------------------------|---------|--------|
| 1 | EARTHWORKS | 77 | |
| 2 | CONCRETE, FORMWORK AND REINFORCEMENT | 79 | |
| 3 | MASONRY | 83 | |
| 4 | WATERPROOFING | 84 | |
| 5 | ROOF COVERINGS | 87 | |
| 6 | CARPENTRY AND JOINERY | 89 | |
| 7 | IRONMONGERY | 91 | |
| 8 | METALWORK | 92 | |
| 9 | IN SITU FINISHES | 93 | |
| 10 | PLUMBING AND DRAINAGE | 94 | |
| 11 | GLAZING | 95 | |
| 12 | PAINTWORK | 97 | |
| Carried to Final Summary | | | R |
| 3 SEATS GIRLS TOILETS BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 6</u> | | | |
| | <u>BILL NO. 1</u> | | | |
| | <u>EARTHWORKS</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>SITE CLEARANCE</u> | | | |
| 1 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush and trees not exceeding 200mm girth, etc. | m2 | 81 | |
| 2 | Stripping average 100mm thick layer of top soil and stockpiling on site | m2 | 82 | |
| | <u>EXCAVATION, FILLING, ETC</u> | | | |
| | <u>Excavation in earth not exceeding 2m deep</u> | | | |
| 3 | Trenches | m3 | 11 | |
| 4 | Pit | m3 | 26 | |
| 5 | For aprons thickening | m3 | 1 | |
| | <u>Extra over trench and hole excavations in earth for excavation:</u> | | | |
| 6 | Soft rock | m3 | 4 | |
| 7 | Hard rock | m3 | 2 | |
| | Carried Forward | | R | |
| | 2/4 SEATS & URINALS BOYS TOILETS EARTHWORKS BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|--|--|------|----|
| <u>Extra over all excavations for carting away:</u> | | | |
| 8 | Surplus material from excavations and/or stock piles on site to a dumping site to be allocated by the Contractor | m3 | 8 |
| <u>Risk of collapse of excavations</u> | | | |
| 9 | Sides of trench and hole excavation not exceeding 1,5m deep. | m2 | 39 |
| <u>Keeping excavations free of water.</u> | | | |
| 10 | Keeping excavations free of water other than subterranean water | Item | |
| <u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% Mod AASHTO density</u> | | | |
| 11 | Under floors, steps, pavings, etc. | m3 | 4 |
| 12 | Backfilling to trenches, holes, etc. | m3 | 31 |
| <u>Compaction of surfaces</u> | | | |
| 13 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 30 |
| 14 | Compaction of ground surface to pits etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 18 |
| Carried Forward | | | R |
| 2/4 SEATS & URINALS BOYS TOILETS EARTHWORKS BTKM QUANTITY SURVEYORS | | | |

[illegible]

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | | R |
|---|--|----|----|---|
| <u>SOIL POISONING</u> | | | | |
| <u>Soil insecticide</u> | | | | |
| 17 | Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming. | m2 | 27 | |
| 18 | To bottom of concrete aprons | m2 | 20 | |
| 19 | To bottoms and sides of trenches, etc. | m2 | 44 | |
| Carried Forward to Summary of Section No. 5 | | | | R |
| 2/4 SEATS & URINALS BOYS TOILETS | | | | |
| EARTHWORKS | | | | |
| BTKM QUANTITY SURVEYORS | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 6</u> | | | |
| | <u>BILL NO. 2</u> | | | |
| | <u>CONCRETE, FORMWORK AND REINFORCEMENT</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to | | | |
| | be used - PW 371" | | | |
| | <u>UNREINFORCED CONCRETE, ETC</u> | | | |
| | <u>25Mpa/19mm Concrete</u> | | | |
| 1 | Strip footings | m3 | 4 | |
| 2 | Ditto, but surface bed in pit | m3 | 2 | |
| 3 | 2Aprons cast in panels | m3 | 2 | |
| 4 | Ramp | m3 | 1 | |
| 5 | Extra over concrete in surface beds for thickening 85mm deep the bottom including all excavation, backfilling etc. | m | 20 | |
| 6 | Thickening down apron on edge 110mm deep x 200mm wide | m | 20 | |
| | <u>REINFORCED CONCRETE, ETC</u> | | | |
| | <u>25Mpa/19mm Concrete</u> | | | |
| 7 | Slabs | m3 | 3 | |
| | Carried Forward | | | |
| | 2/4 SEATS & URINALS BOYS TOILETS CONCRETE, FORMWORK AND REINFORCEMENT BTKM QUANTITY SURVEYORS | | | |
| | | | R | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R | |
|--|---|----|----|--|
| <u>CONCRETE SUNDRIES</u> | | | | |
| <u>Finishing top surfaces of concrete smooth with a wood float</u> | | | | |
| 8 | Aprons and pavings to falls | m2 | 20 | |
| <u>Finishing top surfaces of concrete smooth with a steel trowel</u> | | | | |
| 9 | Surface beds, slabs, etc. | m2 | 14 | |
| <u>TEST CUBES</u> | | | | |
| 10 | Allow for preparing a set of three test cubes each size 150x150x150mm, sending them to an approved testing laboratory for testing and paying all charges in connection therewith. | No | 3 | |
| <u>FORMWORK</u> | | | | |
| <u>Rough formwork to sides:</u> | | | | |
| 11 | Edges, risers, ends and reveals not exceeding 300mm high or wide | m | 22 | |
| <u>Permanent formwork to soffits:</u> | | | | |
| 12 | Slabs propped up not exceeding 1.5m high | m2 | 2 | |
| 13 | Leave or form 500mm diameter opening in top of floor slab | No | 4 | |
| <u>REINFORCEMENT</u> | | | | |
| <u>Mesh Reinforcement (measure nett)</u> | | | | |
| 14 | Mesh ref. No. 395 fabric reinforcement fixed horizontal in surface beds | m2 | 13 | |
| Carried Forward to Summary of Section No. 5 | | | R | |
| 2/4 SEATS & URINALS BOYS TOILETS | | | | |
| CONCRETE, FORMWORK AND REINFORCEMENT | | | | |
| BTKM QUANTITY SURVEYORS | | | | |

| Item No | Quantity | Rate | Amount |
|---|----------|------|--------|
| <u>SECTION NO. 6</u> | | | |
| <u>BILL NO. 3</u> | | | |
| <u>BRICKWORK</u> | | | |
| <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| <u>BRICKWORK</u> | | | |
| Sizes in descriptions | | | |
| Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick | | | |
| Hollow walls etc | | | |
| Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole. | | | |
| Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats "Brixal" bitumen emulsion waterproofing coating. | | | |
| User note: The above preamble generally applies for works in hot and humid coastal areas | | | |
| Face bricks | | | |
| Bricks shall be ordered timeously to obtain uniformity in size and colour | | | |
| Carried Forward | | | R |
| 2/4 SEATS & URINALS BOYS TOILETS MASONRY BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|---|--|----|----|
| <u>Pointing</u> | | | |
| Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc | | | |
| <u>SAMPLES</u> | | | |
| Samples of all masonry building units, except those for walls units. Samples of building units to be used in walls described as "load bearing" shall consist of 30 units from every 30 000 units delivered to site described as "load bearing", shall consist of a minimum of 6 | | | |
| <u>FOUNDATIONS</u> | | | |
| <u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class I mortar</u> | | | |
| 1 | One brick walls | m2 | 13 |
| 2 | One brick walls in pit | m2 | 14 |
| 3 | Half brick corbelling in pit | m | 21 |
| <u>FACE BRICKWORK</u> | | | |
| <u>Face bricks (purchase price of R 4000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u> | | | |
| 4 | Extra over brickwork for face brickwork in foundation | m2 | 3 |
| <u>SUPERSTRUCTURE</u> | | | |
| <u>FACE BRICKWORK</u> | | | |
| <u>Face bricks (purchase price of R 4000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u> | | | |
| 5 | Half brickwork for face brick walls pointed both sides | m2 | 18 |
| Carried Forward | | | R |
| 2/4 SEATS & URINALS BOYS TOILETS MASONRY BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R | |
|-----------------|---|----|-----|---|
| 6 | One brickwork for face brick walls pointed both sides | m2 | 51 | |
| 7 | Half brickwork for face brickwork in beamfilling | m2 | 5 | |
| 8 | Fair raking and cutting | m | 9 | |
| | <u>Brick-on-edge header course coping, sills, etc. of face bricks (purchase price of R 3 500.00/1000 delivered to site excluding VAT) pointed with recessed joints on all exposed faces</u> | | | |
| 9 | Extra over brickwork for brick-on-edge header course lintels pointed on two sides and 110mm soffit | m | 7 | |
| 10 | Face brick-on-edge window sill 220mm wide pointed on two side and on top and set at a angle | m | 9 | |
| 11 | Fair cutting and fitting around pipe not exceeding 100mm diameter. | No | 2 | |
| | <u>BRICKWORK SUNDRIES</u> | | | |
| | <u>Brick reinforcement</u> | | | |
| 12 | 75mm Wide reinforcement built in horizontally | m | 62 | |
| 13 | 150mm Wide reinforcement built in horizontally | m | 211 | |
| | <u>Turning pieces</u> | | | |
| 14 | 220mm Wide turning piece to lintel etc | m | 5 | |
| | <u>Galvanised wire ties etc</u> | | | |
| 15 | 6mm Diameter roof tie 2m girth bent double with one end fixed to timber and other built into brickwork | No | 22 | |
| | <u>Prestressed fabricated lintels</u> | | | |
| 16 | Pair of 110 x 75mm Lintels in lengths exceeding 3m and not exceeding 4,5m | m | 8 | |
| | Carried Forward | | | R |
| | 2/4 SEATS & URINALS BOYS TOILETS MASONRY BTKM QUANTITY SURVEYORS | | | |

| | | | |
|---|-----------------|---|---|
| | Brought Forward | R | |
| Ventillation bricks | | | |
| Set of two 22 x 155mm high terra cotta clay vermin proof air bricks including making good reveals and gauze | No | 6 | |
| Carried Forward to Summary of Section No. 5 | | | R |
| 2/4 SEATS & URINALS BOYS TOILETS MASONRY BTKM QUANTITY SURVEYORS | | | |

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 6</u> | | | |
| | <u>BILL NO. 4</u> | | | |
| | <u>WATERPROOFING</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>DAMP-PROOFING OF WALLS AND FLOORS</u> | | | |
| | <u>One layer 375mm micron embossed damp proof course</u> | | | |
| 1 | In walls | m2 | 5 | |
| | <u>One layer of 250 micron waterproof sheeting and sealed at overlaps with pressure sensitive tape</u> | | | |
| 2 | Under surface beds | m2 | 13 | |
| | <u>FLOOR AND WALLS SEALERS</u> | | | |
| | <u>"Secomastic" non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight:</u> | | | |
| 3 | Around steel windows and door frames. | m | 9 | |
| | Carried Forward to Summary of Section No. 5 | | R | |
| | 2/4 SEATS & URINALS BOYS TOILETS | | | |
| | WATERPROOFING | | | |
| | BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 6</u> | | | |
| | <u>BILL NO. 5</u> | | | |
| | <u>ROOF COVERINGS</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | NOTE : Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No. 124 for CPAP formula purposes | | | |
| | <u>PROFILED METAL SHEETING AND ACCESSORIES</u> | | | |
| | <u>0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)</u> | | | |
| 1 | Roof covering with pitch not exceeding 25 degrees | m2 | 30 | |
| | <u>Sundries</u> | | | |
| 2 | 12" Thermal resistance sisalition laid on purlins | m2 | 30 | |
| | <u>RAINWATER DISPOSAL</u> | | | |
| | <u>Aluzink seamless metal gutters:</u> | | | |
| 3 | 100 x 100 x 0.6mm Standard rainwater gutters fixed with gutters brackets | m | 7 | |
| 4 | 75 x 100 x 0.6mm Thick galvanised rainwater downpipes fixed to wall | m | 5 | |
| 5 | Extra over rainwater pipe for eaves offset | No | 2 | |
| | Carried Forward | | | |
| | 2/4 SEATS & URINALS BOYS TOILETS | | | |
| | ROOF COVERINGS | | | |
| | BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

Brought Forward

R

Carried Forward

R

2/4 SEATS & URINALS BOYS TOILETS
ROOF COVERINGS
BTKM QUANTITY SURVEYORS

| Brought Forward | | | R |
|---|----------------------------|----|---|
| 6 | Extra over for closed ends | No | 2 |
| 7 | Ditto ,for shoe | No | 2 |
| Carried Forward to Summary of Section No. 5 | | | R |
| 2/4 SEATS & URINALS BOYS TOILETS | | | |
| ROOF COVERINGS | | | |
| BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 6</u> | | | |
| | <u>BILL NO. 6</u> | | | |
| | <u>CARPENTRY AND JOINERY</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>ROOFS, ETC.</u> | | | |
| | <u>Sawn softwood</u> | | | |
| 1 | 38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m | m | 34 | |
| 2 | 50 x 76mm Purlins in lengths exceeding 3,9m and not exceeding 6,6m | m | 38 | |
| 3 | 76 x 38mm Wall plates | m | 7 | |
| | <u>Sundries</u> | | | |
| 4 | Two coats creosote on sawn timbers | m2 | 24 | |
| 5 | 6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together | No | 14 | |
| 6 | Hurricane clips | No | 19 | |
| | <u>EAVES, VERGES, ETC.</u> | | | |
| | <u>Pressed fibre-cement</u> | | | |
| 7 | 15 x 230mm Fascias and barge boards including galvanised steel H-profile jointing strips | m | 20 | |
| | Carried Forward | | R | |
| | 2/4 SEATS & URINALS BOYS TOILETS CARPENTRY AND JOINERY BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|---|---|----|---|
| <u>DOORS, ETC.</u> | | | |
| <u>Wrought meranti doors hung to steel frames</u> | | | |
| 8 | 44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard (D1) | No | 2 |
| 9 | 44mm Purpose made Framed batten door 813 x 1882mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed (door raised by 120mm from bottom) (D2) | No | 2 |
| Carried Forward to Summary of Section No. 5 | | | R |
| 2/4 SEATS & URINALS BOYS TOILETS | | | |
| CARPENTRY AND JOINERY | | | |
| BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 6</u> | | | |
| | <u>BILL NO. 7</u> | | | |
| | <u>IRONMONGERY</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>CATCHES, CABIN, HOOKS, ETC</u> | | | |
| | <u>Approved</u> | | | |
| 1 | 150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged | No | 2 | |
| | <u>LOCKS</u> | | | |
| | <u>Approved</u> | | | |
| 2 | Three lever mortice lockset | No | 2 | |
| 3 | Indicator lockset | No | 2 | |
| | <u>HANDLES</u> | | | |
| | <u>Aluminium Pull Handle</u> | | | |
| 4 | Set of two, 300mm pull handles fixed back to back on doors | No | 2 | |
| | <u>DOORSTOPS</u> | | | |
| | <u>Approved</u> | | | |
| 5 | 38mm Diameter rubber door stop plugged | No | 4 | |
| | Carried Forward | | | |
| | 2/4 SEATS & URINALS BOYS TOILETS IRONMONGERY BTKM QUANTITY SURVEYORS | | | |
| | | | R | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R | |
|--|--|----|---|--|
| <u>LETTERS, NAMEPLATES, ETC.</u> | | | | |
| <u>"Union" or similar approved</u> | | | | |
| 6 | 75 x 150mm Natural anodised aluminium plate with male or female symbol | No | 2 | |
| <u>BATHROOM FITTINGS</u> | | | | |
| <u>"Kimberley-Clark" or Simlilar</u> | | | | |
| 7 | "Kimberly Clark" SQ2 code 405607B white lockable toilet roll holder | No | 2 | |
| Carried Forward to Summary of Section No. 5 | | | | |
| 2/4 SEATS & URINALS BOYS TOILETS | | | | |
| IRONMONGERY | | | | |
| BTKM QUANTITY SURVEYORS | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 6</u> | | | |
| | <u>BILL NO. 8</u> | | | |
| | <u>METALWORK</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>PRESSED STEEL DOOR FRAMES</u> | | | |
| | <u>1,2mm Single rebated frames suitable for half brick walls</u> | | | |
| 1 | Frame for door 813 x 2032mm high | No | 2 | |
| | <u>1,6mm Double rebated frames suitable for one brickwalls</u> | | | |
| 2 | Frame for door 813 x 2032mm high | No | 2 | |
| | <u>STEEL WINDOWS, DOORS, ETC</u> | | | |
| 3 | Window type NE1, 533 x 654mm high including burglar bars | No | 4 | |
| 4 | Window type NE 7,1022 x 654mm high including burglar bars | No | 2 | |
| | <u>WELDED SCREENS, GATES, ETC</u> | | | |
| | <u>Steel gates and frames</u> | | | |
| 5 | Purpose made square hallow section mild steel security gate, size 813 x 2032mm High | No | 2 | |
| | Carried Forward to Summary of Section No. 5 | | R | |
| | 2/4 SEATS & URINALS BOYS TOILETS | | | |
| | METALWORK | | | |
| | BTKM QUANTITY SURVEYORS | | | |

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 6</u> | | | |
| | <u>BILL NO. 9</u> | | | |
| | <u>PLASTERING</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>CEMENT SCREEDS TO CONCRETE</u> | | | |
| | <u>Screeds to steel trowelled, on concrete:</u> | | | |
| 1 | 30mm thick on floors | m2 | 13 | |
| | <u>INTERNAL PLASTER</u> | | | |
| | <u>Cement plaster on brickwork or blockwork</u> | | | |
| 2 | On pits walls | m2 | 15 | |
| | <u>FLOOR AND WALLS SEALERS</u> | | | |
| | <u>Minimum two coats approved epoxy coat:</u> | | | |
| 3 | On screed | m2 | 13 | |
| 4 | On internal textured plaster walls and floors in pit | m2 | 15 | |
| | Carried Forward to Summary of Section No. 5 | | R | |
| | 2/4 SEATS & URINALS BOYS TOILETS IN SITU FINISHES BTKM QUANTITY SURVEYORS | | | |

**INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL**

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 6</u> | | | |
| | <u>BILL NO. 10</u> | | | |
| | <u>PLUMBING AND DRAINAGE (PROVISIONAL)</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>ENVIRO-LOO TOILET SYSTEMS</u> | | | |
| 1 | Supply and Install "Enviro-Loo" Industrial 1040 Model, complete with Standard Ceramic Toilet Bowl as per manufacturer's specification and manufacturer's compliance inspections | No | 2 | |
| 2 | Supply and Install "Enviro-Loo" 4-bowl Urinal Evaporative Tank system complete as per manufacturer's specification | No | 1 | |
| 3 | Supply and install pre-cast concrete double wash-trough, complete with all necessary pipework including soakaway size 1000 x 1000 x 1000mm covered with "bidim" | No | 2 | |
| | <u>FITTINGS</u> | | | |
| 4 | 19mm chrome plated push button taps to wash troughs | No | 2 | |
| | Carried Forward to Summary of Section No. 5 | | | R |
| | 2/4 SEATS & URINALS BOYS TOILETS | | | |
| | PLUMBING AND DRAINAGE | | | |
| | BTKM QUANTITY SURVEYORS | | | |

[illegible]

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 6</u> | | | |
| | <u>BILL NO. 12</u> | | | |
| | <u>PAINTWORK</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>ON FIBRE-CEMENT</u> | | | |
| | <u>Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint</u> | | | |
| 1 | On fascias and barge boards | m2 | 4 | |
| | <u>ON WOOD</u> | | | |
| | <u>Undercoat and minimum 2 coat gloss enamel</u> | | | |
| 2 | On doors (External) | m2 | 9 | |
| 3 | On doors (Internal) | m2 | 11 | |
| | <u>ON METAL</u> | | | |
| | <u>Undercoat and minimum 2 coat gloss enamel</u> | | | |
| 4 | On door frames | m2 | 10 | |
| 5 | On gates (Measured over the full flat area of both sides) | m2 | 9 | |
| 6 | On gutters and down pipes | m | 12 | |
| | Carried Forward | | R | |
| | 2/4 SEATS & URINALS BOYS TOILETS PAINTWORK BTKM QUANTITY SURVEYORS | | | |

| Brought Forward | | | R |
|---|---|----|---|
| 7 | <u>Spot prining defects in prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP, golden brown gloss enamel paint on steel</u> On windows | m2 | 5 |
| Carried Forward to Summary of Section No. 5 2/4 SEATS & URINALS BOYS TOILETS PAINTWORK BTKM QUANTITY SURVEYORS | | | R |

[illegible]

**INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL**

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 7</u> | | | |
| | <u>BILL NO. 1</u> | | | |
| | <u>STORMWATER CONTROL</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>Earthworks</u> | | | |
| 1 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush and trees not exceeding 200mm girth, etc. | m2 | 95 | |
| 2 | Excavate in earth below natural, reduced or made up ground level, not exceeding 2m deep, to reduced levels under aprons, paving, etc | m3 | 20 | |
| 3 | Extra over surplus material from excavations and/stock piles on site to the dumping site to be located by the Contractor. | m3 | 20 | |
| 4 | Extra over trench or hole for excavations in soft rock | m3 | 11 | |
| 5 | Extra over trench or hole for excavations in hard rock | m3 | 7 | |
| 6 | Re-compaction of disturbed formation levels, including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 95 | |
| 7 | Treat soil under concrete rain water channels, etc. with an approved insecticide solution at the rate not less than 2 litre per 1m2 | m2 | 95 | |
| | Carried Forward | | | |
| | EXTERNAL WORKS | | | |
| | STORMWATER CONTROL | | | |
| | BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|---|---|----|-----|
| <u>Reinforced Concrete</u> | | | |
| 8 | 25Mpa/19mm Mass concrete in V-shaped channel 2000mm wide x 75mm thick with rounded salient edges and finished on exposed surfaces with 2:1 cement mortar, with and including one layer of ref.193 mesh reinforcement, laid to falls in panels not exceeding 2,0m long with 12mm bitumen impregnated softboard movement joints with exposed edges raked out for a depth of 10mm and filled with bituminous compound including all necessary excavations and formwork | m | 256 |
| 9 | Extra for fair open end | No | 15 |
| 10 | Extra for fair stopped end | No | 15 |
| 11 | Extra for angle intersection | No | 20 |
| Carried Forward to Summary of Section No. 6 | | | R |
| EXTERNAL WORKS | | | |
| STORMWATER CONTROL | | | |
| BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 7</u> | | | |
| | <u>BILL NO. 2</u> | | | |
| | <u>PAVED WALKWAYS</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>Site Clearance</u> | | | |
| 1 | Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush and trees not exceeding 200mm girth, etc. | m2 | 250 | |
| 2 | Stripping average 100mm thick layer of top soil and stockpiling on site | m2 | 250 | |
| | <u>Open face excavation in earth over sloping site</u> | | | |
| 3 | Excavation in earth not exceeding 2m open face excavation to form platforms under parking areas etc and depositing excavated material over site, including haulage not exceeding 10m from perimeter of excavations exceeding 2m deep | m3 | 45 | |
| | <u>Extra over all excavations for carting away</u> | | | |
| 4 | Surplus material from excavations and/stock piles on site to the dumping site to be located by the Contractor. | m3 | 45 | |
| | <u>Earth filling supplied by the contractor under parking areas, roadways, etc</u> | | | |
| 5 | Sub-base course of G5 material in accordance with SABS 1200 DM, compacted to 93% Mod AASHTO density | m3 | 35 | |
| | Carried Forward | | R | |
| | EXTERNAL WORKS PAVED WALKWAYS BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R |
|---|---|----|-----|
| <u>Compaction of surfaces</u> | | | |
| 6 | Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density | m2 | 250 |
| <u>Soil poisoning</u> | | | |
| 7 | Weedkiller (active ingredients metalaclor 102,8 g/l, terbitilasien 248,6 g/l and atrisien 248,6 g/l) mixed in the proportion of 100 ml weedkiller to 100 l water and applied at a rate of 10 l/m ² on cleared ground | m2 | 250 |
| <u>60mm Thick precast concrete DZZ interlocking heavy duty block paving of grey paving blocks in accordance with SANS 1058, laid to falls on and including 25mm thick sand layer with joints filled in with sand, compacted with a vibration compactor:</u> | | | |
| 8 | Paving to toilet areas etc to falls | m2 | 250 |
| 9 | 25Mpa/19mm unreinforced concrete edge beam | m | 320 |
| Carried Forward to Summary of Section No. 6 | | | R |
| EXTERNAL WORKS | | | |
| PAVED WALKWAYS | | | |
| BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|--------|
| | <u>SECTION NO. 7</u> | | | |
| | <u>BILL NO. 3</u> | | | |
| | <u>WATER TANKS</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>Excavation in earth not exceeding 2m deep</u> | | | |
| 1 | Trenches | m3 | 15 | |
| | <u>Extra over trench and hole excavations in earth for excavation in</u> | | | |
| 2 | Soft rock | m3 | 1 | |
| 3 | Hard rock | m3 | 1 | |
| | <u>Extra over all excavations for carting away</u> | | | |
| 4 | Surplus material from excavations and/stock piles on site to the dumping site to be located by the Contractor. | m3 | 15 | |
| | <u>Risk of collapse of excavations</u> | | | |
| 5 | Sides of trench and hole excavation not exceeding 1,5m deep. | m2 | 40 | |
| | <u>Keeping excavations free of water.</u> | | | |
| 6 | Keeping excavations free of water. | Item | | |
| | <u>Earth filling obtained from the excavations and / or prescribed stock piles on site compacted to 93 % Mod AASHTO density</u> | | | |
| 7 | Backfilling to trenches, holes, etc. | m3 | 15 | |
| | Carried Forward | | R | |
| | EXTERNAL WORKS | | | |
| | WATER TANKS | | | |
| | BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | | R |
|-------------------------|--|----|-----|---|
| | <u>Soil insecticide</u> | | | |
| 8 | To bottoms and sides of trenches, etc. | m2 | 18 | |
| | <u>15Mpa/19mm Concrete</u> | | | |
| 9 | Strip footings | m3 | 7 | |
| 10 | Platform surface beds cast in panels | m3 | 4 | |
| | <u>Finishing top surfaces of concrete smooth with a wood float</u> | | | |
| 11 | Platform surface beds | m2 | 10 | |
| | <u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class I mortar</u> | | | |
| 12 | One brick walls | m2 | 35 | |
| | <u>Brick reinforcement</u> | | | |
| 13 | 150mm Wide reinforcement built in horizontally | m | 100 | |
| | <u>Face bricks pointed with recessed horizontal and vertical joints to match the existing.</u> | | | |
| 14 | Extra over brickwork for face brickwork in foundation | m2 | 25 | |
| | <u>Extra over brickwork for face brickwork in foundation bricks pointed with recessed joints on all exposed faces to match the existing.</u> | | | |
| 15 | Coping on top of one brick wall | m | 20 | |
| | <u>One layer of 375 micron embossed black polyethylene damp proof course</u> | | | |
| 16 | On walls | m2 | 10 | |
| Carried Forward | | | | R |
| EXTERNAL WORKS | | | | |
| WATER TANKS | | | | |
| BTKM QUANTITY SURVEYORS | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Brought Forward | | | R | |
|---|---|----|----|--|
| | <u>One layer of 250 micron green medium density waterproof sheeting sealed at laps with pressure sensitive tape in accordance with the manufacturer's instructions.</u> | | | |
| 17 | Under surface beds | m2 | 10 | |
| | <u>Galvanized medium normalized mild steel piping</u> | | | |
| 18 | 25mm Pipes | m | 60 | |
| 19 | 50mm Pipes | m | 60 | |
| | <u>Extra over galvanised mild steel water supply pipes for fittings:</u> | | | |
| 20 | 25mm Fittings. | No | 30 | |
| 21 | 50mm Elbows. | No | 30 | |
| 22 | 50mm Union. | No | 30 | |
| 23 | 50mm Reducing bush. | No | 30 | |
| 24 | 15mm "Cobra Ref. 108LK" brass hose biptap. | No | 10 | |
| | <u>"Jojo" approved SANS PVC water tanks</u> | | | |
| 25 | 5 000 Litre plastic water tank fitted onto and secured to tank platforms | No | 4 | |
| 26 | 10 000 Litre plastic water tank fitted onto and secured to tank platforms | No | 2 | |
| Carried Forward to Summary of Section No. 6 | | | R | |
| EXTERNAL WORKS | | | | |
| WATER TANKS | | | | |
| BTKM QUANTITY SURVEYORS | | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

| Item No | | Quantity | Rate | Amount |
|---------|--|----------|------|--------|
| | <u>SECTION NO. 7</u> | | | |
| | <u>BILL NO. 4</u> | | | |
| | <u>FENCING</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | <u>Welded mesh fence</u> | | | |
| 1 | 1800mm High welded mesh fencing formed of 2.5 x 50mm galvanized welded mesh in long lengths, with three strands of 1.6mm galvanized steel wire at 150mm centres to and including four strings of 2.5mm galvanized steel binding wire stringed through holes and secured to straining bolts or posts ,10mm Diameter galvanized straining eye bolt 300mm long with nut and washer sawn off and bent after straining, 3150mm high, 50mm diameter x 2.8mm round mild steel intermediates posts with cover cap,Corner post formed of 100mm diameter x 3mm thick x 3150mm overall length steel post and 50mm Diameter x 2.6mm steel stays. | m | 350 | |
| 2 | 1800mm High and 900mm wide swing gate from 32mm diameter framework, all tube hot dipped galvanised after fabrication, with 50 x 50 x 2.5mm hot dipped galvanised welded mesh infill, fixed with heavy duty hinges to 100mm diameter x 3.5mm HDG corner posts, 2400mm long with standard type cap, 150 x 150 x 3mm base plate and casting into and including 500 x 500 x 600mm deep 20MPa concrete in ground, each corner post with off 32mm diameter x 2.5mm HDG stays at 45 degree angle, 50 x 50 x 2mm baseplate and casting into and including 300 x 300 x 300mm deep 20MPa concrete complete with all earthworks, trimmings and fixing | No | 3 | |
| | Carried Forward to Summary of Section No. 6 | | R | |
| | EXTERNAL WORKS | | | |
| | FENCING | | | |
| | BTKM QUANTITY SURVEYORS | | | |

INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL

Section No. 6

EXTERNAL WORKS

SECTION SUMMARY - EXTERNAL WORKS

**Bill
No**

- 1 STORMWATER CONTROL
- 2 PAVED WALKWAYS
- 3 WATER TANKS
- 4 FENCING

**Page
No**

125
127
130
131

Amount

Carried to Final Summary

R

EXTERNAL WORKS
BTKM QUANTITY SURVEYORS

**INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL**

| Item No | | Quantity | Rate | Amount |
|---------|---|----------|------|------------|
| | <u>SECTION NO. 8</u> | | | |
| | <u>BILL NO.1</u> | | | |
| | <u>PROVISIONAL SUMS</u> | | | |
| | <u>SUPPLEMENTARY PREAMBLES</u> | | | |
| | All the provisional sums cover supply of material and equipment and installation where applicable by firms of specialists. | | | |
| | Provisional sums are net and do not include builder's discount, but the Tenderer may allow under "Profit" items any profit he considers necessary. | | | |
| | The Tenderer is referred to Clause 87.1 and 87.2 in the "Preliminaries" section for the definition and adjustment of "General Attendance". | | | |
| | <u>N.B ALL PROVISIONAL WORKS ARE SUBJECT TO RE-MEASUREMENTS. THE PROVISIONAL WORK SHALL BE PAID AS PER THE WORK DONE</u> | | | |
| | <u>Testing existing borehole, upgrade reticulation system and water filtration system:</u> | | | |
| 1 | Provide an amount of R180 000.00 (One Hundred and Eighty Thousand Rand and Zero Cents) for testing existing borehole, upgrading reticulation and installing water filtration system | Item | | 180 000,00 |
| 2 | Allow for profit | Item | | |
| 3 | Allow for attendance | Item | | |
| | Carried Forward | | R | |
| | PROVISIONAL SUMS PS, PROFIT & ATTENDANCE BTKM QUANTITY SURVEYORS | | | |

**INDEPENDENT DEVELOPMENT TRUST
WATER & SANITATION PROGRAMME
TSHANGWANE PRIMARY SCHOOL**

| Brought Forward | | | R |
|---|--|------|------------|
| <u>Structural Steel Stands:</u> | | | |
| 4 | Provide an amount of R240 000.00 (Two Hundred and Forty Thousand Rand and Zero Cents) for two (2) structural steel stands | Item | 240 000,00 |
| 5 | Allow for profit | Item | |
| 6 | Allow for attendance | Item | |
| <u>Lockable fabricated steel manhole for borehole pumps:</u> | | | |
| 7 | Provide an amount of R6 500.00 (Six Thousand Five Hundred Rand and Zero Cents) for a lockable fabricated steel manhole for borehole pump | Item | 6 500,00 |
| 8 | Allow for profit | Item | |
| 9 | Allow for attendance | Item | |
| <u>YBE (Youth Built Environment):</u> | | | |
| 10 | Provide an amount of R19 000.00 (Nineteen Thousand Rand and Zero Cents) for Youth Built Environment mentoring programme (one candidate) | Item | 19 000,00 |
| 11 | Allow for profit | Item | |
| 12 | Allow for attendance | Item | |
| <u>CLO (Community Liaison Officer):</u> | | | |
| 13 | Provide an amount of R35 000.00 (Thirty Five Thousand Rand and Zero Cents) for a Community Liaison Officer monthly wages for 7 Months | Item | 35 000,00 |
| 14 | Allow for profit | Item | |
| 15 | Allow for attendance | Item | |
| Carried to Final Summary | | | R |
| PROVISIONAL SUMS | | | |
| PS, PROFIT & ATTENDANCE | | | |
| BTKM QUANTITY SURVEYORS | | | |

| FINAL SUMMARY | | | Page No | Amount |
|---|----------------------------------|-----|---------|--------|
| Section No | | | | |
| 1 | PRELIMINARIES | 34 | | |
| 2 | ALTERATIONS | 48 | | |
| 3 | 3 SEATS GRADE R TOILETS | 73 | | |
| 4 | 3 SEATS GIRLS TOILETS | 98 | | |
| 5 | 2/4 SEATS & URINALS BOYS TOILETS | 123 | | |
| 6 | EXTERNAL WORKS | 132 | | |
| 7 | PROVISIONAL SUMS | 134 | | |
| SUB TOTAL (A) | | | R | |
| Provide 5% (FIVE PERCENT) on Sub-total (A) as contingency to be deducted in whole or in part if not required in full. | | | R | |
| SUB TOTAL (B) | | | R | |
| Add Value Added Tax @ 15% | | | R | |
| Carried to Form of Offer and Acceptance | | | R | |
| BTKM QUANTITY SURVEYORS | | | | |