



LAYOUT PLAN
SCALE 1:750

Pier 1/ TPT Staff building & EES building					
Meter No	Propose AMR size	Existing pipe size	Exist pipe material	Meter to be installed above ground/ or inside manhole	Position of meter Co-ordinates
11	150mm	375mm	Unknown	Above ground	Y= -2599.432 X= 3307362.997
16	50mm	50mm	Unknown	Above ground	Y= -2434.323 X= 3307555.324
17	80mm	80mm	PVC/HDPE	Above ground attach to building	Y= -2679.957 X= 3307421.674

GENERAL NOTES:

1. ANCHORAGE AND THRUST BLOCKS SHOULD BE USED WHENEVER THE PIPELINE CHANGES VERTICAL OR HORIZONTAL DIRECTION BY MORE THAN 10°. THRUST BLOCKS SHOULD ALSO BE USED WHERE THE SIZE OF THE PIPELINE CHANGES, AT BLANK ENDS AND ON STEEP SLOPES (MORE THAN 1:6).



SITE PLAN
SCALE 1:7500

LEGEND

- NEW METERS CONNECTION WITH AMR TECHNOLOGY TO BE MEASURED AS A UNIT.
- EXISTING ETSEKIWINI SMALL METER
- EXISTING ETSEKIWINI BULK METER
- EXISTING SEWER
- EXISTING FRESH WATER
- EXISTING STORMWATER

FOR APPROVAL



PROJECT / AREA / ASSET / SUBJECT

PORT OF DURBAN

DRAWING STANDARDS

DRAWING TITLE

INSTALLATION OF AUTOMATIC METER READERS TO ISOLATE TPT FROM TNPA WATER RETICULATION

Pier 1/ TPT Staff building & EES building

DATE	2021-10-26	DM - DESIGN CENTRE MANAGER MR. R. M. VILBRO
SCALE	AS SHOWN	SIGNATURE DATE
DESIGNED BY	RB	DM - PORT ENGINEER MR. M. Sutsaka
CHECKED BY		SIGNATURE DATE
DRAWN BY	RB	DM - PLAN DRAWER MR. R. Benade
CHECKED BY	RV	SIGNATURE DATE

PAPER SIZE	TRANSNET DRW. NO.	SHEET	REV.
A1	DH61-J-904-006-00		
	CONSULTANT / CONTRACTOR DRW. NO.		