

Public Address Amplifier- Phase 2

Bill of Quantities

After the site clarification meeting that took place with the Contractors, the following BoQ was compiled from the information that was given to them while on site. However there were minor adjustments to some of the quantities. Also we have added an item “piping” so that all the cables that go onto trenches are inserted onto PVC piping.

	Item	Specification	Quantity
1	Poles (number)	3m high x 25mm OD hollow, Galvanised Steel Pipe	4
2	Amplifiers (number)	Bosch, PRS 1P500	7
3	Horn1 speakers (number)	Bosch, LBC 3482/00	36
4	Horn2 speakers (number)	Bosch, LBC 3428/01	104
5	Cabinet speakers (number)	Bosch, 3018/01	19
6	Speaker Cable (m)	FR120, 1.5mm ²	6 681
7	Conduit (m)	Galvanised Steel conduit, 20mm diameter	4 764
8	Amplifier cubicle (number)		1
9	Trenching (m)	500mm deep trench	1 935
10	Piping (m)	Black Poly-ethylene, 20mm, (outer 24mm, inner 21mm)	1935