

TENDER SCHEDULE

Name of work : special repairs to the Kuttigoundenpathy 1.00 Lakhs OHT And Masthigoundenpathi 60,000 litre OHT in Thirumalayampalayam town panchayat

Estimate amount : Rs 9,00,000 /-

Sl. No.	Probable Quantity		Description of Work	TNDSS No.	Rate		Unit	Remark
					In Figures	In Words		
1			Providing two legged scaffolding using 15cm dia blue-gum posts of 4.0m overall length (3M HT + 0.5M projection + 0.5m into ground) the distance between two rows being 1.25m and the spacing of posts being 2.0m and the spacing of posts being 2.0m in both the rows with two horizontal posts with 0.5m overlap on either side and braces at 2m c/c including longitudinal and transverse middle braces to step up and providing a platform with country wood plank of 40mm tk & 1.0m width in a complete form using color and nails - 1.0m run -- FOR REJUVENATION WORKS					
	71.00	M	For 0.00 -3.00m Ht (Initial rate)				1 m (One Meter)	
	311.00	M	Kuttigoundenpathy 1.00Lakh Litre OHT				1 m (One Meter)	
2	850.00	M2	Supplying and fabrication of steel and placing in position of TMT steel rods for RCC works as per design given including cost of steel and GI binding wire in all floors etc., complete complying with standard specification in TNDSS NO:97 V, VI (S6) VII (S6), VII-3.				1 Kg (One Kilo Gramme)	
3	75.00	M2	Applying Epoxy based zinc rich primer shall be done for existing rods for cathodic protection to steel rods. Applying of one coat of Heavy duty epoxy bonding agent over the parent concrete including all materials and labour charges etc, complete				1 m ² (One Square Meter)	

4	99.00	M2	Providing M 20 grade concrete using 10 mm down size aggregate admixed with Acrylic latex based waterproofing cum bonding agent @2.5 Ltrs. and 10 Kg of Fibre glass powder per bag of cement for the average thickness up to 100 mm. including all labour and hire charges etc, complete				1 m ² (One Square Meter)	
---	-------	----	---	--	--	--	-------------------------------------	--