





Item Rate BoQ

Tender Inviting Authority: The Commissioner, Pudukkotai Municipality

Name of Work: Providing 150 mm dia D.I Main pipe line in Brundhavan to Bose nagar OHT and Narimedu OHT From Singamuthu Iyanar kovil thidal Sump Sump in Pudukkottai Municipality.

Contract No: 12026/2020/E1

| Bidder Name : | |
|------------------|--|
| Name: | |

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

| SI. No. | Item Description | Quantity | Units | | TOTAL AMOUNT Without Taxes | TOTAL AMOUNT In Words |
|------------|--|----------|-------|---|----------------------------|-----------------------|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 1 | Earthwork excavation of for pipe line trench work having bed width of 1.25m and below on linear measurement basis including all cost and conveyance of all materials and labour charges etc. complete as per standard specifications | | Rm | | 0.00 | INR Zero Only |
| 2 | Supply and delivery of DUCTILE IRON SOCKET/SPIGOT PIPES FOR CLASS K9 AS PER IS 8329/2000 including all cost and conveyance of all materials and labour charges etc. complete as per standard specifications | | | | | |
| 2.01 | 150 mm DI K9 Socket/Spigot pipes | 880.00 | Rm | | 0.00 | INR Zero Only |

| SI. No. | Item Description | Quantity | Units | | TOTAL AMOUNT Without Taxes | TOTAL AMOUNT In Words |
|------------|---|----------|-------|---|----------------------------|-----------------------|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 3 | Conveyance of C.I/G.I/D.I. Pipes and Specials Unloading, stacking at stock yard and Conveyance from stock yard to site (Unloading from Railway wagons or loading into Railway, Loading into carts or lorries/ Size Tonne, Unloading from carts or lorries & stacking, Transport charges up to 8km or part there of Tonne) | | | | | |
| 3.01 | Over 125 mm up to 200 mm | 28.23 | Tonne | | 0.00 | INR Zero Only |
| 4 | Supply and delivery of DUCTILE IRON SPECIALS AS PER IS 9523/2000 including all cost and conveyance of all materials and labour charges etc. complete as per standard specifications | | | | | |
| 4.01 | ALL FLANGE (100mm - 200 mm dia) | 500.00 | Kg | | 0.00 | INR Zero Only |
| 5 | Supply and delivery of CI D/F SLUICE VALVE WITH CAP/ WHEEL AS PER IS 14846/2000 PN 1.0 WITH ISI MARKING including all cost and conveyance of all materials and labour charges etc. complete as per standard specifications | | | | | |
| 5.01 | 150 mm dia CI D/F sluice valve | 2.00 | No | | 0.00 | INR Zero Only |
| 6 | Supply and delivery of CI SINGLE AIR VALVE AS PER ISI 14845/2000 including all cost and conveyance of all materials and labour charges etc. complete as per standard specifications | | | | | |

| SI. No. | Item Description | Quantity | Units | | TOTAL AMOUNT Without Taxes | TOTAL AMOUNT In Words |
|------------|--|----------|-------|---|----------------------------|-----------------------|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 6.01 | 100 mm dia CI D/F Air valve | 1.00 | No | | 0.00 | INR Zero Only |
| 7 | Jointing C.I/ D.I-S/S pipes and specials with rubber gaskets (tyton joint) including cost of lubricants. (including cost of jointing materials) | | | | | |
| 7.01 | 150 mm dia C.I/ D.I-S/S pipes and specials | 146.00 | No | | 0.00 | INR Zero Only |
| 8 | Lowering of D.I Pipes and specials in the trenches and laying to proper grade and alignment and as directed by the dept Officers complete as per standard specifications. | | | | | |
| 8.01 | 150 mm dia D.I Pipes and Specials | 880.00 | Rm | | 0.00 | INR Zero Only |
| 9 | Testing of M.S. / C.I. / D.I / P.V.C. / H.D.P.E / pipes with hydraulic testing equipment by filling with water (including cost of water @ Rs. 60/KL) and testing to recommended pressure in convenient stretches and attending the bursts if any occured during the test, excluding the cost of pipes but including other incidential and operational charges etc., complete for the following diametres of pipes. | | | | | |
| 9.01 | 150 mm DI K9 pipes | 880.00 | Rm | | 0.00 | INR Zero Only |

| SI. No. | Item Description | Quantity | Units | | Without Taxes | TOTAL AMOUNT In Words | |
|------------|---|----------|---------------|---|---------------|-----------------------|--|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | |
| | Refilling the excavated earth into excavated trench including all cost and conveyance of all materials and labour charges etc. complete as per standard specifications. | | Rm | | 0.00 | INR Zero Only | |
| Total in | Figures | | | | 0.00 | | |
| Quoted | Rate in Words | | INR Zero Only | | | | |