

Name of the Work: Making of New temple Wooden Car (Swamy Car) in A/M Sundhareswarar Swamy Temple @ kovur, Kundrathur Taluk,
Kancheepuram District.

TENDER SCHEDULE

Value of Work Rs.89,99,300/-

Value Of Tender: Rs.89,99,297/- Cost Of EMD: Rs.55,000/-

Period of work 18 months

Name of the contractor
M.R.NO/Date

Tender Schedule Cost : 15000/- + 18% GST = 16800/-

S.No.	Qty	Description of Work	Rate		Amount
			in figure	in words	
1	18.00 Cu.m	Supplying of Country wood(illuppai, vagai, koogu)For Wooden Car of Required size including cost and conveyance of all materials to site and lobour charges etc complete (Details of wood as per given by approved stabathy).			
2	2.50 Cu.m	Supplying of Best Country wood(illuppai, vagai, koogu) including cost and conveyance of materials @ site etc complete as per standard specification (Details of wood as per given by approved stabathy).			
3	6.00 Cu.m	Supplying of Country wood(illuppai, vagai, koogu)For Wooden Car of Required size including including cost and conveyance of all materials to site and lobour charges etc complete (Details of wood as per given by approved stabathy).			
4	2.75 Cu.m	Supply of teak wood frames of ordinary type of required size including including cost and conveyance of all materials to site and lobour charges etc complete (Details of wood as per given by approved stabathy).			

Signature of Executive Officer

No.of Correction/ overwriting

Signature of contractor

5		Supply of best country (Vengai) reapers of following size and stacking at site including cost and conveyance of all materials to site and labour charges etc complete (Details of wood as per given by approved stabathy).				
5a	610 m	50x12 mm Size				
5b	345 m	50x25 mm Size				
6	18 Cu.m	Labour Charges for wrought and put up for wooden frame of ordinary type including sizing, cutting for the required size and fixing the car with accessories and all other handling and labour for fixing etc complete as per standard specification				
7	6.00 Cu.m	Labour Charges for wrought and put up for top portion of car including kodungal, eve board etc. of required size complete.				
8	2.75 Cu.m	Labour Charges for wrought and put up for Alangarakal of large sizes including, hosting fixing etc. Complete as per standard specification.				
9		Labour Charges for wrought and put up for Varivargam height including cutting the wood to size shaping rounding etc fixing in the car including steel fixtures etc all complete				
9a	386 Nos.	upto 1'1/2" ht.				
9b	1 No	upto 2'1/2" ht.				
9b	6 Nos.	upto 6' ht.				
10		Labour Charges for wrought and put up for Country wood reeper of following size including Cutting, hoisting fixing in the car works etc complete as per standard specifications.				
10a	610 m	50x12 mm Size				
10b	345 m	50x25 mm Size				

Signature of Executive Officer

No.of Correction/ overwriting

Signature of contractor