

**ERODE DISTRICT - KANJIKOVIL TOWN PANCHAYAT**

**SCHEDULE - A**

**Schedule of rates and approximate quantities**

a) The quantities here given are those upon which the estimate cost of the work is based but they are subject to alterations, commissions, deduction or additional as provided for in the conditions of this contract and do not necessarily show the actual quantities of work to be done. The unit rates notes below are those government payment for extra or deductions read with the Town Panchayat councils adaptation form and other conditions or specification of this contract and subject to the accepted tender percentage either below, above or at estimate rates as defined in the tender and as shown at the end of Schedule "A"

b) It is expressly understood that measured work is to be taken net-not withstanding any custom to practice to the contrary according to actual quantities when in place and finished according to the drawing or as may be ordered from time by the Assistant Executive Engineer at the cost calculated by measurement or weight at the respective prices with out any additional charge for any necessary or contingent works connected here with. The rates quoted are for works In-SITE and completed in every respect.

**Scheme : SBM (2.0) Solid Waste Management (SWM) Bio- Mining 2021 - 2022**

**Estimate Amount Rs. 4071000**

**Name of work :- Bio-mining and Removing of Historical Garbage @ Ward No.9 Chithode Road Resource Recovery Park in Kanjikoil Town Panchayat.**

Contractor

Executive Officer

**ERODE DISTRICT - KANJIKOVIL TOWN PANCHAYAT**  
**TENDER SCHEDULE**

**Name of work :- Bio-mining and Removing of Historical Garbage @ Ward No.9 Chithode Road Resource Recovery Park in Kanjikovil Town Panchayat.**

Issued Thiru :  
Chalan no. Dt.

**Executive Officer**  
Kanjikovil Town Panchayat  
Erode District

**Scheme : SBM (2.0)Solid Waste Management (SWM) Bio- Mining 2021 - 2022**

**Estimate Amount Rs. 4071000**

Sl. No	Probable Qty. in Figures		Description of Work	TNDSS & MORTH Specification No.	Rates in Rupees		Unit	Remarks
					Figure	Words		
1	5089.00	M3	<p>Revamping of existing dumped garbage in Compost yard at Chithode Road Resource Recovery Park in Kanjikovil Town Panchayat, by Bio -Mining</p> <p>a)Exacavating the existing mixed compacted garbage which underwent biological degradation in the land portion allocated / earmarked by Town Panchayat authority and sieving them by Mechanical sieving machine or any other equipment.</p> <p>b) Stabilization of the open land fill site</p> <p>c) Control mal odour</p> <p>d) Eco friendly and nonpolluting process in order to reduce the impact of dumping site in the adjacent areas</p> <p>e)Exacavating the soil which lost its stability due to garbage dumping with necessary dewatering works in the portion of the land earmarked</p> <p>f)Segregate the exacavated garbage in the land portion</p> <p>g)Selling, diverting for recycling, marketing and Segregation, without any accumulation in storage facility at the project site</p>	Special			1M3 (One Cubic Metre)	

Sl. No	Probable Qty. in Figures		Description of Work	TNDSS & MORTH Specification No.	Rates in Rupees		Unit	Remarks
					Figure	Words		
			<p>h)Creation and maintenance of infrastructure, facilities and amenities, for sieving, the excavated garbage, storing the segregated materials before selling / taking out them from the project site</p> <p>i)Deployment of necessary manpower, materials, equipments, tools and construction of plants and sheds and creation of facilities for handling, separating, segregating, storing and weighing facilities for the operation of the plant and using only covered body vehicles for the transportation of materials</p> <p>j)Create all facilities and make arrangements for controlling the emission,pollution and contamination of Environment including atmosphere,air,water and earth including control of dust and noise pollution</p>					