

**VEERAVANALLUR TOWN PANCHAYAT****TENDER SCHEDULE****NAME OF WORK: Providing Sewage treatment filter bed at Madhan Kovil Street in Veeravanallur Townpanchayat****Estimate Rs. 350000**

| Sl. No | Probable Quantity |     | Description of works   | Rate in |       | Per Unit               | Total Amount |
|--------|-------------------|-----|--|---------|-------|------------------------|--------------|
|        |                   |     |  | Figures | Words |                        |              |
| 1      | 18.00             | Cum | Earth work excavation for foundation in Hard stiff clay, stiff black cotton, hard red earth, shales murram, gravel, stoney earth and earth mixed with small size boulders SS.20B and Sand, silt or other loose soil, wet sand, or silt not under water, light black cotton soil, sandy loam ordinary soil and to full depth as may be directed except in hardrock requiring blasting inclusive of shoring shuttering and baling out water and cleaning and levelling the site etc., complete |         |       | 1Cum (One cubic meter) |              |
| 2      | 2.40              | Cum | Plain Cement Concrete 1:4:8 (one cement four fine aggregates and eight coarse aggregates) using 40mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges and all incidental charges such as water providing etc., complete as per standard specification   |         |       | 1Cum (One cubic meter) |              |

| Sl. No | Probable Quantity |     | Description of works  | Rate in |       | Per Unit                | Total Amount |
|--------|-------------------|-----|---|---------|-------|-------------------------|--------------|
|        |                   |     |   | Figures | Words |                         |              |
| 3      | 12.25             | Cum | A) Reinforced Cement Concrete 1:1½:3 Mix (One part cement, one and half part sand and three part of aggregate)using 20mm size ISS HBG metal machine crushed from approved quarry including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing but excluding cost of reinforcement etc. Complete with std. Specifications. TNDSS NO: 30 V, VI (S3), VII-3. |         |       | 1Cum (One cubic meter)  |              |
| 4      | 1300.00           | Kg  | A) Supplying and fabrication of steel and placing in position of TMT steel rods for RCC works as per design given including cost of steel and GI binding wire in all floors etc., complete complying with standard specification in TNDSS NO:97 V,VI (S6) VII (S6), VII-3.  |         |       | 1Sqm (One square meter) |              |
| 6      | 100.00            | Kg  | Supply and fixing of M.S Grills with Doors and Windows with one coat of Red oxide with Primer including all costs such as welding,grinding and fabrication charges, cost and conveyance of all materials to site etc,complete as per standard specification.  |         |       | 1Kg (One kilo gramme)   |              |
| 7      | 3.00              | Cum | Supply and delivery of 40mm HBG ISS metal including cost and conveyance of all materials to site and all labour charges for filling and all other incidental charges therefore etc complete   |         |       | 1Cum (One cubic meter)  |              |

| Sl. No | Probable Quantity |     | Description of works  | Rate in |       | Per Unit                | Total Amount |
|--------|-------------------|-----|---|---------|-------|-------------------------|--------------|
|        |                   |     |   | Figures | Words |                         |              |
| 8      | 3.00              | Cum | Supply and delivery of 20mm HBG ISS metal including cost and conveyance of all materials to site and all labour charges for filling and all other incidental charges therefore etc complete |         |       | 1Cum (One cubic meter)  |              |
| 9      | 5.00              | Rm  | Supply and delivery of 200mm Dia PVC Pipe including cost and conveyance of all materials to site including all labour charges and all other incidental charges therefore etc complete.      |         |       | 1Rm (One running meter) |              |
| 10     | 2                 | Nos | Supply and Fixing of Ci Manhole including cost and conveyance and all labour charges etc completed  |         |       | Each                    |              |