

[Validate](#)[Print](#)[Help](#)

Item Rate BoQ

Tender Inviting Authority: Block Development officer BP Madathukulam

Name of Work :Strengthening to the Road from Thanthoni Main road to Cheran Nagar road

Contract No: SFC (District Panchayat) 2021-22 - Package 01

Bidder Name :					
<p style="text-align: center;"><u>PRICE SCHEDULE</u></p> <p style="text-align: center; color: red;">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>					
NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #
Sl. No.	Item Description	Quantity	Units	RATE exclusive of GST in figures To be entered by the Bidder (Reffer section 2, ITB, Clause 13.3 of SBD) Rs. P	TOTAL AMOUNT
1	2	4	5	6	7
1.00	Strengthening to the Road from Thanthoni Main road to Cheran Nagar road	1.0000	nos		
2.00	Clearing light Jungles including all labour charges for burrying and burning etc., complete.,	1.0000	nos		
3.00	Km 0/0-0/700	840.0000	sqm		
4.00	Earth work excavation and depositing on bank within initial lead and lift in hard gravelly soil for Cutting side drain etc. complete as per SO 22 A	1.0000	nos		

5.00	Km 0/0-0/700	6.7500	sqm		
6.00	Picking the Existing BT surface including all etc.	1.0000	nos		
7.00	Km 0/0-0/700	885.4200	sqm		
8.00	Collection and supply of gritty gravel from appd quarry including cost and conveyance of all materials to site including all labour charges for spreading etc., complete Shoulders	1.0000	nos		
9.00	Km 0/0-0/700	132.0000	cum		
10.00	Providing and laying 75mm compacted thick WBM Gr.III using 1 cum of 63 mm to 26.50 mm IRC HBG metal and 0.24 cum of Gravel for blindage for 10sqm. Of 75mm compacted thick (the blindage material shall have PI value less than 6%) including cost and conveyance of all materials from approved quarry to worksite and stacking to departmental gauge for pre-measurement as directed by the departmental officers including labour for spreading metal and gravel hand packing to camber and grade lines blinding with required quantity of gravel forming edge bunds watering with all leads for good water slurring rolling and consolidation by power roller and finishing has per MOST 404 (III revision) including hire and fuel charges for power roller and water sprinkler and all other tools and plants employed therefor and all other incidental charges etc., complete for top layer.	1.0000	nos		
11.00	Km 0/0-0/700	199.2200	cum		
12.00	Applying TACK COAT over WBM surface at 4.0Kg/10 sq.m including labour for spraying, hire charges for bitumen sprayer etc., complete	1.0000	nos		
13.00	Km 0/0-0/700	2656.2500	sqm		

14.00	Providing, laying and rolling of open- graded premix carpet of 20 mm thick composed of 13.2 mm to 5.60 mm aggregates eithe using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kn static roller capacity , finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical specification Clause 508.	1.0000	nos		
15.00	Km 0/0-0/760	2656.2500	sqm		
16.00	KM Stone	4.0000	nos		
17.00	HM Stone	9.0000	nos		
18.00	Provision for Name board	1.0000	nos		
19.00	Provision for Sign board	4.0000	nos		
20.00	GST Amount for providing Service to Government Contract Works for the above Construction & Maintenance Works. { GST Amount is the Total GST Amount for overall quoted amount (Both Construction and Maintenance) above this row in column "BB" for all works in this package} (Refer Clause 13.2 & 13.3 of Section 2 of Instruction to Bidders (ITB) of SBD)	1.000	GST Amount		
Total in Figures					