

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: The Commissioner, Pudukkottai Municipality

Name of Work : Providing Mini Power Pump @ Machuvadi Industrial Estate near Sri Balathandayuthapani Murugan kovil in Pudukkottai Municipality.

Contract No : 12625/2021/E1

Bidder Name :						
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>						
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Drilling 150 mm dia borewell in hard rock area with a pilot bore of 150mm dia including labour charges for inserting casing pipe in the drilled bore.	145.00	Rm		0.00	INR Zero Only
2	Supply and delivery of pvc casing pipe AS PER IS 12818 / 2010					
2.01	150 mm dia PVC Casing pipes	36.00	Rm		0.00	INR Zero Only
2.02	250 mm OD PVC Casing Pipes Assembly	6.00	Rm		0.00	INR Zero Only
3	Supply and delivery of Pumpset 15lpm x 125m head-1.5HP single phase submersible pumpset as per 8034/2002 without panel board including all cost and conveyance of all materials and labour charges etc. complete as per standard specifications	1.00	No		0.00	INR Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
4	Erection of power pumps in borewell labour charges for erection of twin packer duplex type jet pumps in borewells upto 150mm dia including fixing of suction pipe regulating valves with jet assembly upto a maximum depth of 30m and delivery pipe valves pressure gauges upto the exterior wall of pump room and erection of panel board consisting of TPICN switches starter,voltmeter, Ammeter, three indicator lamps capacitor and laying and jointing the canles and twin earthing as per IE rules etc., complete and testing the pumps and trail run for 10 days including signing of completion of reports as required by EB authorities and finishing the pipe holes including the foundation bolts, nuts and earth pits.	1.00	No		0.00	INR Zero Only
5	Single phase panel board with two level guard and auto start for 1.5HP motor including all cost and conveyance of all materials and labour charges etc. complete as per standard specifications	1.00	No		0.00	INR Zero Only
6	PVC insulated and sheathed 3 core flat type copper cable 2.5 sq.mm conforming to IS 694/1990	110.00	Rm		0.00	INR Zero Only
7	Supply and delivery of HDPE pipes and specials including all cost and conveyance of all materials and labour charges etc. complete as per standard specifications					
7.01	32mm S.S hook	1.00	No		0.00	INR Zero Only
7.02	32mm S.S hoose collar	1.00	No		0.00	INR Zero Only
7.03	32mm HDPE pipe	85.00	Rm		0.00	INR Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
7.04	Nylon Rope for Bore-well	88.00	No		0.00	INR Zero Only
7.05	GI Hex Nipple 32mm	2.00	No		0.00	INR Zero Only
7.06	32mm GI coupling	1.00	No		0.00	INR Zero Only
7.07	32mm GI Elbow	1.00	No		0.00	INR Zero Only
7.08	GI cover 150mm	1.00	No		0.00	INR Zero Only
7.09	Bore clamp set	1.00	No		0.00	INR Zero Only
8	Construction of pedestal for HDPE tank including cost of 1000 lit tank etc	1.00	No		0.00	INR Zero Only
9	Construction of pedestal for kiosk including cost of kiosk of size 0.75 x 0.45 x .75 etc complete	1.00	No		0.00	INR Zero Only
Total in Figures					0.00	
Quoted Rate in Words		INR Zero Only				