

Narasimmanaickenpalayam Town Panchayat

15 TH FINANCE TIED GRANT 2021-2022

TENDER SCHEDULE

Name of Work : Repairs and Maintenance works to the Community Toilets at Poochiyur road in Narasimmanaickenpalayam Town Panchayat.

Estimate Amount : Rs.650000

Schedule Cost remitted vide Challan no- Date -

Issued to Thiru.

Sl. No.	Probable quantity.		Description of work etc.,	MOT SSRB	Rate in		Unit	Remarks
					Figures	Words		
1	3.00	M ³	Earth work excavation for foundation and depositing on bank with in the initial lead of 10m and a lift of 2m in hard stiff clay, stiff block cotton, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders etc. complete. complying with std. specifications.SS 20 B				one cubic Metre	
2	23.00	M ²	Dismantling,and clearing Floor finish and dadoing walls in cement mortar with Mosaic Tiles / Glazed Tiles / Cuddapah Slabs				one square metre	
3	4.00	M ³	Plain Cement Concrete 1:4:8 Mix (one part cement, Four part M sand and Eight part of aggrigate) using 40mm size ISS HBG metal machine crushed from approved quarry including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing etc. complete. Complying with std. specifications.				one cubic Metre	

Sl. No.	Probable quantity.		Description of work etc.,	MOT SSRB	Rate in		Unit	Remarks
					Figures	Words		
4	23.00	M ²	Supplying and erecting centering to sides and soffits including supports and strutting with necessary cross bracing for plain surface such as RCC slabs rectangular beams all beams lintels etc., centering for soffits upto 3 meter height using mild steel sheet of size 90 cm x 60 cm x 10 mm gauge with MS angles of size 25mm x 25mm x 3mm laid over silver oak (CW) joists of size 10cm x 6cm spaced upto 90cm c/c and casurina props or 10 cm to 13 cm dia spaced at 0.750 cm c/c complying with standard specifications as per TNDSS NO : 30 & 86.				one square metre	
5	1.00	M ³	Cement concrete 1:2:4 mix (One cement, two sand and four aggregate) using 40mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.				one cubic Metre	
6	9.00	M ²	Supplying and fixing over the floors best quality of scratch ceramic tiles of 30 c.m x 30c.m x 6mm size of approved colour laying with cement mortor 1:2 mix pointing the joints with colour pigments etc. Complete.				one square metre	
7	207.00	M ²	Dadoing the walls with glazed tiles of 15 c.m x 15c.m 6mm size laid in cement mortor 1:2 mix 10mm thick and pointing with 0.40 kg white cement etc.,complete., For - 10 sqm				one square metre	

Sl. No.	Probable quantity.		Description of work etc.,	MOT SSRB	Rate in		Unit	Remarks
					Figures	Words		
8	10.00	Nos	Supply and fixing in position 22" Indian type water closet with foot reset includes "P" (or) "S" trap including cost and conveyance of all materials to site and all labour charges etc., to complete as per std., specifications.				one numbers	
9	13.00	M ²	Fabricating, supplying and fixing in position of SOLID PVC DOORS with frames of different sizes as per the specifications given below: PVC door frames made out of best quality PVC extruded section of 40mm * 58 mm * 2.50 mm +/- 0.3 mm thick, having multichamber cross section and duly reinforced with steel to be mitre cut at the corners and welded including providing tie rod at the bottom and necessary weather seal etc., and PVC door shutters made out of extruded plastic section of 60 mm * 24 mm size in the configuration of an "A" section for shutter frames and multi-chamber hollow plastic section of 200 mm * 200 mm * 1 mm (average thickness) with tongue and groove section for panels etc., with necessary holdfasts, rubber beddings, furniture fittings, locking arrangements etc., complete including dismantling the masonry, making chippings, holes in the RCC column, beam etc., wherever necessary with power drill to the extent required and redoing the same to the original condition after fixing etc., complete as per specifications and as directed by the departmental officers.				one square metre	
10	100.00	KG	Supplying and fixing of steel door Including cost of conveyance of all labour charges and materials charges etc., complete.				one kilogram	

Sl. No.	Probable quantity.		Description of work etc.,	MOT SSRB	Rate in		Unit	Remarks
					Figures	Words		
11	178.00	M ²	Painting the new walls two coats over one coat of priming with best Emulsion paint of approved colour and quality including preparation of surface and finishing neatly etc., complete complying with standard specification and as directed by the department officers etc., complete complying with standard specifications.				one square metre	
12	8.00	M ²	Painting two coats new iron work for doors, windows and ventilators using iron bars, window grills weld mesh screen in opt courtyard etc., with two coat synthetic enamel paint and approved quality and color including priming coat in all floors. The rate is inclusive of cost of all materials, labour brushes and scaffolding charges etc., complete complying with standard specifications.				one square metre	
13	73.00	M ²	Providing and laying of 83mm thick high strength type conforming IS 15658-2006 of rubberized interlocking paver block in required sizes of minimum compressive strength of 40 N/mm ² in uniform shape of approved make to be laid in flurrying bone pattern with approved non sticking surface in the top and the rate including leveling the base preparation of sub base with stone dust cushion 100mm thick, laying out the pavement cut the pieces to fit the edge, vibrating the pavers, sweeping transporting, loading unloading and laying of paver block as per standard specification				one square metre	

Sl. No.	Probable quantity.		Description of work etc.,	MOT SSRB	Rate in		Unit	Remarks
					Figures	Words		
14	1.00	nos	Supply and delivery and fixing of HDPE tank as per IS 12701 / 1996 including loading,unloading, transportation and labour charges for fixing of the GI pipes and specials for pipe connection works including cutting, threading and fixing charges etc.,				one numbers	