

SCHEDULE STATEMENT

Schedule Quantities of the work Providing Painting Works in Vimanams & Rajagopuram in Arulmigu Soleeswarar Temple At Muthur, Kangeyam Taluk , Tirupur District.

EMD :-

Tender Value :-

Issued to Thiru :.....

Rs: 14000.00/-

Rs:- 13,97,177.00/-

Date : .....

S.NO	Qty.	Units	Description of Work	MDSS No	Rate Quoted		Unit	Amount
					In Figures	In Words		
1			Scaffolding charges for Vimanans and gopurams with casurina posts coconut or plam trees wherever necessary for main, form work and providing with Non Flamable Shaded coverings, providing ladder arrangements, country wood plant for working, inspection etc, complete hire charges only for erection, maintenance and removing the same on completion of the work1 sq,ft					
	930.00	Sqm	A) Upto 15'0" Height				One Sqm	
	290.00	Sqm	B) Upto 25'0" Height				One Sqm	
	475.00	Sqm	C) Upto 50'0" Height				One Sqm	
2	5125.00	Sqft	Though Scraping the Old lime plaster from the surface of Vimanams and Gopurams, carefully including isolated bricks or brickwork without damaging the vari vargams, racking out the joints, cleaning the surface with water, including all working in heights, hire charges for special tools, brushes complete superficial area including all folds - 100sft.				One Sqft	
3	7606.00	Sqft	Washing the Cutstone for Restoration of the existing natural stone structure.				One Sqft	
4	731.00	Sqm	Pointing the cut stone joints with Lime mortar 1:1.5 20mm thick including cost of special tiles such brush and watering, curing etc complete, as per standard Specifiacations.				One Sqm	

Contractor :

No of Corrections:  
No of over writing:

Executive officer

S.NO	Qty.	Units	Description of Work	MDSS No	Rate Quoted		Unit	Amount
					In Figures	In Words		
5	75.00	Sqm	Clean removal of old cement plaster and Replastering in Special Plastering with cement mortar 1:3,20mm thick over the existing RCC surface including cost and conveyance of all materials, all labour charges and weld mesh of size 7.5x2.5cm of 10Gauge ,curing etc,complete complying with standard specifications.				One Sqm	
6			Painting with multicolour (Panchavarnam) good water based exterior emulson paints complete for the Vinamans/Gopurams, including cost and conveyance of all materials, labour charges including Artist painter, working in heights, lifting of material, cost of brushes etc, complete-which including all extra for foldings-100sft, superficial area.				One Sft	
	340.00	Sqft	<b>A) Kalkaram</b>				One Sqft	
	2415.00	Sqft	<b>B) Vimanam / gopuram of ht. Up to 15'0" excluding Kalkaram</b>				One Sqft	
	700.00	Sqft	<b>C) Vimanam / gopuram of ht. Up to 25'0" excluding Kalkaram</b>				One Sqft	
	2200.00	Sqft	<b>D) Vimanam / gopuram of ht. Up to 50'0" excluding Kalkaram</b>				One Sqft	
7	4.00	Sqm	Removing the machine pressed tiles from the Roof and Finishing the top of roof with one course of existing machine pressed tiles laid in cm 1:3,12mm thick mixed with water proofing compound 2% by weight of cement used etc, complete with standard specifications.				One Sqm	
8	44.00	Sqm	Finishing the top of roof with one course of machine pressed tiles 20cmx 20cmx20mm of approved quality laid in cm 1:3,12mm thick mixed with water proofing compound 2% by weight of cement used etc, complete with standard specifications.				One Sqm	
9	7.00	Sqm	Dismantiling Ac sheet Removing without roof timbers etc.,Complete. SRO Page-22				One Sqm	

Contractor :

No of Corrections:  
No of over writing:

Executive officer

S.NO	Qty.	Units	Description of Work	MDSS No	Rate Quoted		Unit	Amount
					In Figures	In Words		
10	21.00	Sqm	Dismantling, Floor finish and dadoing walls in cement mortar with Mosaic Tiles / Glazed Tiles / Cuddapah Slabs etc.,Complete.				One Sqm	
11	89.00	Sqm	Painting two coat with approved water based Exterior Emulsion over the cement plastered wall surface, ceiling and other new surface including clearing preparing the surface curing in all floors including brushes etc., complete as per specification. -10 m 2 ( S.I. No 358 )				One Cum	

Contractor :

No of Corrections:  
No of over writing:

Executive officer