

SCHEDULE – A
ANNUR TOWN PANCHAYAT
NAMAKKU NAAME THITTAM -2021-2022

Est. No.:
Estimate Amount: **Rs.16,80,000/-**
EMD.Amount :
Tender Date & Time:

Sold to : Thiru.
Challan No.

Date.

Schedule of rates and approximate quantities to accompany the tender for the work of

Construction of Drain at Ward No.13 Thenampalayam Main Road Ammani Aruna nagar in Annur Town Panchayat

- a) The quantities have given are those upon which the lump-sum tender cost at the work is caused but they are subject to alterations, omissions, deductions or additions as provided for in the conditions of the contract and do not necessarily show the actual quantities of the work to be done. The unit of rates noted below are those governing payment for extras or deductions for omission according to the conditions of the contract as set forth in the conditions and specification for the contract.
- b) It is to be expressly understood that the measured work it is to be taken out (Not withstanding any customarily practice to the contrary according to the actual quantities when the place and finished accordingly to the Drawings or as may be ordered time to time by the Town Panchayat Engineer and the cost calculated by works connected there with. The rate quoted is for the works in site and complete in every respect.
- c) The material required for the works must be supplied by the contractor and of the approved quality

Signature of Contractor

TENDER SCHEDULE

Name of work : Construction of Drain at Ward No.13 Thenampalayam Main Road Ammani Aruna nagar in Annur Town Panchayat

Estimate amount: Rs.16,80,000/-

Name of Scheme: NAMAKKU NAAME THITTAM -2021-2022

Sl. No.	Probable Quantity		Description of Work	TNDSS & MORTH Specification No.	Rate		Unit	Amount
					In Figures	In Words		
1	420.00	M3	Earth work excavation for foundation and depositing on bank with in the initial lead of 10m and a lift of 2m in hard stiff clay, stiff block cotton, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders etc. complete. complying with std. specifications.SS 20 B				1 m3 (One Cubic Metre)	

Signature of Contractor

Sl. No.	Probable Quantity		Description of Work	TNDSS & MORTH Specification No.	Rate		Unit	Amount
					In Figures	In Words		
2	33.00	M3	Plain Cement Concrete 1:4:8 Mix (one part cement, Four part sand and Eight part of aggregate) using 40mm size ISS HBG metal machine crushed from approved quarry including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing etc. complete. Complying with std. specifications.				1 m3 (One Cubic Metre)	
3	960.00	M2	Supplying and erecting centering for sides and soffits including supports and strutting upto 3.00m height for plane surface such as RCC Slab, Rectangular Beams, Tee (or) ELL Beams, Lintel Bed Block, Slabs, Landing Slabs, Beams Canopy, Side Slab (or) Square (or) Round columns etc., as detailed below with all cross branching using M.S. Sheets of size 80cm x 60cm and B.G. 10 stiffended with welded M.S. Angles of size 25 x 25 x 3mm for boarding laid over silver oak or country wood joints of 10cm to 30cm to dia spaced at 75cm c/c etc., complete complying with standard specifications as directed by departmental officers etc., complete.				1 m2 (One Square Metre)	

Signature of Contractor

Sl. No.	Probable Quantity		Description of Work	TNDSS & MORTH Specification No.	Rate		Unit	Amount
					In Figures	In Words		
4	167.00	M3	Plain Cement Concrete 1:2:4 Mix (one part cement, two part sand and four part of aggregate) using 20mm size ISS HBG metal machine crushed from approved quarry including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing etc. complete. Complying with std. specifications.				1 m3 (One Cubic Metre)	
5	150.00	M2	Finishing the top of flooring with granolithic floor finish in cement concrete 1:2:4 mix using 10-12mm ISS metal to 25mm thick including cost and conveyance of all materials to site and all labour charges for mixing, laying, curing etc complete				1 m2 (One Square Metre)	

Junior Engineer
Town Panchayats
Annur Group

Signature of Contractor