

TENDER SCHEDULE

NAME OF WORK : Providing 2000 litre capacity PVC Tank and Extention of Pipe line at ward no:13 Kangayampalayam Nadaar colony in Chinnakkampalayam Town Panchayat.

Estimate Amount : Rs.3,00,000/-

| SL. No. | QTY. | | DESCRIPTION OF WORK | TNDSS NO. | RATE IN | | UNIT |
|---------|--------|----------------|--|-----------|---------|-------|---------------------------------------|
| | | | | | Figure | WORDS | |
| 1 | 394.00 | M ³ | Earth work excavating and depositing on bank with initial lead of 10 metre and initial lift of 2 metre in hard stiff clay, stiff block cotton, hard red earth, shales, murrum, gravel, stoney earth and earth mixed with small size boulders as per standard specification | | | | One Cubic Meter |
| 2 | 1.00 | | Plain Cement concrete 1:4:8 mix using 40mm HBG metal for foundation and flooring including cost of all materials to site and all labour charges for mixing, laying and curing etc., complete as per standard specification | | | | One Cubic Meter |
| 3 | 12.00 | | R.R. Masonry in Cm 1:5 mix using rough stone Bond stone including cost & conveyance and all labour charges etc., complete | | | | One Cubic Meter |
| 4 | 4.00 | | Plastering with cement mortal 1:5 mix using 20 mm thick including cost and conveyance of all materials to site and all labour charges etc., complete as per stand specification. | | | | 1M ² (One Square Metre) |

| | | | | | | | |
|---|--------|-----|--|--|--|--|---------------------------------------|
| 5 | 7.00 | | Painting the new walls two coats over one coat of priming with best Emulsion paint of approved colour and quality including preparation of surface and finishing neatly etc., complete complying with standard specification and as directed by the department officers etc., complete complying with standard specifications. | | | | 1M ² (One Square Metre) |
| 6 | | | Supply of PVC PIPE 6 Kg/cm ² and GI Pipes (B Class) including all cost and conveyance. | | | | |
| | 960.00 | M | 90mm dia PVC Pipe | | | | One Meter |
| | #REF! | M | 110mm dia PVC Pipe | | | | One Meter |
| | #REF! | nos | 3)100 mm CI Sluice Valve | | | | One Nos |
| 7 | | | Conveying of PVC right pipe to trench with in a lead of 200m lowering in to a trench carefully laying to proper grad and alignment jointing with PVC couplers with cement paste and testing to the requited pressure including conveyance of water upto 1.00km | | | | |
| | 960.00 | M | 90mm dia PVC Pipe | | | | One Meter |
| | #REF! | M | 110mm dia PVC Pipe | | | | One Meter |

| | | | | | | | |
|---|--------|----------------|--|--|--|--|-----------------|
| 8 | 389.00 | M ³ | Refilling with excavated earth other than sand complying with standard specification. | | | | One Cubic Meter |
| 9 | | | Supply and Delivary of Plastic tankincluding cost & conveyance and all labour charges etc., complete | | | | |
| | 1.00 | | Supply and Delivary of 2000 liter Plastic tank | | | | One Nos |