KOTAGIRI (SPL. GRADE) TOWN PANCHAYAT SCHEDULE – A

Name of the Scheme:

are for works in site and complete in every respect.

SADP - 2021 - 2022

of the work : CONSTRUCTION OF DRAIN AT KOTTAHALL ROAD IN KOTAGIRI TOWN PANCHAYAT						
	Mr. NoDt					
Est. Amount: Rs. 750000.00	Sold to Thriu:					
Tender Date	Executive Officer Kotagiri Town Panchayat					
Contract Value:						
Schedule of rates and approximate quantities to accompany the tender for the work of						
(a) The quantities have given are those upon which the lump sum tender cost of the work is based, but they are subject to alternations, omissions						
deductions of additions a provided for in the conditions of the contract and do not necessarily show the actual quantities of work to be done.						
The unit of rates noted below are those governing payment for extras of deduction for omission according to the conditions of the contract in the						
conditions and specifications for the contract.						
(b) It is to be expressively undertook that the measured work it is to be taken out (not with standing any outstemerly practice to the contrary)						

according to the actual quantities who the place and finished according to the drawing or as may be ordered from time to time. The rates quoted

S. No	Quantity	Description of Work	Units	Rate in Figures	Rate in Words
1	7.00 m3	Dismantaling the existing Damage RR masonry Drain and stacking in materials for reuse and rate including cost conveyance except rock etc., complete complying with standard specification.	One Cubic Meter		
2	119.00 m3	Earthwork excavation for foundation and depositing on Bank within initial lead of 10mt and lift of 2mt of all soil except rock etc., complete complying with standard specification.	One		
3	150.00 m2	Supplying and erection of Steel Centering with strutting and the rate including cost and conveyance of all materials to work site and labour charges etc., complete complying with standard specification	One Sa		
4	17.00 m3	P.C.C.1:4:8 mix using 40mm metal and the rate including cost and conveyance of all materials to work site and labour charges etc., complete complying with standard specification	Cubic		

S. No	Quantity	Description of Work	Units	Rate in Figures	Rate in Words
5	67.50 r	Plain Cement Concrete 1:3:6 Mix (one part cement three part sand and six part of aggrigate) using 20 m size ISS HBG metal from approved quarry includir cost and conveyance of all materials to site. Loading ar unloading charges and labour charges for mixin Laying and curing etc. complete. Complying with st specifications.	one Globic Meter		
6	3.00 r	P.C.C.1:2:4 mix using 20mm metal and the raincluding cost and conveyance of all materials to worsite and labour charges etc., complete complying wirstandard specification	Cubic		

Signature of Contractor.