

SCHEDULE – A
ANNUR TOWN PANCHAYAT

OPERATION AND MAINTENANCE GAP FILLING FUND -2021-2022

Est. No.:
Estimate Amount: **Rs.10,00,000/-**
EMD.Amount :
Tender Date & Time:

Sold to : Thiru.
Challan No.

Schedule of rates and approximate quantities to accompany the tender for the work of

Repairs and Maintenance of the Existing OHT at Ward No.15 Sakkampalayam and Ward No.14 Kumarapalayam in Annur Town Panchayat

- a) The quantities have given are those upon which the lump-sum tender cost at the work is caused but they are subject to alterations, omissions, deductions or additions as provided for in the conditions of the contract and do not necessarily show the actual quantities of the work to be done. The unit of rates noted below are those governing payment for extras or deductions for omission according to the conditions of the contract as set forth in the conditions and specification for the contract.
- b) It is to be expressly understood that the measured work it is to be taken out (Not withstanding any customarily practice to the contrary according to the actual quantities when the place and finished accordingly to the Drawings or as may be ordered time to time by the Town Panchayat Engineer and the cost calculated by works connected there with. The rate quoted is for the works in site and complete in every respect.
- c) The material required for the works must be supplied by the contractor and of the approved quality

ANNUR TOWN PANCHAYAT

TENDER SCHEDULE

Name of work: Repairs and Maintenance of the Existing OHT at Ward No.15 Sokkampalayam and Ward No.14 Kumarapalayam in Annur Town Panchayat

Estimate Amount Rs.10,00,000/-

Schedule Cost remitted vide Challan no-
Date -
Issued to Thiru.

SI · N O.	Probable quantity.		Description of work etc.,	MOT SSRB	Rate in		Unit	Remarks
					Figures	Words		
1			Providing two legged scaffolding using 15cm dia blue-gum posts of 4.0m overall length (3M HT + 0.5M projection + 0.5m into ground) the distance between two rows being 1.25m and the spacing of posts being 2.0m and the spacing of posts being 2.0m in both the rows with two horizontal posts with 0.5m overlap on either side and braces at 2m c/c including longitudinal and transverse middle braces to step up and providing a platform with country wood planks of 40mm tk & 1.0m width in a complete form using color and nails - 1.0m run -- FOR REJUVENATION WORKS					
	58.00	m	0.00 -3.00 m				1 m (One Metre)	
	58.00	m	3.00 -5.50 m				1 m (One Metre)	
	58.00	m	5.50 -8.00 m				1 m (One Metre)	
	58.00	m	8.00 -10.50 m				1 m (One Metre)	

Sl - N o.	Probable quantity.		Description of work etc.,	MOT SSRB	Rate in		Unit	Remarks
					Figures	Words		
	58.00	m	10.50 -12.50 m				1 m (One Metre)	
	38.00	m	12.50 -15.00 m				1 m (One Metre)	
2	628.00	m2	Chipping of Concrete and roughening the existing Damaged cement concrete surface as per standard specification including cost and conveyance of materials to site and all labour charges etc. complete.				1 m ² (One Square Metre)	
3	304.00	m2	Plastering with cement mortar 1:3 mix to 20mm thick including cost and conveyance of all materials to site including curing etc.,complete as per standard specification – 10m2				1 m ² (One Square Metre)	
4	324.00	m2	Plastering with cement mortar 1: 3mix to 12mm thick including cost and conveyance of all materials to site including curing etc.,complete as per standard specification – 10m2				1 m ² (One Square Metre)	
5	1300.00	Kg	Supplying and fixing of M.S grill of approved design for doors, windows and ventilators using necessary mild steel flats for inner and outer members which should be fixed to window frames inclusive of priming coat of best approved quality red oxide primer etc., complete complying with standard specifications.				1 Kg (One Kilo Gram)	

Sl · N o.	Probable quantity.		Description of work etc.,	MOT SSRB	Rate in		Unit	Remarks
					Figures	Words		
6	563.00	M2	Exterior Emulsion paint Two coats with good quality of approved Emulsion paint including cost of all materials to site and all labour charges for mixing applying and proper curring etc., Complete as per Standard Specifications				1 m ² (One Square Metre)	
7	4.00	No	Supplying and fixing of Manhole Cover 60 x 60cm (Heavy Duty) with Frame including cost of all charges etc., complete complying with standard specifications.				1 No (One Number)	
8	2.00	No	Fabrication, supply, delivery and fixing of outsideMS Ladder of 45cm clear wide made out of 50 mm x 50mm x 6mm MS angle for both sides and forsteps at 30cm C/C welded jointed etc ., for Istaging from GL to 1st level brace (weight4.5kg/m) lInd and Illrd staging upto floor slab and IVth staging from floor slab to roof top. Supply,delivery and fixing of 32 mm GI pipes medium forhand rails from I stage to IVth stage. RCC M30Grade mix for Landing slab 5 nos. at Ground Level-1No. and above Ground Level - 4Nos. Supply andfixing of 32mm GI pipe medium for hand rails forthe Landing slab. Supplying and fixing of MS Baseplate of 100mm X 100mm X 6mm thick for fixingAnchore fastener bolt for fixing of hand rails at Landing slab and MS Ladder providing locking arrangements with two coats of approved enamel paint over one coat of red oxide paint as perapproved Type Design and as directed by TWAD board officers.				1 No (One Number)	

Sl · N O.	Probable quantity.		Description of work etc.,	MOT SSRB	Rate in		Unit	Remarks
					Figures	Words		
9	34.00	m2	Painting Two Coats on new Iron works with best synthetic enamel paint of approved colour and quality including cost of all materials to site and all labour charges for mixing applying etc., Complete as per Standard Specifications				1 m ² (One Square Metre)	

Junior Engineer
 Annur Town Panchayat (Group)
 Coimbatore