

<u>SCHEDULE A</u>								
Name of work :			Reconstruction of the Temple Thirumukku Tank wall for Arulmighu Nachiyar (Aandal) Thirukovil, Srivilliputhur Town and Taluk , Virudhunagar District.					
Estimate Value Rs.89,50,000/-			EMD Amount Rs.55,000			Dated Of Tender - 26.04.2022		
S.No	Quantity		Description of Work	TNBP No	Rate	Figures and words	Unit in figures and words	Amount in figures
1	504.00	Sqm	Removing the cutstone members including numbering , hire charges , tools and plants, scaffolding for working in heights etc complete.	SP 1			1 Sqm (One Square Metre)	
	(Five Hundred and Four Square Metre Only)							
2	658.00	Cum	Earth work Open excavation for foundation in all soils and to the full depth as may be directed except hard rock requiring blasting including of shoring strutting and baling water wherever necessary refilling the sides of foundation with excavated earth in layers of 15cm thick well rammed and compacted depositing the surples earth in places shown by the departmental officers with an initial lead of 10 meters and lift 2 meters and clearing and leveling site etc., complete with standard specification.	23 24			1 Cum (One Cubic Metre)	
	(Six Hundred and Fifty Eight Cubic Metre Only)							
3	152.00	Cum	Cement concrete 1:5:10 (one cement five sand and Ten aggregate) using 40mm gauge hard granite broken stone jelly for foundation including cost and conveyance of all materials labour for mixing, laying, compacting, curing, dewatering, side shuttering, wherever necessary including curing etc.,complete complying with standard specification.	23 24			1 Cum (One Cubic Metre)	
	(One Hundred and Fifty Two Cubic Metre Only)							

4			Refixing the cutstone members including hire charges for tools and plants, scaffolding for working in heights and fixing in position including cost and conveyance of all materials and all labour charges etc complete.					
a)	412.00	Sqm	Old stones	SP 1			1 Sqm (One Square Metre)	
	(Four Hundred and Twelve Square Metre Only)							
b)	103.00	Sqm	New stones	SP 1			1 Sqm (One Square Metre)	
	(One Hundred and Three Square Metre Only)							
5	26.00	Cum	Supply of cutstone including cost and conveyance of all materials and all labour charges etc complete.	SP 1			1 Cum (One Cubic Metre)	
	(Twenty Six Cubic Metre Only)							
6	690.00	Cum	Random Rubble Masonry in cement mortar 1:5 [one cement and five sand] using new hard granite stones including providing new bond stones wherever necessary including simultaneous flush pointing of the exposed surface above ground level with the same mortar and all incidental charges such as scaffolding, finishing and curing as directed by the departmental officers etc., complete complying with the standard Specifications.	23 24			1 Cum (One Cubic Metre)	
	(Six Hundred and Ninety Cubic Metre Only)							
7	275.00	Cum	Cement concrete 1:3:6 (one cement Three sand and Six aggregate) using 20mm gauge hard granite broken stone jelly for foundation including cost and conveyance of all materials labour for mixing, laying, compacting, curing, dewatering, side shuttering, wherever necessary including curing etc.,complete complying with standard specification.	23 24			1 Cum (One Cubic Metre)	
	(Two Hundred and Seventy Five Cubic Metre Only)							