

JAGATHALA (SEL.GRADE) TOWN PANCHAYAT
SCHEDULE – A

Name of the Scheme : SADP 2021-2022

Name of the work : Providing footpath at Annai Indra Nagar in Jegathala Town Panchayat

Mr. No.....Dt.....

Est. Amount : Rs. 500000.00

Sold to Thiru:.....

Tender Date

Executive Officer
Jegathala Town Panchayat

Contract Value :

Schedule of rates and approximate quantities to accompany the tender for the work of

(a) The quantities have given are those upon which the lump sum tender cost of the work is based, but they are subject to alternations, omissions deductions of additions a provided for in the conditions of the contract and do not necessarily show the actual quantities of work to be done.

The unit of rates noted below are those governing payment for extras of deduction for omission according to the conditions of the contract in the conditions and specifications for the contract.

(b) It is to be expressly undertook that the measured work it is to be taken out (not with standing any outstemerly practice to the contrary) according to the actual quantities who the place and finished according to the drawing or as may be ordered from time to time. The rates quoted are for works in site and complete in every respect.

S. No	Quantity		Description of Work	Units	Rate in Figures	Rate in Words
1	12.00	m3	Earthwork excavation for Open cutting and depositing on Bank within initial lead of 10mt and lift of 2mt of all soil except rock etc., complete complying with standard specification.	One Cubic Meter		
2	41.00	m3	Earthwork excavation for Foundation and depositing on Bank within initial lead of 10mt and lift of 2mt of all soil except rock etc., complete complying with standard specification.	One Cubic Meter		
3	19.00	m3	P.C.C.1:4:8 mix using 40mm metal and the rate including cost and conveyance of all materials to work site and labour charges etc., complete complying with standard specification	One Cubic Meter		
4	56.00	m2	Supplying and erection of Steel Centering with strutting and the rate including cost and conveyance of all materials to work site and labour charges etc., complete complying with standard specification	One square Meter		
5	30.00	m3	P.C.C.1:3:6 mix using 40mm metal and the rate including cost and conveyance of all materials to work site and labour charges etc., complete complying with standard specification	One Cubic Meter		

6	8.00	m3	P.C.C.1:2:4 mix using 20mm metal and the rate including cost and conveyance of all materials to work site and labour charges etc., complete complying with standard specification	One Cubic Meter		
---	------	----	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------	--	--