

KETTI TOWN PANCHAYAT
SCHEDULE – A

Mr. No.....Dt.....

Name of the Scheme : MLACDS 2021-2022

Name of the work : Supply and Fixing of 60W LED Street Light in Ketti Town Panchayat.

Est. Amount Rs. : 220000.00

Thru:.....

Tender Date :

Executive Officer
Ketti Town Panchayat

Schedule of rates and approximate quantities to accompany the tender for the work of

(a) The quantities have given are those upon which the lump sum tender cost of the work is based, but they are subject to alternations, omissions deductions of additions a provided for in the conditions of the contract and do not necessarily show the actual quantities of work to be done.

The unit of rates noted below are those governing payment for extras of deduction for omission according to the conditions of the contract in the conditions and specifications for the contract.

(b) It is to be expressly undertook that the measured work it is to be taken out (not with standing any outstemerly practice to the contrary) according to the actual quantities who the place and finished according to the drawing or as may be ordered from time to time. The rates quoted are for works in site and complete in every respect.

S. No	Quantity	Description of Work	Units in Figure & words	Rate in Figures	Rate in Words
1	201.00 Nos	Supply and fixing of 60 W LED Street light fitting in the Existing EB Empty Pole system made of pressure die cast aluminium housing with heat resistant toughened glass cover confirming to IP65. Separate compartment for LEDs & electronic driver with CCT of 5700k, PF >0.90 System Efficacy >85 . Operating voltage range of 120V to 270V with surge arrestor minimum of 1 kv. Driver current not less than 700mA, THD< 10%. Lumens package not less 100 LM/w for LED Source. Test certificate from NABL (National accredited board for Testing & Calibration laboratory) for LM79 report. In house Testing facility to be available for the same. Lamp life not less than 50,000 Hours etc ; complete as per standard specification .3 RM Supply and delivery of 3 core 1.50 sqmm Flexible cable with ISI mark. Supply and Delivery of 25 mm dia "B " Class (L Shape) GI Bracket , Supply and Delivery of 7" x 3" x 4 mm RCC Post Clamp Size 50X3mm thickness with 6 Nos of 5/8 " Full thread 2 " MS Bolt nuts. Labour charges for Fixing of New 60 W LED Lamp fittings complete set and including all necessary items. As directed by departmental officers etc Complete.	One Number		

(Schdule Approved for item 1 to 1 only)

Signature of Contractor.