

**KETTI TOWN PANCHAYAT**  
**SCHEDULE – A**

**Name of the Scheme :** S.A.D.P 2021-2022

**Name of the work :** IMPROVEMENTS TO MUKKATTY ROAD IN KETTI TOWN PANCHAYAT.

Mr. No.....Dt.....

**Est. Amount :** Rs. 2000000.00

Sold to Thiru:.....

**Tender Date**

**Executive Officer**  
**Ketti Town Panchayat**

**Contract Value :**

Schedule of rates and approximate quantities to accompany the tender for the work of

(a) The quantities have given are those upon which the lump sum tender cost of the work is based, but they are subject to alternations, omissions deductions of additions a provided for in the conditions of the contract and do not necessarily show the actual quantities of work to be done.

The unit of rates noted below are those governing payment for extras of deduction for omission according to the conditions of the contract in the conditions and specifications for the contract.

(b) It is to be expressively undertook that the measured work it is to be taken out (not with standing any outstemerly practice to the contrary) according to the actual quantities who the place and finished according to the drawing or as may be ordered from time to time. The rates quoted are for works in site and complete in every respect.

S. No	Quantity	Description of Work	Units	Rate in Figures	Rate in Words
1	191.00 m3	Earthwork excavation in all soils and sub soils except hard rock requiring blasting with initial lead and lift including re-filling the sides of foundation in layer of 15 cm thick watering , ramming ,depositing the surplus earth in the premises as directed by departmental officers etc., complete as per standard specification. as per SS 20 B TNDSS NO: 23&24VI (S2), VII 9,10	One Cubic Meter		
2	80.00 m2	Supplying and erecting centering to sides and soffits including supports and strutting for drainage sides and culvert body wall sides using 90cm x 60cm and B.G 10stifened with welded mild steel angles of size 25mm x 25mm x 3mm for boarding laid over( silver oak joists ) of size 10cm x 6.50cm spread at about 90cm including all labour charges and cost and conveyance of all materials to site etc. complete complying with standard specification.TNDSS NO: 30&46J V, VI	One Square Meter		
3	145.00 m3	four sand and eight aggregates) using 40 mm ISS HBG metal including cost and conveyance of all materials to work site and all labour charges for mixing, laying,consolidating and curing etc complete as per the standard specifications. TNDSS NO: 28 V, VI (S2) V,VI (S5A) VII	One Cubic Meter		
4	98.00 m3	Plain Cement concrete in 1:2:4 (one cement , two sand and Four aggregate) mix using 20mm ISS hard broken granite metal including cost and conveyance of all materials to work site and all labour charges etc., for mixing laying , consolidating,levelling and curring etc., complete complying with as per standard specifications. TNDSS NO: 30 V,VI (S3) VII-3	One Cubic Meter		

5	7.00	m2	Provision Made For 12 MM Thick Bitumen Pad The Rate Including The Cost And Conveyance Of All Materials And Labours To site Etc Complete,Copmplying With Standard Specification.	One Square Meter		
---	------	----	---	------------------	--	--

**Signature of Contractor.**