

## TENDER SCHEDULE

NAME OF WORK : Providing CC Pavement at RR Park in Alangulam Town Panchayat.

**Estimate Amount Rs. 9.58 Lakhs**

Sl. No.	Quantity	Description of woks	Unite	Rate in	
				Figure	Words
1	49.00 Cum	Collection supply and filling of well gravel filling approved quarry including cost and Conveyance of all materials to site and all labour charges for filling etc., Complete.	1m3 (One Cubic metre)		
2	49.00 Cum	Providing and laying, spreading and compacting graded stone aggregates to Wet Mix Macadam 250mm thick specification including premixing the materials with water at OMC in mechanical mix plant carriage of mixed material by tipper to site laying in uniform layers with pavers in Sub Base/ Base course on well prepared surface and compacting with vibratory roller to acheive the desired density including cost of material, labour charges, rentals for machinery, fuel and all other incidental charges etc., complete as per clause 406 of MORTH	1m3 (One Cubic metre)		
3	24.00 Cum	Earth work excavation for Drain work including all labour charges etc, complete.	1m3 (One Cubic metre)		

Sl. No.	Quantity	Description of woks	Unite	Rate in	
				Figure	Words
4	39.00 Cum	P.C.C 1:4:8 mix (One Cement, Four Sand and Eight Aggregate) using 40mm HBG ISS metal including all cost and conveyance of materials to site and all labour charges etc, complete.	1m3 (One Cubic metre)		
5	182.00 Sqm	Centering for soffits of PCC Plain Surface works including all cost and conveyance of materials to site and all labour charges etc, complete.	1m2 (one square metre)		
6	28.00 Cum	Plain Cement Concrete 1:2:4 Mix (one part cement, two part sand and four part of aggrigate) using 20mm size ISS HBG metal machine crushed from approved quarry including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing etc., complete as per TNDSS NO: 28 & VI (S2) VI (S5A) VII standard specifications as directed by Engineer incharge.	1m3 (One Cubic metre)		
7	37.00 Cum	P.C.C 1:1.5:3 mix (One part of Cement, 1.5 part of Sand and three part of Aggregate) using 20mm HBG ISS metal including all cost and conveyance of materials to site and all labour charges etc, complete.	1m3 (One Cubic metre)		
8	13.00 Sqm	Providing Bitumen Pad 12mm thick for Expansion Joint including cost and conveyance of all other labour and material charges to site etc., complete.	1m2 (one square metre)		

Sl. No.	Quantity	Description of woks	Unite	Rate in	
				Figure	Words
9	364.00 Sqm	CC Road Top Serface Finishing with Power Travellor Machine Including Cost of all Labour charges etc.complete	1m2 (one square metre)		

(Approved 1- 9 items only)