## SALEM CITY MUNICIPAL CORPORATION TENDER SCHEDULE

				_					
N	lam	Δ.	∩t		nn	tro	201	∩r	•
ı	ıaııı	<b>C</b>	vı.	v	911	LIC	ıvı	vı	

EMD Details Rs.33,000/-

Tender Date 06.05.2022

Name of Work:

Providing SS Hand Rail arrangements at Bharath Rathna Dr MGR Central Bus Stand Town Bus Terminal in Div.24, Salem City Municipal

Corporation

Est. No. E4/Est No: 459/B/2021-2022

Estimate Cost Rs.33.00 Lakhs

- 1. The Quantities here given are those upon the lump sum tender cost of work is based, but they are subject to alterations, omissions, deductions or additions as provided for the conditions of the contract and do not necessarily show the actual quantities of work to be done. The unit rates are those governing payment for extracts or deductions for omissions according to the contract, as set forth in the preliminary specifications of the (Madras Detailed Standard Specifications) Tamil Nadu building practice and other conditions or specifications of the contract.
- 2. It is to be expressly understood that the measured work is to be taken nett (not with standing any custom or practice to the contrary) according to the actual quantities when in place and finished according to the drawing or as may be ordered from time to time by the Corporation Engineer and the cost calculated by measurement of weight, of the respective prices, with out additional charge for any necessary contingent works connected herewith. The Rates quoted are for works in 'situ' and complete in every respect.
  - 3. The work must be completed with in Days/Month from the date of receipt of acceptance of this tender.

Item	m Probable Quantity		Description of Work	Rate	l.	Unit in	Amount in
No	Figures	Units	Description of Work	Words	Figures	Words	Figure
1	1250.00	Kg	Supplying and fixing of M.S Grill works including all labour and material charges with one coat red oxide primer etc.,complet as per standard specification			Kg	
2	2270.00	Sft	Supply and planting Grass cover Zoycia Matrella as per plant list to be done over RCC grid pavers with a mix of 50mm thick layers of soil and manure consisting of 1 part of top soil earth, 1 part of river sand and organic manure/compost and grass seed. This mix to be filed uniformly in the gaps of RCC paver grids. The rate includes transportation of plants, loading, unloading at site, manuring, intial watering, cutting, trimming, soil racking, weeding and soil tilting			Sft	
3			Supply and Plantation of the following plants including Cost and Coveyance of Red Gravel, Mannure and Fertilisers etc., complete.				
	60.00	Nos	Areca Palm			Nos	

11.00	Nos	Odicka Palms		Nos	
25.00	Nos	Surul Palms		Nos	
2.00	Nos	fountain palms		Nos	
2.00	Nos	Cycas Plant		Nos	
1.00	Nos	Traveller's Tree		Nos	

25.00	Nos	Tecoma Orange		Nos	
25.00	Nos	Tecoma Yellow		Nos	
5.00	Nos	Paper flower plant		Nos	
4.00	Nos	Red Palms		Nos	
25.00	Nos	Ixora Plant		Nos	

	6.00	Nos	Jatropha Plant		Nos	
	25.00	Nos	Phycos Plant		Nos	
	2.00	Nos	adenium plant Big		Nos	
	4.00	Nos	adenium plant Small		Nos	
4			Supply and Delivery of following specials with ISI making as per standard specifications (MEDIUM)			

282.00	Rm	32 mm UPVC Pipe		Rm	
120.00	Rm	25 mm UPVC Pipe		Rm	
50.00	Rm	20 mm UPVC Pipe		Rm	
15.00	Rm	32 mm UPVC Elbow		Rm	
14.00	No	32 mm UPVC Tee		No	

14.00	No	32 mm UPVC Union		No	
15.00	No	25 mm UPVC Elbow		No	
15.00	No	25 mm UPVC Tee		No	
15.00	No	25 mm UPVC Union		No	
14.00	No	20 mm UPVC Elbow		No	

14.00	No	20 mm UPVC Tee		No	
14.00	No	20 mm UPVC Union		No	
30.00	No	32 mm UPVC Coupler		No	
15.00	No	25 mm UPVC Coupler		No	
10.00	No	20 mm UPVC Coupler		No	

	15.00	No	32 mm x 25 mm Reducer		No	
	15.00	No	25 x 20 mm Reducer		No	
	28.00	No	20 x 15 mm Reducer		No	
5	392.00	m2	Manufacturing, Supplying and Fixing of Stainless Steel Hand rails for staircase using 50mm dia 304L Grade Stainless Steel pipe of 1.60mm thick at required locations to a height of 900mm from finished floor level welded to 38mm dia Stainless Steel pipe post of 1.00mm thick as vertical at 900mm centre with 2 Nos. of 25mm dia intermediate horizontal stainless steel pipe of 1.60mm thick in between. The vertical pipe has to be welded to the 100 X 100 X 6mm MS base plate encased in the base concrete. The rate is inclusive of the charges for cutting, bending, welding, grinding, polishing, conveyance, electrical charges, etc. complete (as per P.No.54 PWD SOR)		m2	