

# KATTUMANNARKOIL TOWN PANCHAYAT - CUDDALORE DISTRICT

## TENDER SCHEDULE

Issued to Thiru/Tmt-----

Estimate Amount: Rs.5000000/-  
EMD Amount : Rs 50000/-  
Tender Date : 29.04.2022

**Executive officer**  
**KATTUMANNARKOIL Townpanchayat**

### **SCHEDULE OF QUANTITIES RATES AND APPROXIMATE QUANTITIES TO ACCOMPANY THE WORK OF Renovation of Bus Stand Area in Kattumannarkoil Town Panchayat.**

#### **SCHEDULE- A**

**A)** The quantities given here those upon which the lump sum tender cost of the work is based but they are subject to alterations, omissions, deductions or additions & are provided for in the conditions of the contract and do not necessarily be so to the actual quantities of work to be done. The unit rates noted below are those governing payment for extras or deductions or omissions according to the conditions of the contract as set forth in the conditions and specifications for the contract.

**B)** It is to be expressly understood that the measured work is to be taken out notwithstanding any customary practice to be contrary according to the actual quantities when the place and finished according to the drawings are as may be ordered from time to time by the Engineer and the cost calculated by the measurement to weight at the respective price with out any additional charges for necessary the contingent works connected there with. The rates quoted are for works in site and complete in every respect.

SL. No	Qty	<u>Description of Items</u>	Per	SSRB MDSS No	<u>Rate</u>		Unit Per	Amount in Rupees
					In figures	In Words		
1	2	3		4	5	6	7	8
1	280.00	Reinforced Cement Concrete 1:1½:3 Mix (One part cement, one and half part sand and three part of aggregate) using 20mm size ISS HBG metal machine crushed from approved quarry including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing but excluding cost of reinforcement etc. Complete with std. Specifications. (Using Vibrator) TNDSS NO: 30 V, VI (S3), VII-3.	m2				1 m2 (One Square Metre)	
2	5000.00	Supplying and fabrication of steel and placing in position of TMT steel rods for RCC works as per design given including cost of steel and GI binding wire in all floors etc., complete complying with standard specification in TNDSS NO: 97 V, VI (S6) VII (S6),	m2				1 m2 (One Square Metre)	

**Signature of Contractor**

SL. No	Qty	<u>Description of Items</u>	Per	SSRB MDSS No	<u>Rate</u>		Unit Per	Amount in Rupees
					In figures	In Words		
1	2	3		4	5	6	7	8
3	2320.00	Plastering in Cement Mortar 1:3 Mix (one cement, Three sand ) 12 mm thick including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing etc. complete. Complying with std. specifications.	m2				1 m2 (One Square Metre)	
4	47.00	Weathering course concrete with broken brick jelly of 20 mm gauge in pure slacked lime ( no sand to be added) over roof slab the proportion of brick jelly to lime being 32:12.5 by volume and laid over In a single layer and consolidated require designed and finished thickness by beating the concrete with wooden beaters of approved pattern , keeping the surface constantly with springing lime jiggery water asper standard specification and as directed by the departmental officers Complete as per standard specification.	m3				1 m3 (One Cubic Metre)	
5	580.00	Finishing with top of roof with one course of machine pressed tiles of size 20cmx20cmx2cm of approved quality laid in cement mortar 1:3 (One part of cement and three part of sand) 12mm thick mixed with water proofing compound conforming to ISS by 2% weight of cement used and the joint pointed neatly to full depth of tiles with same water proofing compound mixed with cement motar ,red oxide, etc Complete as per standard specification.	m2				1 m2 (One Square Metre)	
6	2320.00	Exterior Emulsion paint Two coats with good quality of approved Emulsion paint including cost of all materials to site and all labour charges for mixing applying and proper curring etc., Complete as per Standard Specifications for 10 sqm	m2				1 m2 (One Square Metre)	

**Signature of Contractor**