

SCHEDULE – A

PERIYANAICKENPALAYAM TOWN PANCHAYAT

Est. No.:

Estimate Amount: **Rs.75.40 lakhs**

EMD.Amount :

Tender Date & Time:

Sold to : Thiru.

Challan No.

Date.

Schedule of rates and approximate quantities to accompany the tender for the work of

Name of work : Processing of BIO MINING the Dumping of Historical Waste at Resource Recovery Park in Periyanaickenpalayam Town Panchayat.

- a) The quantities have given are those upon which the lump-sum tender cost at the work is caused but they are subject to alterations, omissions, deductions or additions as provided for in the conditions of the contract and do not necessarily show the actual quantities of the work to be done. The unit of rates noted below are those governing payment for extras or deductions for omission according to the conditions of the contract as set forth in the conditions and specification for the contract.
- b) It is to be expressively understood that the measured work it is to be taken out (Not withstanding any customarily practice to the contrary according to the actual quantities when the place and finished accordingly to the Drawings or as may be ordered time to time by the Town Panchayat Engineer and the cost calculated by works connected there with. The rate quoted is for the works in site and complete in every respect.
- c) The material required for the works must be supplied by the contractor and of the approved quality

TENDER SCHEDULE

Name of work **Processing of BIO MINING the Dumping of Historical Waste at Resource Recovery Park in Periyanaickenpalayam Town Panchayat.**

Estimate amount: Rs.75.40 lakhs

Name of Scheme: SWM - 2019-2020

Sl. No.	Probable Quantity		Description of Work	TNDSS & MORTH Specificati on No.	Rate		Unit	Amount
					In Figures	In Words		
			a) Excavation the existing mixed compacted Garbage which underwent biological degradation in the land portion allocated / earmarked by Karamadai Town Panchayat Compost Yard and spraying with microbial innoculam for sanitizing and stabilizing the excavated mass sieving them using Mechanical Seiving machine or any other equipment at the cost of the Bidder					

Sl. No.	Probable Quantity		Description of Work	TNDSS & MORTH Specificati on No.	Rate		Unit	Amount
					In Figures	In Words		
1	11587.00	M3	<p>(b) Control of mal odour using Deodorizing agent and stabilizing the waste using Bio Culture for aerobic composting using industrial sprayer Eco friendly and non pollution process in order to reduce the impact of dumping site in the adjacent areas</p> <p>Segregate the excavated garbage in the land portion earmarked, into as many kind and categories as possible at the cost of the Bidder including cost of any power or fuel consumption</p> <p>Selling, diverting for recycling marketing and recycling the excavated materials</p> <p>Cleanly rehanded over the site including clean removal of any residue from the site including conveyance away from the Karamadai Town Panchayat limit and handling ovet the earmarked site by the Town Panchayat including cost and conveyance and handling labour charges etc complete</p> <p>Creation and maintenance of infrastructure facilities and amenities at Bidder's risk and cost, for sieving, the excavated garbage, storing the segregation materials</p> <p>Deployment of necessary manpower, materials, equipments tools and construction of plants and sheds and creation of facilities for handling, separating, segregation and storing for the operation of the plant</p> <p>Leveling the earth surface by bull-dozer or any other earth moving equipment</p> <p>Providing security arrangement for the plan project site, machineries, equipment etc, at the cost of the Bidder</p>				1 M3 (One Cubic metre)	

Junior Engineer
Town Panchayats
Coimbatore District