

Validate

Print

Help

Item Rate BoQ

Name of Work : Renewal to the Road from Vaikkalmettupuduhr to Kangeyampalayam road H/O Velampalayam Km 0/0-1/4 (Working Length : km 0/0-1/185) (R 314)

Contract No: 15th Finance Basic Untied Grant 2021-2022

Bidder Name :	
---------------	--

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #
Sl. No.	Item Description	Quantity	Units	RATE exclusive of GST in figures To be entered by the Bidder (Reffer section 2, ITB, Clause 13.3 of SBD) Rs. P	TOTAL AMOUNT
1	2	4	5	13	54
1.00	Renewal to the Road from Vaikkalmettupuduhr to Kangeyampalayam road H/O Velampalayam Km 0/0-1/4 (Working Length : km 0/0-1/185) (R 314)	1.0000	nos		
2.00	Clearing the Light jungle including all labour charges for burying and burning etc., complete.	1.0000	nos		
3.00	Km 0/0 - 1/185	711.0000	sqm		
4.00	Earth work excavation and depositing on bank within initial lead and lift in hard gravelly soil for Cutting side	1.0000	nos		

5.00	Km 0/0 - 1/185	455.6300	cum		
6.00	Collection and supply of gritty gravel from appd quarry including cost and conveyance of all materials to site including all labour charges for spreading and compaction with power roller etc.complete, for SHOULDERS	1.0000	nos		
7.00	Km 0/0 - 1/000	168.0000	cum		
8.00	Km 1/0 - 1/185	33.3000	cum		
9.00	Picking 5 cm to 10 cm old metalled surface and sectioning in all etc complete	1.0000	nos		
10.00	Km 0/0 - 1/100	93.7500	cum		
11.00	Providing and laying 75mm compacted thick WBM Gr.III using 1 cum of 63 mm to 26.50 mm IRC HBG metal and 0.24 cum of Gravel for blindage for 10sqm. Of 75mm compacted thick (the blindage material shall have PI value less than 6%) including cost and conveyance of all materials from approved quarry to worksite and stacking to departmental gauge for pre-measurement as directed by the departmental officers including labour for spreading metal and gravel hand packing to camber and grade lines blinding with required quantity of gravel forming edge bunds watering with all leads for good water slurring rolling and consolidation by power roller and finishing has per MOST 404 (III revision) including hire and fuel charges for power roller and water sprinkler and all other tools and plants employed therefor and all other incidental charges etc., complete for top layer.	1.0000	nos		
12.00	Km 0/0 - 1/000	21.0900	cum		

14.00	Providing and laying TACK COAT over the WBM surface using 4 Kg of bituminous emulsion for 10 sqm. including cost of bituminous emulsion which will be supplied by the department at section stores and its cost will be recovered as per special condition appended including labour charges for preparing the surface for laying tack coat and for applying required quantity of bituminous emulsion by mechanical sprayer including hire and fuel charges for all tools and plants employed etc., complete as per clause 503 of MOST specification.	1.0000	nos		
15.00	Km 0/0-1/10	281.2500	sqm		
14.00	Providing and laying TACK COAT over the BT surface using 3 Kg of bituminous emulsion for 10 sqm. including cost of bituminous emulsion which will be supplied by the department at section stores and its cost will be recovered as per special condition appended including labour charges for preparing the surface for laying tack coat and for applying required quantity of bituminous emulsion by mechanical sprayer including hire and fuel charges for all tools and plants employed etc., complete as per clause 503 of MOST specification.	1.0000	nos		
15.00	Km 0/0-1/185	4258.1300	sqm		

16.00	Providing, laying and rolling of open- graded premix carpet of 20 mm thick composed of 13.2 mm to 5.60 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kn static roller capacity , finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical specification Clause 508.	1.0000	nos		
17.00	Km 0/0 - 1/000	3761.2500	sqm		
18.00	Km 1/0 - 1/185	778.1300	sqm		
19.00	Provision for KM stones	1.0000	no		
20.00	Provision for HM stones	4.0000	no		
27.00	Provision for Name boards	1.0000	RM		
28.00	Provision for Sign boards	2.0000	no		
29.00	GST Amount for providing Service to Government Contract Works for the above Construction & Maintenance Works. { GST Amount is the Total GST Amount for overall quoted amount (Both Construction and Maintenance) above this row in column "BB" for all works in this package} (Refer Clause 13.2 & 13.3 of Section 2 of Instruction to Bidders (ITB) of SBD)	1.000	GST Amount		
Total in Figures					
Quoted Rate in Figures			Select		0.0000
Quoted Rate in Words		#NAME?			