

SALEM CITY MUNICIPAL CORPORATION

TENDER SCHEDULE

Name of Contractor :

EMD Details **Rs.3,700/-**

Tender Date **10.05.2022**

Name of Work **Extension of Pipe line for Improvement of Water supply at Karuvattu mandi main road from Toilet to Apna maruthi service in Division no - 47 & 48 @ Kondalampatty Ward office.**

Est. No. **E2/Est No: 467/WS/2021-2022**

Estimate Cost **Rs.3,70,000/-**

1. The Quantities here given are those upon the lump sum tender cost of work is based, but they are subject to alterations, omissions, deductions or additions as provided for the conditions of the contract and do not necessarily show the actual quantities of work to be done. The unit rates are those governing payment for extracts or deductions for omissions according to the contract, as set forth in the preliminary specifications of the (Madras Detailed Standard Specifications) Tamil Nadu building practice and other conditions or specifications of the contract.

2. It is to be expressly understood that the measured work is to be taken nett (not with standing any custom or practice to the contrary) according to the actual quantities when in place and finished according to the drawing or as may be ordered from time to time by the Corporation Engineer and the cost calculated by measurement of weight, of the respective prices, with out additional charge for any necessary contingent works connected herewith. The Rates quoted are for works in 'situ' and complete in every respect.

3. The work must be completed with in Days/Month from the date of receipt of acceptance of this tender.

SIGNATURE OF THE CONTRACTOR

Item No	Probable Quantity		Description of Work	Rate		Unit in	Amount in
	Figures	Units		Words	Figures	Words	Figure
			Pipe line area				
1	240.00	m3	Earth work excavation and depositing on bank with initial lead of 10 m and lift of 2 M in narrow trenches having bed width 1.25m & below for laying of pipes for water supply and sewerage works in the following type of soils as directed by Departmental officers Sand, silt or other loose soil, wet sand or silt not under water light black cotton soil, sandy loam and ordinary soil.SS20B			m3	
2			Supply and delivery of the following Pipes and Specials including all cost and conveyance etc., complete and as per s.s.				
	318.00	RM	160mm PVC Pipe 6 KSC			RM	
	60.00	RM	110mm PVC Pipe 6 KSC			RM	

SIGNATURE OF THE CONTRACTOR

	3.00	Nos	160mm PVC Bend			Nos	
	2.00	Nos	160mm PVC Elbow			Nos	
	2.00	Nos	160mm PVC Tee			Nos	
	3.00	Nos	110mm PVC Bend			Nos	

SIGNATURE OF THE CONTRACTOR

	2.00	Nos	110mm PVC Elbow			Nos	
	2.00	Nos	110mm PVC Tee			Nos	
	3.00	Nos	150mm Sluice Valve with Flange Socket			Nos	
	60.00	Kgs	Rubber Sheet			Kgs	

SIGNATURE OF THE CONTRACTOR

	45.00	Kgs	Bolt nut washer			Kgs	
	30.00	Kgs	Rendroc Cement			Kgs	
	15.00	Lit	Hard grade oil			Lit	
	15.00	Lit	Solvent Cement			Lit	
3	378.00	RM	Lowering PVC/ DWSC rigid pipes and specials to trench and laying to proper grade and alignment, jointing with PVC couplers with cement paste 180mm to 250mm dia (OD) PVC pipe			RM	
4	240.00	m3	Refilling with excavated soil (other than sand) complying with the standard specification for filling in foundation and basement			m3	

SIGNATURE OF THE CONTRACTOR