

SALEM CITY MUNICIPAL CORPORATION

TENDER SCHEDULE

Name of Contractor :

EMD Details **Rs.1,200/-**

Tender Date **06.05.2022**

Name of Work **Additional Works to the Electrical and Plumbing works of ABC Building at Veeranam Compost Yard Campus Ammapet Ward Office in D.No.9.**

Est. No. **E3/Est No: 426/2021-2022**

Estimate Cost **Rs.1,20,000/-**

1. The Quantities here given are those upon the lump sum tender cost of work is based, but they are subject to alterations, omissions, deductions or additions as provided for the conditions of the contract and do not necessarily show the actual quantities of work to be done. The unit rates are those governing payment for extracts or deductions for omissions according to the contract, as set forth in the preliminary specifications of the (Madras Detailed Standard Specifications) Tamil Nadu building practice and other conditions or specifications of the contract.

2. It is to be expressly understood that the measured work is to be taken nett (not with standing any custom or practice to the contrary) according to the actual quantities when in place and finished according to the drawing or as may be ordered from time to time by the Corporation Engineer and the cost calculated by measurement of weight, of the respective prices, with out additional charge for any necessary contingent works connected herewith. The Rates quoted are for works in 'situ' and complete in every respect.

3. The work must be completed with in Days/Month from the date of receipt of acceptance of this tender.

SIGNATURE OF THE CONTRACTOR

Item No	Probable Quantity		Description of Work	Rate		Unit in	Amount in
	Figures	Units		Words	Figures	Words	Figure
1	24.00	Each	Wiring with 2x1.5 sq.mm. (22/0.3) PVC insulated SC unsheathed copper conductor of 1100V grade insuitable PVC rigid pipe on wall and ceiling with PVC accessories with suitable TW box in flush with wall to house the control switch regulator and covered with 3mmthick hylemsheet with painting of suitable colour with continuous earth connection of 14 SWG TC wire for open PVC fan point (for rheostatic type fan regulator) (SD.NO.34)			Each	
2	4.00	Each	Supplying and fixing of 4' 18W Crystal Glass LED Tube light Fitting			Each	
3	9.00	Each	Supply and fixing of 1200mm (48") sweep AC ceiling fan complete with stepped electronic 300W regulator with 1 metre down rod with fan clamp with side plates and cross arm of size 450mm (18") etc, complete.(SD 106)			Each	
4	9.00	Each	Supplying and fixing of AC Exhaust Fan 225mm (9") Sweep (Light Duty)			Each	

SIGNATURE OF THE CONTRACTOR

5	2.00	Each	Wiring with 2x1.5 sq.mm (22/0.3) PVC insulated SC unsheathed copper conductor of 1100V grade insuitable PVC rigid pipe onwall and ceiling with PVC accessories with 150x100x113mm TW sitchbox for 5A 3pin non interlocking Wall socke twith 5A flush type switch with painting of suitable colour with continuous earth wire connection of 14 SWG TC wire for open PVC plug point (SD-36)			Each	
6	4.00	Each	Supply and fixing of 4'40W twin street light fluorescent fitting complete with copper choke and condensor with 19mm dia Glpipe (Class'B') with1No.19mm GI bend complete on the existing post/wall with16A aerial fuse unit on MS plate with PVC unsheathed copper leads with MS clamps and aluminium painting with fluorescent tubes (SD-94)			Each	
7			Supplying and Stacking the PVC Pipes and Specials with ISI make etc, complete.				
	9.00	Rm	160mm PVC Pipe			Rm	
	3.00	Each	160mm PVC Elbow			Each	

SIGNATURE OF THE CONTRACTOR

	6.00	Each	20mm Brass Ball Valve			Each	
	50.00	Rm	25mm PVC Pipe			Rm	
	20.00	Each	25mm PVC Elbow			Each	
	6.00	Each	25 x 15 mm PVC Reducer			Each	

SIGNATURE OF THE CONTRACTOR