

**SALEM CITY MUNICIPAL CORPORATION**

**TENDER SCHEDULE**

**Name of Contractor :**

**EMD Details**                **Rs1,900/-**

**Tender Date**                **06.05.2022**

**Name of Work**                **Providing Fencing Compound, Construction of Borewell Chamber, Painting of Compound wall and Gravel filling at Veeranam Compost Yard low lying areas Campus Ammapet Ward Office in D.No.9.**

**Est. No.**                        **E3/Est No: 425/2021-2022**

**Estimate Cost**                **Rs.1,90,000/-**

1. The Quantities here given are those upon the lump sum tender cost of work is based, but they are subject to alterations, omissions, deductions or additions as provided for the conditions of the contract and do not necessarily show the actual quantities of work to be done. The unit rates are those governing payment for extracts or deductions for omissions according to the contract, as set forth in the preliminary specifications of the (Madras Detailed Standard Specifications) Tamil Nadu building practice and other conditions or specifications of the contract.

2. It is to be expressly understood that the measured work is to be taken nett (not with standing any custom or practice to the contrary) according to the actual quantities when in place and finished according to the drawing or as may be ordered from time to time by the Corporation Engineer and the cost calculated by measurement of weight, of the respective prices, with out additional charge for any necessary contingent works connected herewith. The Rates quoted are for works in 'situ' and complete in every respect.

3. The work must be completed with in    Days/Month from the date of receipt of acceptance of this tender.

SIGNATURE OF THE CONTRACTOR

Item No	Probable Quantity		Description of Work	Rate		Unit in	Amount in
	Figures	Units		Words	Figures	Words	Figure
1	1.00	m3	Earthwork Excavation for foundation in all types of soils and sub soils including soft disintegrated rock and soft rock to the full depth including all leads and lifts etc., complete			m3	
2	250.00	m3	Collection,supply and filling of Well gravel from approved quarry to work site and stocking to the Departmental gauge for premeasurement as directed by the Departmental Engineer, to required depth not more than 15cm depth including cost and Conveyance of gravel to site and all labour charges for filling etc., Complete complying with Standard Specification			m3	
3	1.00	m3	Cement concrete of mix 1:4:8 (one cement – four sand – Eight broken stone) using Hard broken granite stone jelly of 40 mm gauge for foundation leveling course. Including cost and conveyance of all materials to working site, laying concrete and curing etc.			m3	
4	0.50	m3	Plain cement concrete 1:2:4 mix (One cement two sand and four aggregate) using 20mm size ISS gauge HBBG metal including mixing, laying, consolidating, curing, cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification			m3	

SIGNATURE OF THE CONTRACTOR

5			Brick work in cement mortar 1:5 mix using Fly Ash bricks of 230x110x70mm (8 3/4" x 4 1/4" x 2 3/4") from approved quarry including cost and conveyance of all materials to site. Loading and unloading charges and labour charges for mixing, laying and curing etc. complete. Complying with std. specifications				
	0.60	m3	upto Basement			m3	
6	8.00	m2	Plastering with cement mortar 1:5 mix, 12mm thick including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing etc. complete . complying with std. specifications			m2	
7	490.00	m2	Painting two coats with approved cement paint over cement plastered surface ceiling and other new surface including cleaning prepering the surface and curing etc., complete			m2	

SIGNATURE OF THE CONTRACTOR

8	160.00	Kg	Supplying, fabricating, erecting structural steel work for roofing welded or bolted type using MS channels, angles, plates and round bars etc. conforming to IS specification including primer coating as per Design given by the departmental officers etc, complete as per standard specification			Kg	
9	33.00	m2	Providing Chain Link - 2" x 2" using 10 Gauge Galvanised Iron Wire (of all sizes) fencing with necessary binding wire etc., complete			m2	

SIGNATURE OF THE CONTRACTOR