

TENDER SCHEDULE TYPE "A"

**Name of work: Providing Paver block road @ Pillaiyarkoil kela veethi
in Thalanayar Town Panchayat, Nagapattinam District**

Estimate Amount Rs. 430000.00

Contract Amount Rs 368002.00

Name of Scheme: MLA Fund - 2021-2022

Sl. No	Probable Qty.		Description of Work	TNDSS or MORTH No.	Rate in Rupees		Units	Amount in Rupees
					Figures	Words		
1	9.00	M ³	Earth work excavation for foundation in hard stiff clay, stiff black cotton, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders, sand, silt or other loose soil and to full depth as may be directed except in hardrock requiring blasting inclusive of shoring shuttering and bailing out water wherever necessary refilling the sides of foundation with excavated soil other than sand in layers of 15cm thick well rammed and completed depositing the surplus excavated soil with in the compound in places shown by the departmental officers with initial lead and lifts and cleaning, levelling, the site etc., complete as per SS 20B for foundation				1M ³ (One Cubic Metre)	

No. of Corrections:

No. of overwritings:

Signature of Contractor

Sl. No	Probable Qty.		Description of Work	TNDSS or MORTH No.	Rate in Rupees		Units	Amount in Rupees
					Figures	Words		
2	4.00	M ³	Cement concrete of mix 1:4:8 (One part of cement Four part of fine aggregate and eight part of coarse aggregates) using 40mm gauge hard broken including cost conveyance of all materials to site including labour charges, transporting and placing in position including shoring, strutting forming protective bunds, cofferdams bailing out of water labour for mixing compacting, finishing and curing, working at depths, tools and plants and incidental charges such as sheeting, shoring and bracing and their subsequent removal etc., complete as per standard specification.				1M ³ (One Cubic Metre)	
3	108.00	M ²	Supplying & Erecting centering for sides & soffits including necessary supports & strutting upto 3.29m height for plane surfaces in all floors with all cross bracings using mild steel sheets of size 90 x 60cm & 10 gauge stiffened, welded with steel angle of size 25 x 25 x 3mm for boarding laid over silver oak joists(Country wood) of size 10 x 6.5cm spaced @ about 90cm c/c and supported by casurina props of 10 - 13cm dia. spaced @ 75cm c/c etc., complete complying with standard specifications and as directed by the departmental officers. Rate for 10m2.for the following items.(RCC floor slab, roof slab, Rectangular/ square, Tee/ Ell beams, Lintels, staircase waist slabs, Landing slabs, Landing beam, Portico beam etc.,).				1M ² (One Square Metre)	
4	13.00	M ²	Cement Concrete 1:2:4 (One part of cement, two part of fine aggregate and four part of coarse aggregate) mix using 20mm HBG ISS metal from approved quarry including cost and conveyance of all materials to site and labour charges, including dewatering if found necessary and laid in layers of not more than 15cm thick and compacted etc., complete complying with standard specifications as directed by the departmental officers				1M ² (One Square Metre)	

No. of Corrections:

No. of overwritings:

Signature of Contractor

Sl. No	Probable Qty.		Description of Work	TNDSS or MORTH No.	Rate in Rupees		Units	Amount in Rupees
					Figures	Words		
5	23.00	M ³	Providing and laying, spreading and compacting graded stone aggregates to Wet Mix Macadam 250 mm thick specification including premixing the materials with water at OMC in mechanical mix plant carriage of mixed material by tipper to site laying in uniform layers with pavers in Sub Base/ Base course on well prepared surface and compacting with vibratory roller to achieve the desired density including cost of material, labour charges, rentals for machinery, fuel and all other incidental charges etc., complete as per clause 406 of MORTH Rev-5				1M ³ (One Cubic Metre)	
6	153.00	M ²	Supplying and laying Rubberised interlocking Paver block M40 grade Providing and laying of 83mm thick high strength type conforming IS 15658-2007 Of rubberized interlocking paver lock in size of minimum compressive strength of 40N mm ² in uniform shape of approved make to be laid in flurring bone pattern with stone dust cushion below the uniform shap of approved non skitting surface in the top and the rate including levelling the base preparation of pavers as sub base, stone dust cushion 100mm thick laying out of pavement cut the pieces to fix the edge vibrating the pavers,sweeping tranporting loading unloading of laying paver block as per standard specification,.				1M ² (One Square Metre)	
Note:								
(1) Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the Other rates and prices in the Bill of /Quantity (refer: ITB clause 13.2 and GCC Clause 43.3)								
(2) Unit rates and prices shall be quoted by the bidder in Indian Rupee (ITB Clause 14.1)								
(3) Where there is a discrepancy between the rate in figures and words, the rates in words will govern (ITB Clause 27s.1(a))								
(4) Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity, the unit rate quoted shall govern (ITB Clause 27.1(b)).								
				Tender Schedule approved for 01 to 06 items only				

No. of Corrections:

No. of overwritings:

Signature of Contractor