

Name of work : Supply and fixing of Amman car shed – Vertical post, purlin, Framed structure of GI sheet and composite solid poly carbonate sheet, Roof with Pre painted Galvanized iron sheet belongs to Arulmighu Thanumalaya Swamy Thirukoil, Suchindrum, Kanniyakumari District.							
Issued to							
Estimate Amount - Rs.15,80,000/-					E.M.D. - Rs.15,117/-		
Agreement Amount - Rs.15,11,686/-							
Data of Tender : 11.05.2022					Period of Completion : 3 Months		
Sl. No.	Qty		Description	Unit in figures and words	Rate in		Total
					figures	words	
1	96.00	RM	Supply and fixing of new vertical post made out of 65x6mm ISA ms angle –Box type having clit arrangement for fixing horizontal rows of purling- 65x6mm ISA all round four sides. Top of post welded with 10mm thick base plate 0.25x0.25x10mm thick for fixing roof Latex truss and bottom necessary base plate. Painting by zinc chrome primer painting over that painting with special quality of 24 carat bronze color based first quality paint. The cost including materials, labour charges, transport cost, loading, un loading cost, painting cost etc complete as directed by Department Officers.	1 RM (One Running Meter only)			

Signature of Contractor

No of Correction:
No of Overwritings:

Joint Commissioner / Executive Officer

Sl. No.	Qty		Description	Unit in figures and words	Rate in		Total
					figures	words	
2	226.00	RM	Supply and fixing of new purling all round of car - made out of 65x6mm angles having holes for fixing with horizontal rows of clit all round four sides of vertical post. Painting by zinc chrome primer painting over that painting with special quality of 24 carat bronze color based first quality paint. The cost including materials, labour charges, transport cost, loading, un loading cost, painting cost etc complete as directed by Department Officers	1 RM (One Running Meter only)			
3	130.00	Sqm	Supply and fixing of car shed side covering – up to bottom 1.50mt and top 1.30mt - made by GI sheet using ms angle 32x32x3mm as outer frame all round with stiffeners of 25x6mm ms flat and jointing the frame and new GI sheet by welding with the frame. Painting by zinc chrome primer painting over that painting with special quality of 24 carat bronze color based first quality paint at both sides. The cost including materials, labour charges, transport cost, loading, un loading cost, painting cost etc complete as directed by Department Officers	1 Sqm (One Square Meter only)			

Signature of Contractor

No of Correction:
No of Overwritings:

Joint Commissioner / Executive Officer

Sl. No.	Qty		Description	Unit in figures and words	Rate in		Total
					figures	words	
4	92.00	Sqm	Supply and fixing car shed side covering top portion up to 3.70mt height made by 4mm thick plain visible composite solid Poly carbonate sheet using ms angle 32x32x3mm as outer frame all round with stiffeners of 25x6mm ms flat and jointing the frame by screw. Painting by zinc chrome primer painting over that painting with special quality of 24 carat bronze color based first quality paint. The cost including materials, labour charges, transport cost, loading, un loading cost, painting cost etc complete as directed by Department Officers.)	1 Sqm (One Square Meter only)			
5	81.00	Sqm	Supplying and fixing of roof truss – Made out of Latex truss model dismantling type using all round outer frame of 40x40mm square tube having inner bracings of 25x25mm square tube - 3nos of truss. Each truss bottom having 0.25x0.25mmx10mm thick base plate for fixing with vertical post. Top purling of 50x6mm ms angle at both side 5 rows on each side. Roof top covered with new Pre painted Galvanized iron sheet of 0.45mm thick. Painting by zinc chrome primer painting over that painting with special quality of 24 carat bronze color based first quality paint. The cost including materials, labour charges, transport cost, loading, un loading cost, painting cost etc complete as directed by Department Officers.	1 Sqm (One Square Meter only)			

Signature of Contractor

No of Correction:
No of Overwritings:

Joint Commissioner / Executive Officer

Sl. No.	Qty	Description	Unit in figures and words	Rate in		Total
				figures	words	
Total Value of work as per basic rate Rs._____ ()						
Add GST @ 18% (CGST @ 9% + SGST @ 9%) Rs._____ ()						
Total Value of Tender Rs._____ ()						

Signature of Contractor

No of Correction:
No of Overwritings:

Joint Commissioner / Executive Officer