

Issued To Tr.

TENDER SCHEDULE						
NAME OF WORK : RENOVATION OF ARULMIGU KARAIKANDESWARAR THIRUKOVIL AT THENMATHIMANGALAM, KALASAPAKKAM TK, THIRUVANNAMALAI DT.						
TENDER VALUE : Rs 39.35 Lakhs					EMD VALUE : Rs 40000.00	
TENDER DATE : 10.05.2022					CONTRACT PERIOD : 9 months	
S.NO	QUNATITY	DESCRIPTION OF THE ITEMS	TNBP NO	UNIT	RATE IN FIGURES	RATE IN WORDS
1		Providing Scaffolding for vimanam raja gopuram with Casurnia post non flammable wherever necessary for main form work and by providing non flammable as covering the areas & plat form for inspection etc all complete. (15'0")				
a)	530.00 Sqm	Vimanam Height upto 50'-0"		Sqm		
b)	450.00 Sqm	Vimanam Height upto 25'-0"		Sqm		
c)	275.00 Sqm	Vimanam Height upto 15'-0"		Sqm		

CONTRACTOR

NO OF CORRECTIONS

EXECUTIVE OFFICER

S.NO	QUNATITY	DESCRIPTION OF THE ITEMS	TNBP NO	UNIT	RATE IN FIGURES	RATE IN WORDS
2	1,690.00 Sqm	Scraping the old plastering surface of wall carafully including isolated bricks or brick work without damaging the vari vargams, racking out the joints, cleaning the surfaces with water including all working in heights, hire charges for special tools, brushes complete.		Sqm		
3		Providing Varagapoochu over a core wall of vimanam, raja gopuram with lime mortar 1:1.5 etc complete including shaping the mugapathram mahanasi koodu and all ornamental work rough plastering with cm or combination mortar with final ornamental plastering for finishing of nayam theervai etc all complete.				
a)	355.00 Sft	Vimanam Height upto 25'-0"		Sft		
b)	175.00 Sft	Vimanam Height upto 15'-0"		Sft		
4	1,405.00 Sqm	Painting with two coat of the water based exterior paint including all labour charges etc complete complying the std specification.,.		Sqm		
5		Painting with Panchavaranam using water based emulsion paint over a priming coat add for ornamental works etc complete the std specification.(Ht upto 15'-0")				

CONTRACTOR

NO OF CORRECTIONS

EXECUTIVE OFFICER

S.NO	QUNATITY	DESCRIPTION OF THE ITEMS	TNBP NO	UNIT	RATE IN FIGURES	RATE IN WORDS
a)	1,800.00 Sft	Vimanam Height upto 25'-0"		Sft		
b)	1,090.00 Sft	Vimanam Height upto 15'-0"		Sft		
6	4.00 Sqm	Painting two coats for old iron works such as iron bars flats and other similar works etc, complete complying with std specification (using zinc chromite primer)		Sqm		
7	10.00 Sqm	Painting old wood work with good quality paint two coats including cost conveyance and labour charges etc complete..		Sqm		
8	20.00 Sqm	Supplying and fixing teak wood temple type including all amterials, labour charges for manufacturing and fixing I position including all furniture fittings etc complete with std specifications.		Sqm		
9	25.00 Sqm	Removal of Cement concrete on flooring clearing carefully away from site		Sqm		
10	165.00 Sqm	Supplying and fixing of cut stone slabe for flooring of size 600mmX600mm and less than the 100mm thick in combination mortar 1:1:5 including quring setting etc all complete complying the std specifications.		Sqm		

CONTRACTOR

NO OF CORRECTIONS

EXECUTIVE OFFICER

S.NO	QUNATITY	DESCRIPTION OF THE ITEMS	TNBP NO	UNIT	RATE IN FIGURES	RATE IN WORDS
11	136.00 Sqm	Removal of tiles clearing carefully away from site		Sqm		
12	31.00 Cum	Weathering course with brick jelly lime concrete using 20mm brick jelly with pure slacked lime over R.C.C. roof slab in the proportion of 32:12.5 and well watering consolidated with wooden beaters to slop including cost and conveyance of materials to site and labour charges etc complete for 10Cum		Cum		
13	320.00 Sqm	Finising the top of the roof with one course of pressed tiles over a bed of LM 1:1.5 12mm thick mixed with water proof compound at 2% b weight of cement including cost and conveyance of all materials to site and all labour charges etc complete for 10 Sqm		Sqm		
14	6.00 Sqm	Removal of cutstone wall carefully from site and including all labour charges anf meterials		Sqm		
15	6.00 Sqm	Resettling of cutstone wall carefully from site and including all labour charges anf meterials		Sqm		

CONTRACTOR

NO OF CORRECTIONS

EXECUTIVE OFFICER

S.NO	QUNATITY	DESCRIPTION OF THE ITEMS	TNBP NO	UNIT	RATE IN FIGURES	RATE IN WORDS
16	16,947.00 Sft	Restoration by providing herbal water wash and approrimats methodology to restore the originalities of the existing granite structure inclusive of hire charges scaffolding arrangements conveyance charges for tools & plants and machinaries to the workshop spot and cleaning the site after completion of work etc		Sft		
17	1,575.00 sqm	Pointing with Lime mortar 1:1.5 including all tools and plants and labour etc all complete for cut stone masonry.		sqm		
18	50.00 Rmt	Repair and fixing run of 4X6 Sqmm(84/0.3) PVC inslutated SC unsheathed Cu.conductor of 1100 V on 7/20GI bearer wire for service connection mains(Sd-68)		Rmt		
19	11.00 Nos	Wiring with 2 x 1.5 sq.mm. (22 / 0.3) PVC insulated unsheathed single core copper conductor of 1100V grade in suitable PVC rigid pipe on wall and ceiling with PVC accessories with TW switch box with 5A FT switch inflush with wall covered with hylem sheet of 3mm thick with painting of suitable colour for open PVC light point / fan point (for electronic regulator)(SD no 21)		Each		

CONTRACTOR

NO OF CORRECTIONS

EXECUTIVE OFFICER

S.NO	QUNATITY	DESCRIPTION OF THE ITEMS	TNBP NO	UNIT	RATE IN FIGURES	RATE IN WORDS
20	50.00 Nos	Renewed Supplying and fixing of 4'-20w Crystal classes LED twin light fittting complete with on wall or cealing with pvc unsheated copper leads from terminals to the fitting with clamp (Data A)		Each		
21	30.00 Nos	Supplying and fixing of WT bluk head fitting with guard (Philips/Bajaj/Crompton/K.Lite) suitable for 11W CFL Lamp with CFI directed by the departmental officers.(SD NO-83)		Each		
22	30.00 Nos	Renewed by Supply and fixing of LED outdoor fittting (Light Emitting diode) 30watts LED street fitting with 32 mm dia GI pipe (Class 'B') complete on the existing post wall with PVC unsheathed Copper leads MS clarnps and aluminium painting with clamp angle nutts (Data B)		Each		
23	20.00 Nos	Supply and fixing of 5A 3 pin and 2 pin combined flush type wall socket with 5A flush type swith concealed in suitable MS box in flush with wall and concealed with 3mm thick hylem sheet.(Sd no 135)		Each		

CONTRACTOR

NO OF CORRECTIONS

EXECUTIVE OFFICER