

SALEM CITY MUNICIPAL CORPORATION

TENDER SCHEDULE

Name of Contractor :

EMD Details **Rs.3,300/-**

Tender Date **17.05.2022**

Name of Work: **Removing the Silt, De-Watering the Polluted water, Providing Safty Grill work and Repairs to the Parapet Wall to the Common Well at Desiyapunaramaippu Colony in D.No.44.**

Est. No. **E2/Est No : 471/WS/2021-2022**

Estimate Cost **Rs.3,30,000/-**

1. The Quantities here given are those upon the lump sum tender cost of work is based, but they are subject to alterations, omissions, deductions or additions as provided for the conditions of the contract and do not necessarily show the actual quantities of work to be done. The unit rates are those governing payment for extracts or deductions for omissions according to the contract, as set forth in the preliminary specifications of the (Madras Detailed Standard Specifications) Tamil Nadu building practice and other conditions or specifications of the contract.

2. It is to be expressly understood that the measured work is to be taken nett (not with standing any custom or practice to the contrary) according to the actual quantities when in place and finished according to the drawing or as may be ordered from time to time by the Corporation Engineer and the cost calculated by measurement of weight, of the respective prices, with out additional charge for any necessary contingent works connected herewith. The Rates quoted are for works in 'situ' and complete in every respect.

3. The work must be completed with in Days/Month from the date of receipt of acceptance of this tender.

Item No	Probable Quantity		Description of Work	Rate		Unit in	Amount in
	Figures	Units		Words	Figures	Words	Figure
1	30.00	m2	Supplying and erecting centering to sides and soffits including supports and strutting for drainage sides and culvert body wall sides using M.S Sheets of size 90cm x 60cm and B.G 10stifened with welded mild steel angles of size 25mm x 25mm x 3mm for boarding laid over(silver oak joists) of size 10cm x 6.50cm spread at about 90cm including all labour charges and cost and conveyance of all materials to site etc. complete Complying with Standard Specification			m2	
2	1831.00	Kg	Supplying, fabricating, erecting structural steel work for roofing welded or bolted type using MS channels, angles, plates and round bars etc. conforming to IS specification including primer coating and enamel painting as per Design given by the departmental officers etc, complete as per standard specification			Kg	
3	250.00	Kg	Suppling and fabricating and placing in position MS (or) R.T.S. bar for reinforcement to all RCC works as per the design given including cost of steel and binding wire also in all floors.			Kg	

4	3.10	m3	Reinforced cement concrete 1:1½:3 mix (One cement one and half sand three aggregate) using 20mm ISS gauge HBBG metal from the approved quarry including mixing, laying, consolidating, curing cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification			m3	
5	67.00	m2	Painting two coats with best synthetic enamel paint of approved Colour for new iron works the rate is inclusive of all materials, brushes and scaffolding charges etc., complete complying with standard specification(paint should be got approved by the Departmental Engineer before use on work.			m2	
6	48.00	m2	White washing two coats with freshly burnt shell lime white in colour in all floors including cost of lime and other materials brushes scaffolding charges etc.complete complying with standard specification and as directed. -100sq.m S.I.333			m2	
7	5.00	Each	De-Watering with help of pump with Engine including cost and conveyance of all materials to site and all labour charges for Loading, unloading and Operating charges with Fuel charges etc., Complete.(PWD SOR 2021-22, Page.No.168, S.No.19)			Each	
8	150.00	m3	Removing the Silt, dumped in Open well with initial lead 10m and lift 10m height including all cost and conveyance of all charges etc, complete.			m3	