

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: The Commissioner, Pudukkottai Municipality

Name of Work : 2)Construction of Channel side wall, Pillar, Deck slab, Screening, Grit and Silt pit chamber Bridge at DD Plan road in Pudukkottai Municipality (MP FUND 2021-2022)

Contract No : 2421/2022/E1

Bidder Name :						
<u>PRICE SCHEDULE</u> (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work excavation for foundation in all types of soils and sub soils including soft disintegrated rock and soft rock to the full depth as may be directed except in hard rock requiring blasting, including necessary string, strutting, shuttering, bailing or pumping out sub soil water, removal of slush wherever necessary and also including refilling the sides of foundations with excavated soil in lavers of 15 cm. thick, well rammed and consolidated depositing the surplus earth within the compound in places shown by the departmental officers with all leads and lifts and clearing and leveling the site etc. complete complying with the standard specifications, drawings and as directed by departmental Engineers SS 20 B TNDSS NO: 23&24VI (S2), VII 9,10 .	128.00	Cum		0.00	INR Zero Only
2	Supplying and filling in foundation and basement with filling sand in layers of not more than 15cm.thick well rammed watered and compacted etc., complete complying with standard specification.	8.00	Cum		0.00	INR Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
3	Plain Cement Concrete 1:4:8 (one cement four fine aggregates and eight coarse aggregates) using 40mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges and all incidental charges such as water providing etc., complete as per standard specification	11.00	Cum		0.00	INR Zero Only
4	Centering for soffits of RCC slabs of plane surface like lintels, beams ,etc.,including strutting 3m high using mild steel sheets of size 90cm X 60cm X and B.G 10 stiffened with M.S angles of size 25mm X 25mm X 3mm laid over silver Oak (C.W) joists of size 10cm X 6.5cm (spaced at about 90cm c/c)and supported dy casurina props of 10cm to 13cm dia (spaced of 75cm C/C) complying with standard specification and directed					
5	column	150.00	Sqm		0.00	INR Zero Only
6	Beam and slab	465.00	Sqm		0.00	INR Zero Only
7	Reinforced Cement concrete 1:1.5 :3 (one cement, one and half sand & three course aggregate) using 20mm gauge hand broken/ and broken granite stone for all RCC items of works excluding centering shuttering and cost of reinforcement but including curing etc.,complete and also including fixing fan clamps and fixtures in rcc works wherever necessary as directed by departmental officer etc., complete.	80.00	Cum		0.00	INR Zero Only
8	Suppling and fabricating and placing in position MS (or) R.T.S. bar for reinforcement to all RCC works as per the design given including cost of steel and binding wire also in all floors.	8801.00	Kg		0.00	INR Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
9	Supply, delivery of S S screening Material cost including loading and unloading charges complying with standard specification and directed	2.00	Nos		0.00	INR Zero Only
10	Supply, delivery of Grit Material cost including loading and unloading charges complying with standard specification and directed	2.00	Nos		0.00	INR Zero Only
Total in Figures					0.00	
Quoted Rate in Words		INR Zero Only				