

Item Rate BoQ

Tender Inviting Authority: Commissioner, Thoothukudi City Municipal Corporation

Name of Work :Construction of Road Crossing Culverts at P&T Colony 1st Street West and 11th Street Middle in West Zone (Ward-34)

File No: E2/1440/2022 , Est No:8/22-23/AEE(W)

Name of the Bidder/ Bidding Firm /							
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Earth work excavating and depositing on bank with initial lead of 10 meters and initial lift of 2 meters in sand silt or other loose soil, wet sand or silt not under water, light Black cotton soil, sandy loam and ordinary soil including excavated as per SS20B.	17.00	1M3 (One cubic metre)			0.00	INR Zero Only
2	Plain Cement concrete 1:4:8 using 40mm I.S.S. HBG metal from approved quarry including cost and conveyance of all materials and labour charges etc., complete.	1.70	1M3 (One cubic metre)			0.00	INR Zero Only
3	Centering with steel centering and shuttering with necessary strutting arrangements for all R.C.C. or P.C.C. items including cost conveyance etc.,complete	45.00	1M2 (One square metre)			0.00	INR Zero Only
4	Plain Cement concrete 1:2:4 using 20mm I.S.S. HBG metal from approved quarry including cost and conveyance of all materials and labour charges etc., complete.	6.00	1M3 (One cubic metre)			0.00	INR Zero Only

5	Plastering with cement mortar (1:4) 20mm thick in all floors including cost and conveyance of all materials to site and labour charges etc, complete complying with standard specifications .	10.00	1M2 (One square metre)			0.00	INR Zero Only
6	Supplying and Fixing of Caddappa Slab metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges etc., complete as per standard specification	13.50	1M2 (One square metre)			0.00	INR Zero Only
7	Suppling and fabricating and placing in position MS (or) R.T.S. bar for reinforcement to all RCC works as per the design given including cost of steel and binding wire also in all floors.	350.00	1Kg (One Kilogram)			0.00	INR Zero Only

8	Providing and laying in position Standardised Concrete Mix M-20 Grade in accordance with IS 456 - 2000 using 20mm and down graded hard broken granite stone jelly for all RCC items of works with minimum cement content of 3250Kg/cum and maximum water cement ratio of 0.55 including admixture (Plasticiser / super plasticiser) in recommended proportions as per IS 9103 to accelerate, related setting of concrete, improve workability without impairing strength and durability with about (5.0cum), 7730Kg of 20mm machine crushed stone jelly and with about (3.3 cum), 5156kg of 10 - 12mm machine crushed stone jelly and with about (4.79cum) 7670 kg of sand, but excluding cost of reinforcement grill and fabricating charges centering and shuttering but including laying, vibrating with mechanical vibrators, finishing, curing, etc and providing fixtures like fan clamps in the RCC floor / roof slabs wherever necessary without claiming extra cost etc., complete complying with standard specification and as directed by the departmental officers - The Coarse and Fine aggregates to be used should comply with the requirements of IS standards. (No separate payment will be made by the Department for the excess usage of materials)	3.50	1M3 (One cubic metre)			0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					