

Item Rate BoQ

Tender Inviting Authority: **President Bodipattii Panchayat.**

Construction of 100000 Lits sump at Nehru Nagar at Periyakotti. H/O Periyakottai.

Contract no :

Bidder Name :						
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>						
NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	BASIC RATE In Words To be entered by the Bidder Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1.00	Earth work Excavation for Foundation in all soils and Sub Soil to full depth as may be directed except in hard rock requiring blasting but inclusive of shoring strutting and requiring the sides of foundation.	33.12	Cum			
2.00	SDR (not requiring blasting) Earthwork excavating & depositing on bank with initial lead of 10m & initial lift of 2m in soft disintegrated rock, laterite, soft rock or kankar, not requiring blasting	44.16	Cum			

3.00	MR & DMR (not requiring blasting)Earthwork excavating & depositing on bank with initial lead of 10m & initial lift of 2m in medium rock and dense medium rock not requiring blasting.	55.20	Cum			
4.00	Cement concrete 1 : 4: 8 mix using 40mm HBG metal for foundation including watering wherever necessary and laid in layers of not more than 15cm thick., compacting etc., complete complying with standard specifications and as directed.	8.83	Cum			
5.00	Cement concrete 1:1.5:3 using 20mm ISS HBG metal for all RCC item of works excluding cost of Rein forcement and fabricating charges, centering and shuttering but including curing and providing fixtures like fan clamps in the RCC floor or roof slabs wherever necessary and bearing surfaces of walls , sides and bottom of the slabs, beams etc., shall be finished smooth with cement mortar 1:3, 12mm thick. and with kraft paper without claiming extra as directed by the departmental officers complete complying with standard specifications.	0.00	Cum			
6.00	Upto 1.50m Depth below G.L.	4.88	Cum			
7.00	Above 1.50m upto 4.50m Depth below G.L.	16.84	Cum			

8.00	Upto 4.50m Height above G.L.	9.71	Cum			
9.00	Supplying & Erecting Curved centering for sides & soffits including necessary supports & strutting upto 3.29m height for plane surfaces in all floors with all cross bracings using mild steel sheets	157.98	Sqm			
10.00	Supplying & Erecting centering for sides & soffits including necessary supports & strutting upto 3.29m height for plane surfaces in all floors with all cross bracings using mild steel sheets	35.84	Sqm			
11.00	Supplying and Fabricating and placing in position MS steel or ribbed for steel for all reinforced cement concrete works as per the design Given including cost of steel and binding wire in all floors etc, Complete complying with stanard specification.	2.90	Mt			
12.00	Finishing the exposed surface of RCC item of work such as slabs, beams, sunshade, facia, canopy slab, staircase waist slab, landing slab etc., with CM 1:3 10mm thick including	132.14	Sqm			
13.00	Wall Painting two coats Using with approved best quality of Emulsion paint of approved colour over the Including priming coat etc., complete complying with standard specifications	60.64	Sqm			
14.00	Supply and fixing of Water tight Manhole cover with frame size 60 Cm x 60Cm including cost of and Conveyance of all Cherges etc complete	1.00	Each			

15.00	Towards supply of the following including all etc complete.	0.00	Each			
16.00	5 HP open well submersible 100 Lpm x 75 m head	1.00	Each			
17.00	5 Hp Panel board	1.00	Each			
18.00	4Sqm 3 core flat cable	10.00	Rm			
19.00	75mm dia PVC 6ksc pipe	498.00	Rm			
20.00	50mm dia GI pipe	30.00	Rm			
21.00	Earth work Excavation for Foundation in all soils and Sub Soil to full depth as may be directed except in hard rock requiring blasting but inclusive of shoring strutting and requiring the	224.10	Cum			
22.00	Towards labour charges for laying and jointing PVC pipes etc complete.	498.00	Rm			