

Tender Document
“NAMAKKU NAAME THITTAM (URBAN) (NNT) 2022-2023”

PRICE BID

Veeraganur Town Panchayat

NAME OF THE WORK : **Construction of Compound wall at
Government Girls Higher Secondary
School in Veeraganur Town Panchayat.**

Estimate Amount: Rs.75.00 Lakhs

OFFICER INVITING BIDS : Executive Officer
Veeraganur Town Panchayat

Price Bid Date :

Invitation for Bid No.

To:

Executive officer,
Veeraganur Town Panchayat,

.

We, the undersigned, declare that:

(a) We have examined and have no reservations to the Bid Documents.

(b) We offer to execute in conformity with the Bid Documents for the work of **“Construction of Compound wall at Government Girls Higher Secondary School in Veeraganur Town Panchayat.**

using Paver Machines (Package No: I)”in Veeraganur Town Panchayat under the “NAMAKKU NAAME THITTAM (URBAN) (NNT) 2022-2023”.

(c) The total price of our Bid, excluding any discounts offered in item (d) below is

- (i) In figures :- Rs...../-
- (ii) In Words:- Rupees

(d) The discounts offered are

- (i) In figures :- Rs...../-
- (ii) In Words:- Rupees

(e) The net price of our bid, after discount offered in (d) above is

(i) In figures :- Rs...../-

(ii) In Words:- Rupees only

(f) Our Bid shall be valid for a period of **180 days** from the date fixed for the bid submission deadline in accordance with the Bidding Documents, and it shall remain binding upon us and may be accepted at any time before the expiry of that period.

(g) If our Bid is accepted, we commit to remit Security Deposit in accordance with the Bid Documents within the stipulated time.

SCHEDULE OF RATES AND APPROXIMATE QUANTITIES

1. The quantities given here are those upon which the item rate tender cost of the work is based, but they are subject to alternations, omissions, deductions or addition as provided for in the conditions of this contract and do not necessarily show the actual quantities of work to be done. The unit rates quoted below are those governing payment for extras or deductions or omissions according to the condition of the contract, as set forth in the Standard Specifications for roads and bridges with the MORTH specifications and other condition of specifications of the contract.
2. It is to be expressly understood that the measured work is to be taken net (Not withstanding any custom or practice to the contrary) according to the actual quantities. When in places and finished according to the drawings, or as may be ordered from time to time by the Engineer in charge and the cost calculated by measurement or weight at the respective prices, without any additional charge for any necessary or contingent works concerned therewith. The rates quoted are for the finished works in situ and complete in every respect.
3. The description given in Schedule - A are to indicate the item of work only and need not be construed as full specification. The quoted rate shall be for carrying out the item as per standards and specifications described in the relevant MOST specification. The contractor shall take no advantage of any apparent error or omission in the Schedule - A description.
4. The Tenderers should quote their rates for the quantity and units specified under metric units under Schedule 'A'.
5. The contractor should sign all the pages of schedule 'A' enclosed in the tender document without any omission. Otherwise the tender will be liable for rejection as per the rules.

Executive Officer
Veeraganur Town Panchayat

Tender Schedule

Name of Work: Construction of Compound wall at Government Girls Higher Secondary School in Veeraganur Town Panchayat..

Estimate Amount : 7500000/-

Scheme: NAMAKKU NAAME THITTAM (URBAN) (NNT) 2022-2023

SI No	Quantity		Description of Work	Unit in	Rs	Amount in words
1	438	Cum	Earth work excavation for foundation and depositing on bank with in the initial lead of 10m and a lift of 2m in hard stiff clay, stiff block cotton, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders etc.,as per SS 20 A. TNDSS NO: 23 & 24 VI (S2) VI,VII 9,10 with standard specifications.	(One Cubic Metre)		
2	383		Earth work excavation for foundation and depositing on bank with in the initial lead of 10m and a lift of 2m in Soft disintegrated rock, Laterite, Soft rock or Kankar, not requiring blasting etc., as per SS 20 A. TNDSS NO: 23 & 24 VI (S2) VI,VII 9,10 with standard specifications.	(One Cubic Metre)		
3	58	Cum	Plain Cement Concrete 1:4:8 (one cement four fine aggregates and eight coarse aggregates) using 40mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges and all incidental charges such as water providing etc., complete as per standard specification	(One Cubic Metre)		

4			Supplying and erecting, centering for sides and soffits including supports and strutting upto 3.29m height for plane surfaces as detailed below in all floors with all cross bracings using mild steel sheet of 90cm x60cm BG 10 gauge stiffened with welded M.S. angle of 25 x 25 x 3mm for boarding laid over silver oak joists of size 10cm x 6.50 cm spaced at about 90 cm centre to centre and supported by casurina props of 10 cm to 13 cm dia spaced at not less than 75 cm centre to centre or at suitable intervals etc. complete in all floors complying with standard specification. (The payment for centering shall be made only after the concrete is laid. The retrieved materials should be taken back by the contractor)			
	615	Sqm	Column	(One Square Metre)		
	285	Sqm	Grade Beam	(One Square Metre)		
	190	Sqm	Plain surface	(One Square Metre)		
4	23300	Kg	Supplying, fabricating and placing in position M.S. or R.T.S. reinforcements grill for RCC works as per the design given including cost of steel and binding wire etc., complete complying with standard specification. (The contractor will have to make his own arrangements for the supply of M.S. plain rods / RTS rods and binding wire)	(One Kilogram)		
5			ReinforcementCement Concrete 1:1½:3 (One cement, one and half sand and three stone jelly) using 20 mm gauge hard granite broken stone jelly for all reinforced			

			cement concrete works excluding cost of reinforcement grill and fabricating charges, centering and shuttering but including laying, vibrating with mechanical vibrator, finishing, curing, etc. complete as directed by the Departmental Officers.			
	184	Cum	UP TO BASEMENT	(One Cubic Metre)		
	49	Cum	GROUND FLOOR	(One Cubic Metre)		
6			Brick work in following Cement Mortar using best quality of country bricks of size 8-3/4" x 4-1/4" x 2-3/4" for foundation and basement including curing, etc., complete complying with standard specification.			
	228	Cum	GROUND FLOOR	(One Cubic Metre)		
7	1089	Sqm	Plastering with Cement Mortar 1:5 (One cement and Five sand), 12 mm thick in all floors including curing etc. complete complying with standard specification and as directed by the departmental officers.	(One Square Metre)		

8	1089	Sqm	Painting two coats with ready mixed Plastic Emulsion Paint approved quality and colour over a priming coat, including thorough scrapping, clean removal of dirt, etc complete and including necessary plaster of paris, putty, wherever required etc, complete as per standard specification. - 10 sq.m	(One Square Metre)		
9	720	Kg	Supplying and fixing M.S. Grill Door, Window, Ventilator of approved design and as directed by the departmental officers including cost of MS Ventilator, labour charges and cost of one coat of red oxide primer with labour charges for priming coat etc. complete complying with standard specification.	(One Kilogramme)		
10	24	Sqm	Painting with ready Mixd enamel Paint over the new Steel works of approved quality and colour without priming coat including the cost all materials etc., complete, in all floors.	(One Square Metre)		