## **Tender schedule**

## NAME OF WORK: Providing Metal Beam Crash Barrier at Thetchanpatcheri Road, Kattumannar kovil road in kallidaikurichi Town panchayat

## Estimate Amount:Rs.15,00,000

SI. NO	Quantity	Description of work	SSRB & Rates in MORT		Rates in	Unit	Amount in Puncos
			H No	Figures	Words	Unit	Amount in Rupees
1	200.00	Providing and erecting <b>Single sided Double Guard</b> <b>Metal Beam Crash Barrier System</b> 1.70m high, comprising of 3mm thick wall 'W' beams posts and spacer channels shall be made by cold roll forming using HR conform to IS 5986 Fe 41/360 and dip galvanized having Zinc Mass of 550gms/sqm, minimum 950mm above road/ground level fixed on ISMC series channel vertical post 150 x 75 x 5mm spaced 2m center 312mm x 83mm flange width x 3mm thick, 4318mm long post directly embedded in the concrete (M15) pit size 350x350x800mm for a depth of 750mm below ground. All fixing bolts and nuts hot dip galvanized conforming to IS:1367 clause 4.60 all complete as per Technical Specification and as directed by the Engineer-in-charge.				1 Mt (One metre)	

**Bidder's Signature**