

P.W.D.

Buildings (C&M) Division,

Ramanathapuram.

SCHEDULE - A

Name of work: **Construction of Veterniray Dispensary Building at Uchipuli in Ramanathapuram District.**

Sl. No.	Quantity	Description	TNBP No.	Rate in Figures and in words	Unit	Amount in Rs.
1	2	3	4	4	5	6
1	299.00 M ³ [Two Hundred and Ninety Nine point Zero cubic metre only]	Earth work Excavation for foundation in all soils and sub soils and to full depth as may be directed except rock requiring blasting inclusive of shoring, strutting and baling- out of water wherever necessary, re-filling the sides of foundation with excavated earth in layers of 15cm thick well rammed and compacted, depositing the surplus earth within the compound in places shown by the Departmental Officers with an initial lead of 10 meters and lift of 2 meters lift etc., complete with standard specifications.			1 M ³ (One cubic metre)	
2	24.50 M ³ [Twenty Four point Five Zero Cubic metre only]	Earth work open excavation in all soils and sub soil and to full depth as may be directed except in hard rock requiring blasting but including shoring, strutting and balling out water wherever necessary and depositing the surplus earth within the compound with an initial lead of 10 metres and lift of 2 metres in places shown by the departmental officers clearing, leveling the site etc., complete complying with standard specification.			1 M ³ (One cubic metre)	
3	7.50 M ³ [Seven point Five Zero cubic metre only]	Cement Concrete 1:5:10 (One Cement, Five sand and Ten hard broken stone jelly) using 40 mm gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers of not more than 15 cm thick well rammed, consolidated and curing etc. complete complying with standard specification	23 & 24		1 M ³ (One cubic metre)	

Contractor

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

1	2	3	4	4	5	6
4		Brick work in following Cement Mortar using best quality of country bricks of size 8-3/4" x 4-1/4" x 2-3/4" in cement mortar 1:5 for foundation and basement including curing, etc., complete complying with standard specification.	23 & 24			
a	14.00 M ³ [Fourteen point Zero Cubic metre only]	In Foundation and Basement	23 & 24		1 M ³ (One cubic metre)	
5		Brick work in cement mortar 1:6 (one cement and six sand) using Country bricks 8-3/4" x 4-1/4" x 2-3/4" for the following items including curing etc., complete complying with standard specification.	23 & 24			
a	29.00 M ³ [Twenty Nine point Zero Cubic metre only]	In Foundation and Basement	23 & 24		1 M ³ (One cubic metre)	
b	54.00 M ³ [Fifty Four point Zero Cubic metre only]	In Ground Floor	23 & 24		1 M ³ (One cubic metre)	
6	60.00 M ³ [Sixty point Zero Cubic metre only]	Supplying and filling in foundation, basement, etc with Wet mix in ratio of 1:1 in layers of not more than 15 cm thick thoroughly mixed, well watered, rammed and consolidated etc. complete complying with standard specification and as directed by the departmental officers.	23 & 24		1 M ³ (One cubic metre)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
7	28.50 M ³ [Twenty Eight point Five Zero Cubic metre only]	Supplying and filling in foundation, basement, etc with filling stone dust in layers of not more than 15 cm thick well watered, rammed and consolidated etc. complete complying with standard specification and as directed by the departmental officers.	23 & 24		1 M ³ (One cubic metre)	
8	41.00 M ³ [Twenty Eight point Five Zero Cubic metre only]	Supplying and filling in foundation and basement with Conveyed earth 3 km other than sand in layers of not more than 15cm thick, well rammed watered and consolidated etc., complete complying with standard specifications.	23 & 24		1 M ³ (One cubic metre)	
9	27.00 M ³ [Twenty Seven point Zero Cubic metre only]	Refilling with excavated earth other than sand with an initial head load of 100 mts. and depositing the earth as shown by the departmental officers in layers of not more than 15 cm thick well rammed, watered and consolidated etc. complete complying with standard specification	23 & 24		1 M ³ (One cubic metre)	
10	81.75 M ² [Eighty one point Seven Five square metre only]	Supplying and erecting steel centering for sides and soffits including supports for plain surfaces for reinforced cement concrete work such as column footing, plinth beam, grade beams, staircase steps, pedestals, bed block covers etc., using mild steel sheets of size 90mm x 60mm of B.G.10 stiffened with welded mild steel angles of size 25 mm x 25 mm x 3 mm boarding laid over silver oak (or) country wood joists of size 10 cm x 6.5 cm spaced at about 90 cm centre to centre and supported by casuarinas props of 10cm to 13 cm dia spaced at 75 cm centre to centre at suitable intervals etc., complete complying standard specifications.	23 & 24		1 M ² (One square metre)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
11		Supplying and erecting centering for sides and soffits including supports and strutting upto 3.29m high for plain surfaces such as RCC slab, beams, TEE or Ell beams, Lintels staircase beams etc., with all cross bearings using mild steel sheets of size 90mm x 60mm of B.G.10 stiffened with welded mild steel angles of size 25 mm x 25 mm x 3 mm boarding laid over silver oak (or) country wood joists of size 10 cm x 6.5 cm spaced at about 90 cm centre to centre and supported by casuarinas props of 10cm to 13 cm dia spaced at 75 cm centre to centre at suitable interval. etc., complete complying standard specifications.	23 & 24			
a	238.00 M ² [Two Hundred and Thirty Eight point Zero square metre only]	Centering for RCC floor slab, roof slab, rectangular, square Tee or Ell beam, lintel, bed block staircase waist slab, landing slab, landing beam, portico beam, portico slab, etc.	23 & 24		1 M ² (One square metre)	
b	167.00 M ² [One Hundred and Sixty Seven point Zero square metre only]	Centering for such as RCC square or rectangular column, top and bottom slab of sunshade, boxing sill slab etc.,	23 & 24		1 M ² (One square metre)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
12		Providing and laying in position, standardised concrete Mix M-25 Grade in accordance using 20mm with IS:456-2000, and down graded hard broken granite stone jelly for all RCC items of works with minimum cement content of 325 kg/ms and maximum water cement ratio of 0.55, including admixture (plasticiser / super plasticiser) in recommended proportions as per IS:9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability with about (5 cu.m.) 7730 kg. of 20mm machine crushed stone jelly and with about (3.3 cu.m.) 5156 kg. of 10-12mm machine crushed stone jelly and with about (4.79 cu'm') 7670 kg. of sand , but excluding cost of reinforcement grill and fabricating charges, centering and shuttering and also including laying, vibrating with mechanical vibrators, finishing, curing, etc. and providing fixtures like fan clamps in the RCC floor/ roof slabs wherever necessary without claiming extra, etc., complete complying with standard specification and as directed by the departmental officers. The coarse and fine aggregates to be used should comply with the requirements of IS standards. (No separate payment will be made by the Department for the excess usage of materials).	23 & 24			
a	58.50 M ³ [Fifty Eight point Five Zero Cubic metre only]	For Foundation and basement	23 & 24		1 M ³ (One cubic metre)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
b	34.00 M ³ [Thirty Four point Zero cubic metre only]	In Ground floor.	23 & 24		1 M ³ (One cubic metre)	
13	81.00 Qtl. [Eighty One point Zero Quintal Only]	Supplying, fabricating and placing in position Mild Steel / Ribbed Tor Steel grills for all RCC works as per design given including cost of steel and G.I. binding wire in all floors etc. complete complying with standard specification. (Contractor has to make his own arrangements for the supply of steel and binding wire)	23 & 24		1 Qtl. (One Quintal)	
14	12.50 M ³ [Twelve point Five Zero Cubic metre only]	Plain cement concrete 1:5:10 (one cement, five sand and ten broken stone) for flooring using hard broken granite stone jelly 40mm gauge for flooring including dewatering if found necessary and laid in layers of not more than 15cm thick in the case of foundation etc. complete complying with standard specification	23 & 24		1 M ³ (One cubic metre)	
15	7.50 M ³ [Seven point Five Zero Cubic metre only]	Cement Concrete 1:2:4 (One Cement, Two sand and Four hard broken stone jelly) using 20 mm gauge hard broken granite stone jelly for all RCC items of works excluding cost of reinforcement grill and fabricating charges, centering and shuttering but including laying, vibrating with mechanical vibrators, finishing, curing, etc. and providing fixtures like fan clamps in the RCC floor / roof slabs wherever necessary and bearing surfaces of walls, beams etc. shall be finished smooth with Cement Mortar 1:3 (One Cement and Three Sand) and kraft paper laid over it without claiming extra, etc., complete complying with standard specification and as directed by the departmental officers	23 & 24		1 M ³ (One cubic metre)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
16	147.00 M ² [One Hundred and Forty Seven point Zero square metre only]	Finishing the top of roof with one course of approved first quality machine pressed tiles of size 230mm x230mm x 20mm thick laid in Cement Mortar 1:3 (One Cement and Three Sand) 12mm thick mixed with water proofing compound conforming IS as approved by the departmental officer at 2% by weight of cement used and the joints pointed neatly to full depth of tiles with the same cement mortar mixed with red oxide and water proofing with standard specification and as directed by departmental officers.	23 & 24		1 M ² (One square metre)	
17		Brick partition walls of 10.80cm thickness using best quality country bricks of size 8-3/4" x 4-1/4" x 2-3/4" in Cement Mortar 1:3 (One Cement and Three Sand) using hoop iron reinforcement if found necessary including curing etc. complete and as directed by the departmental officers. (Hoop iron reinforcement will be measured and paid for separately)	23 & 24			
a	3.00 M ² [Three point Zero square metre only]	Foundation and Basement	23 & 24		1 M ² (One square metre)	
b	45.00 M ² [Forty Five square metre only]	Ground Floor.	23 & 24		1 M ² (One square metre)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
18	15.00 RM [Fifteen point Zero running metre only]	Supplying and fixing in position best approved of BIS quality PVC rain water down fall pipes having a pressure of 4 kg. / sq.cm including cost of necessary PVC shoe, PVC bend, cast iron gratings of required diameter and special clamps, brass screws, nails, etc., and fixing of cast iron gratings at junction of parapet and the RCC roof slab including finishing neatly etc., complete. The rate shall be inclusive of cast of removable cast iron grating. The PVC pipe shall be fixed in wall with special type of "U" clamp at the centre of the pipe line in addition to those for more than 3.0 metre pipe length, etc., complete complying with standard specification. 110 mm Dia	23 & 24		1 RM (One Running metre)	
19	770.50 M ² [Seven Hundred and Seventy point Five Zero square metre only]	Plastering with cement mortar 1:5 (one cement and five sand) 12mm thick in all floors are including finishing neatly curing etc., complete complying with standard specification.	23 & 24		1 M ² (One square metre)	
20	268.00 M ² [Two Hundred and Sixty Eight square metre only]	Special ceiling plastering and finishing the exposed surface of RCC items of work such as slab, beam, sunshade, staircase waist slab, landing slab etc., with cement mortar 1:3 (one cement and three sand) 10mm thick including hacking the surfaces and providing cement mortar nosing, beading for sunshade, staircase step, landing slab neat and finishing and curing etc., complete.	23 & 24		1 M ² (One square metre)	
21	57.00 M ² [Fifty seven square metre only]	Plastering with Cement Mortar 1:3 (One Cement and Three Sand) 12mm thick mixed with water proofing compound conforming to BIS at 2% by weight of cement used including finishing, curing, etc., complete in all floors complying with standard specification and as directed by the departmental officers.	23 & 24		1 M ² (One square metre)	

Contractor

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

1	2	3	4	4	5	6
22	105.50 M ² [One Hundred and Five point Five Zero square metre only]	Flooring with Vitrified Tiles of size 600 x 600 x 8 mm laid over 20 mm thick cement mortar 1:3 (One Cement and Three Sand) base mortar over the existing slab / floor including cutting the tiles to the required size with special cutter wherever necessary, laying in position and pointing with white cement mixed with colouring pigment at the rate of 0.3 Kg. / sq.m. etc., complete complying with standard specification. (The make and brand of the tiles should be got approved by Executive Engineer before use on works)	23 & 24		1 M ² (One square metre)	
23	8.00 M ² [Eight point Zero square metre only]	Flooring with Anti skid Self Designed Colour Ceramic Tiles of size 305 x 305 x 6mm ceramic tiles laid over 20 mm thick cement mortar 1:3 (One Cement and Three Sand) base mortar over the existing slab / floor including cutting the tiles to the required size with special cutter wherever necessary, laying in position and pointing with white cement mixed with colouring pigment at the rate of 0.3 Kg. / sq.m. etc., complete complying with standard specification. (The make and brand of the tiles should be got approved by Executive Engineer before use on works)	23 & 24		1 M ² (One square metre)	
24	7.20 M ² [Seven point Two Zero square metre only]	Paving the floor with pre-polished concrete anti-skid step tiles (Required shape and design) of 20mm thick of approved quality and colour laid in Cement Mortar 1:3 (One Cement and Three sand) 20mm thick and pointed with white cement mixed with colouring pigment at the rate of 0.40 Kg. / sq.m., curing, etc., complete complying with standard specification and as directed by the departmental officers. (The make and brand of the tiles should be got approved by Executive Engineer before use on works)	23 & 24		1 M ² (One square metre)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
25	22.50 M ² [Twenty Two point Five Zero square metre only]	Paving the floor with Cement based Hydraulically pressed Anti skid tiles (pattern design) of 20mm thick of approved quality and colour laid in Cement Mortar 1:3 (One Cement and Three sand) 20mm thick and pointed with white cement mixed with colouring pigment at the rate of 0.40 Kg. / sq.m., curing, etc., complete complying with standard specification and as directed by the departmental officers. (The make and brand of the tiles should be got approved by Executive Engineer before use on works)	23 & 24		1 M ² (One square metre)	
26	0.40 M ³ [Zero point Four Zero Cubic metre only]	Plain Cement Concrete 1:2:4 (one cement, two sand and four hard broken stone jelly) using 20mm jelly for wearing coat including laying, compacting, finishing and curing, etc., complete as per standard specificatins and as directed by the departmental officers.	23 & 24		1 M ³ (One cubic metre)	
27		Manufacturing, supplying and fixing Precast Reinforced Cement Concrete slabs of following thickness in RCC 1:2:4 (one cement, two sand and four aggregates), using following HBGS jelly excluding cost of reinforcement steel in position but including cost of moulding charges, casting of slab, finishing, curing and fixing in position in all floors etc., complete complying with standard specification and as directed by the departmental officers				
a	7.00 M ² [Seven point Zero square metre only]	50mm thick precast slab using 20mm HBGS jelly	23 & 24		1 M ² (One square metre)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
28	49.00 M ² [Forty Nine point Zero square metre only]	Manufacturing, supplying and fixing in position plain cement concrete precast pavement slab of size 450mm x 450mm of 50mm thick in Cement Concrete 1:2:4 (One cement, Two sand and Four jelly) using 20mm HBG stone jelly including cost of moulding charges, casting of slab, finishing, curing, fixing and pointing the slab with CM 1:3 (One Cement and Three Sand) to full depth of slab etc., complete complying with standard specification and as directed	23 & 24		1 M ² (One square metre)	
29	29.00 M ² [Twenty Nine point Zero square metre only]	Supplying and fixing fine polished cuddapah stone slab of 40mm thick for cupboard laid over Cement Mortar 1:3 (One Cement and Three Sand) 20mm thick over the existing bed of Cement Concrete 1:5:10, (One Cement, Five Sand and Ten aggregate) and pointing the joints to full depth of slabs with same mortar mixed with black oxide and the top surface rendered smooth, curing, etc., The cuddapah stone slabs and other materials to be used shall be got approved by the Executive Engineer concerned before use on work, etc., complete complying with standard specification.	23 & 24		1 M ² (One square metre)	
30	26.00 RM [Twenty Six point Zero running metre only]	Supplying and fixing of Hallow pressed steel door frames for single leaf and double leaved door using pressed steel frame of size 105X60mm using mild steel sheet of 1.25mm thick(18 gauge) special profile extruded section. The pressed steel frame should as per IS 4351/1976. The rate in inclusive of bottom the hold fasts and provision to aldrup tower bolt hinges and lock plate etc., with a one coat of zinc chromate yellow primer and filling the inside hallow portion with cement concrete 1:2:4 etc., complete complying with standard specification.	23 & 24		1 RM (One Running metre)	

Contractor

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

1	2	3	4	4	5	6
31	9.23 RM [Nine point Two Three running metre only]	Supplying and fixing in position of MDF Shutter 35mm thick (ISI) for door (single leaf) with commercial solid core with commercial veneering 3mm thick on both sides hot pressed bonded with liquid phenol for maldehyde with resin and teak wood internal (35 x 12mm) lipping as per IS 2202/Part-I/1991.The shutter will be supplied with ISI mark and fixed in steel frames. Necessary furniture fitting such as Alu.anodised butt hinges 100mm - 3Nos with Nylon washers, Alu.anodised tower bolt 300mm - 1No, Alu.anodised aldrop 300mm - 1No, Alu.handle 100mm - 1No, will be supplied and fixed etc., complete as per standard specification.	23 & 24		1 RM (One Running metre)	
32		Fabricating Spplying and fixing in position of aluminium anodised Powder Coated half panelled with 12mm thick bothside prelaminated partile board at bottom and half glazed using 5.50mm thick Plain glass at top .The outer frame shall be with aluminium box section 101.60x44.45x3.18m at 2.319kg/m and with Shutter section bottom rail 100x44.45x2.50mm @ 1.974 kg/m,Top&Vertical rail : 50x44.45x2.50mm @ 1.292kg/m,Lock rail: 50x44.45x2.50mm @ 1.292kg/m, Alu.clips:17.15x17.27x1.50mm @ 0.176kg/m,Aluminium Handle : 100x30mm @ 0.988kg/m the following shutter frames and necessary accessories such as aluminium clips, rubber beading PVC felt, handle for a length of shutter (both sides), locking arrangements, furniture fittings such as aluminium tower bolts-250x12mm - 2 Nos., aluminium tower bolt 200x12mm - 1No., aluminium Hydraulic door closser - 2Nos ., lock-1No., Door stopper with rubber bush as per BIS standards including cost of all materials, labour charges and power consumption charges required for fabrication including chipping dismantling and making holes to the required extent in RCC in column/beam/masonry with power drill wherever neccessary and redoing the damaged portion to the original condition after fixing etc. complete.Alu. Section are to be anodised with matt finish under electricaly controlled condition in accordance with IS 1868/1962 for an average anodic film thickness of 15 microns etc., complete.Aluminium sections,and furniture fittings shall be got approved by the Executive Engineer incharge.				

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

1	2	3	4	4	5	6
a	3.15 M ² [Three point One Five square metre only]	Double leaves	23 & 24		1 M ² (One square metre)	
33	952.00 Kg [Nine Hundred and Fifty Two point Zero Kilogram only]	supplying and fixing Ms grills for doors, windows and ventilators of approved design and as directed by the departmental officers including cost of ms grills labour charges and cost of one of red oxide primer coat etc., complete complying with std. specification.	23 & 24		1 Kg (One Kilogram)	
34	3.80 M ² [Three point Eight Zero square metre only]	Solid PVC door shutters using 19 Gauge 19mm MS square tubes for styles and outer frames. 15mm MS square tubes for top, lock and bottom rails. The steel tubes shall be covered with 5mm thick solid PVC sheets. Shutter using 5mm thick solid PVC sheets for panelling shall rigidly fixed in position including necessary furniture and fittings. The over all size of styles shall be 50mm x 30mm. The over all size of top rail, Lock rail and bottom rail shall be 75mm x 30mm. The over all size of frames shall be 50mm x 45mm, with suitable rabate for housing the shutter.Solid panel PVC door with frame	23 & 24		1 M ² (One square metre)	

Contractor

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

1	2	3	4	4	5	6
35		UPVC Window Specification: Supplying and fixing UPVC (Un-Plasticized Polyvinyl Chloride) Windows of casement type (open) from the profile the size of outer frame 60mm x 58mm and shutter profile are reinforcement with GI/1mm 125GSM and 100% corrosion free, the profiles are multi chambered sections with wall thick of 2mm. The EPDM rubber (black colour) covered with over all the edges of frame and shutter the shutter will be provided with Espag multi power point locks and also it operates as handle. The corners and joints should be welded and cleaned. Radiations free pin headed plain or brown colour glass 4mm thick should be provided to the shutter and it should not allow leakage of water even at most ranging storms and should have key lockable action, security protective hinges, strong locking systems and as per size for arresting noise and energy loss. The connecting mechanism between sash and outer frame that enables opening of the window. The window should be fixed to the wall with 100% packing with screws and silicon packing all round the frames. The window should be got approved from the Executive Engineer before use on work	23 & 24			
a	9.36 M ² [Nine point Three Six square metre only]	Two leaves window	23 & 24		1 M ² (One square metre)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

1	2	3	4	4	5	6
36	1.10 M ² [Forty Two point Five Zero square metre only]	Supplying and fixing UPVC (Un-Plasticized Polyvinyl Chloride) Louvered Ventilators of from the profile the size of outer frame 60mm x 58mm and shutter profile size of 60 x 78mm both profiles are reinforced with GI/1mm 125GSM and 100% corrosion free, the profile are multi chambered sections with wall thick of 2mm. The EPDM rubber (black colour) covered with all over the edges of frame and shutter. The corners and joints should be welded and cleaned. Radiations pin headed glass 4mm thick should be provided in the louvers. The window should be fixed to the wall with 100% packing with screws and silicon packing all round the frames. The ventilator should be got approved from the Executive Engineer before use on work	23 & 24		1 M ² (One square metre)	
37	72.00 M ² [Seventy Two square metre only]	Painting new iron works such as steel doors, windows, ventilators, window bars, balustrates etc., with two coats of best approved first quality and colour of synthetic enamel paint over the existing red oxide priming coat in all floors. The rate is inclusive of all materials, brushes and scaffolding charges etc., complete complying with standard specification. (The make, quality and colour of Paint should be got approved by the Executive Engineer before use on work)	23 & 24		1 M ² (One square metre)	
38	20.30 M ² [Twenty point Three Zero square metre only]	Painting new wood work with two finishing coats of synthetic enamel ready mixed paint of approved quality and colour over one coat priming coat in all floors including the cost of primer etc., complete complying with standard specification. (The make, quality and colour of paint should be got approved by the Executive Engineer before use on works.)	23 & 24		1 M ² (One square metre)	

Contractor

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

1	2	3	4	4	5	6
39	133.00 M ² [One Hundred and Thirty Three point Zero square metre only]	White washing three coat with freshly burnt white shell lime in all floors including cost of lime, blue powder, fevicol type gum, brushes, scaffolding charges, etc., complete complying with standard specification and as directed by the departmental officers.	23 & 24		1 M ² (One square metre)	
40	308.50 M ² [Three Hundred and Eight point Five Zero square metre only]	Painting two coats of newly plastered wall surface with ready mixed plastic Exterior emulsion paint of first class quality and of approved colour over a priming coat including thorough scrapping, clean removal of dirt, and including necessary plaster of paris putty, wherever required etc., complete complying with standard specification.	23 & 24		1 M ² (One square metre)	
41	463.00 M ² [Three Hundred and Seventy Nine point Zero square metre only]	Painting two coats of newly plastered wall surface with ready mixed plastic Interior emulsion paint of first class quality and of approved colour over a priming coat including thorough scrapping, clean removal of dirt, and including necessary plaster of paris putty, wherever required etc., complete complying with standard specification.	23 & 24		1 M ² (One square metre)	
42	1.00 Nos [One Number only]	Supplying and fixing in position European Water Closet (Oriya type) of size 580 x 440mm white glazed earthenware of approved quality and brand with "P" or "S" trap conforming to BIS with sand cushion and forming flooring around the closet using 40mm bro	23 & 24		1 No (One Number)	

Contractor

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

1	2	3	4	4	5	6
43	1.00 Nos [One Number only]	Supplying and fixing in position Indian Water Closet (Oriya type) of size 580 x 440mm white glazed earthenware of approved quality and brand with "P" or "S" trap conforming to BIS with sand cushion and forming flooring around the closet using 40mm broken brick jelly in lime concrete 1:2:5 (One lime, Two sand and Five brick jelly) 100mm thick and finishing the top to the required slope and including giving necessary connection to CI soil pipes (including the cost of 100mm dia CI pipe for a length of 600mm) by dismantling brick masonry wall / reinforced cement concrete roof / floor slab and making good the dismantled portion to the original condition with leakages etc., complete complying with standard specifications and as directed by the departmental officers. (The water closet should be got approved by the Executive Engineer before use on works).	23 & 24		1 No (One Number)	
44	1.00 Nos [One Number only]	Supplying and fixing in position best quality and approved make Indian made white glazed earthenware wash hand basin With out Pedestal of size 550 x 400mm with a pair of cast iron brackets, including cost 15mm dia brass CP pillar tap, 32mm dia "B" class GI waste pipe with rubber plug and chain, 15mm dia GM wheel valve, 15mm brass nipple, 15mm dia nylon connection, 32mm dia CP brass waste coupling including fixing of wash basin using CI brackets on to the wall in position with TW plugs and screws, rubber washers, white lead and giving necessary water supply connection and painting the brackets with two coat of painting over a priming coat of anti-corrosive paint including testing for leakages etc., complete complying with standard specification and as directed by the departmental officers. (The wash hand basin and specials should be got approved by the Executive Engineer before use on works).	23 & 24		1 No (One Number)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
45	2.00 Nos [Two Numbers only]	Supplying and fixing in position best quality cuddapah sink of 600mm x 450mm x 200mm sizes including cost of 32mm dia CP waste coupling, 32mm dia PVC waste pipe with rubber plug and chain, 15mm dia brass nipple including fixing the sink in position and testing for leakages etc., complete complying with standard specifications excluding CI brackets. [The sink and specials should be got approved by the Executive Engineer before use on works]	23 & 24		1 No (One Number)	
46	2.00 Nos [Two Numbers only]	Supplying and fixing in position indian make beveled edge mirror of approved quality and brand of size 600x450x5.5mm PVC shelf type frame in necessary ply wood baking, urbbber buttons, brass CP screws T.W. plugs etc complete complying in standard specification and as directed by the departmental officers (The minor should be got approved by the Executive Engineer before use on)	23 & 24		1 No (One Number)	
47	2.00 Nos [Two Numbers only]	Supplying and fixing approved best quality brass CP towel rail 600mm long and 20mm dia with brackets of same materials including cost of teak wood plugs and CP screws, etc., complete complying with standard specifications. (The tower rail should be got approved by Executive Engineer before use on works).	23 & 24		1 No (One Number)	
48	2.00 Nos [Two Numbers only]	Supplying and fixing in position best approved quality Aluminum C.P. brass soap tray of size 150x150mm including cost of teak wood plugs, brass screws, etc., complete complying with standard specification and as directed by the departmental officers.	23 & 24		1 No (One Number)	

Contractor

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

1	2	3	4	4	5	6
49		Supplying and fixing in position best quality PVC soil / waste pipes of various dia having 6 kg / sq.cm. pressure BIS mark and providing leak proof joints using PVC adhesives including fixing to the wall with special PVC / MS clamp, teak wood plugs, brass screws, etc., and making connection to all sanitary fittings, dismantling masonry / RCC works wherever found necessary and making the good dismantled portion to the original condition, including testing for any leakages, etc., complete complying with standard specifications. (The PVC pipes should be got approved by the Executive Engineer before use on works). The rate for earth work excavation will be measured and paid separately in the cases where the pipe lines are proposed to laid below ground level				
a	10.00 RM [Ten running metre only]	110mm dia PVC soil pipe	23 & 24		1 RM (One Running metre)	
b	5.00 RM [Five running metre only]	75 mm dia PVC soil pipe	23 & 24		1 RM (One Running metre)	
50		Supplying and fixing in position PVC specials of the following dia and types of approved quality confirming to BIS and providing leak proof joints including fixing to the walls and giving connection to the PVC soil stacks, dismantling the masonry or RCC works and re-doing the dismantled portion to original condition etc., complete complying with standard specifications. (The PVC specials should be got approved by the Executive Engineer before use on works).				

Contractor

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

1	2	3	4	4	5	6
a	5.00 Nos [Five Numbers only]	110mm dia PVC plain Elbow	23 & 24		1 No (One Number)	
b	4.00 Nos [Four Numbers only]	110mm dia PVC door Elbow	23 & 24		1 No (One Number)	
c	6.00 Nos [Six Numbers only]	110mm dia PVC Tee Elbow	23 & 24		1 No (One Number)	
d	5.00 Nos [Five Numbers only]	75mm dia PVC plain Elbow	23 & 24		1 No (One Number)	
e	4.00 Nos [Four Numbers only]	75mm dia PVC door Elbow	23 & 24		1 No (One Number)	
f	4.00 Nos [Four Numbers only]	75mm dia PVC door Elbow	23 & 24		1 No (One Number)	
g	4.00 Nos [Four Numbers only]	75mm dia PVC door Tee	23 & 24		1 No (One Number)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
h	6.00 Nos [Six Numbers only]	110mm dia PVC door Bend	23 & 24		1 No (One Number)	
i	6.00 Nos [Six Numbers only]	75mm dia PVC door Bend	23 & 24		1 No (One Number)	
j	5.00 Nos [Five Numbers only]	110mm dia PVC door Y	23 & 24		1 No (One Number)	
51	4.00 Nos [Four Numbers only]	Supplying and fixing position PVC Nahani Trap of size 100 x 75mm with PVC gratings with best stainless steel gratings of approved brand and quality, fixed over a bed of brick jelly lime concrete 1:2:5 (One part of lime, two part of sand and five part of 40mm gauge brick jelly) and finished with Cement Mortar 1:3 (One Cement, Three sand) including dismantling masonry works wherever found necessary and making good the dismantled portions to the original condition and giving connection to the CI / PVC pipes, etc., complete complying with standard specification. (The Nahani Trap should be got approved by the Executive Engineer before use on works)	23 & 24		1 No (One Number)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
52		Supplying, laying and jointing PVC pipes (having working pressure 10 kg. / sq.cm) of approved quality and best variety conforming to BIS of the following dia including cutting, threading and fixing PVC specials using PVC adhesives (but excluding cost of such specials) and fixing into wall with teak wood plugs, PVC clamps and screws making holes on the wall (or) drilling holes in the roof and making good the dismantled portion to original condition with necessary brick work / cement concrete and plastering neatly wherever necessary with necessary scaffolding charges upto 4 metre height above ground level, etc., complete complying with standard specifications. The PVC pipes shall be got approved by Executive Engineer before use on works.				
		Internal-Above Ground Level				
a	25.00 RM [Twenty Five running metre only]	25 mm dia	23 & 24		1 RM (One Running metre)	
b	20.00 RM [Twenty running metre only]	20 mm dia	23 & 24		1 RM (One Running metre)	
		External -Below Ground Level				
c	15.00 RM [Nine running metre only]	40 mm dia	23 & 24		1 RM (One Running metre)	
		External - Above Ground Level				

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
d	10.00 RM [Four running metre only]	40 mm dia		23 & 24		1 RM (One Running metre)
53		Supplying and fixing in position the following PVC Specials of heavy type and approved quality and good variety of various sizes excluding fixing charges but including necessary cutting and threading of PVC Pipes jointing the PVC Specials and painting two coats with good variety and best quality synthetic enamel paint over a coat of red oxide primer in case of pipe line above ground level and one coat of tarring in case of pipe below ground level for both internal and external water supply arrangements etc. complete complying with standard specification and as directed by the departmental officers. (The G.I. Specials used on the work shall be got approved by the Executive Engineer before use on words)				
a	5.00 Nos [Five Numbers only]	40 mm dia PVC Elbow		23 & 24		1 No (One Number)
b	3.00 Nos [Three Numbers only]	40mm dia PVC Tee		23 & 24		1 No (One Number)
c	4.00 Nos [Four Numbers only]	40mm dia PVC Coupler		23 & 24		1 No (One Number)
d	4.00 Nos [Four Numbers only]	40mm dia PVC bend		23 & 24		1 No (One Number)

Contractor

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

1	2	3	4	4	5	6
e	5.00 Nos [Five Numbers only]	25 mm dia PVC Elbow	23 & 24		1 No (One Number)	
f	3.00 Nos [Three Numbers only]	25mm dia PVC Tee	23 & 24		1 No (One Number)	
g	3.00 Nos [Three Numbers only]	25mm dia PVC Coupler	23 & 24		1 No (One Number)	
h	5.00 Nos [Five Numbers only]	25mm dia PVC bend	23 & 24		1 No (One Number)	
i	4.00 Nos [Four Numbers only]	25mm x 20mm dia PVC Reducer	23 & 24		1 No (One Number)	
j	5.00 Nos [Five Numbers only]	25mm x 20mm dia PVC Tee	23 & 24		1 No (One Number)	
k	4.00 Nos [Four Numbers only]	20 mm dia PVC Elbow	23 & 24		1 No (One Number)	
l	3.00 Nos [Three Numbers only]	20mm dia PVC Tee	23 & 24		1 No (One Number)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
m	3.00 Nos [Three Numbers only]	20mm dia PVC Coupler	23 & 24		1 No (One Number)	
n	2.00 Nos [Two Numbers only]	20mm dia PVC bend	23 & 24		1 No (One Number)	
o	4.00 Nos [Four Numbers only]	20mm x 15mm dia PVC Reducer	23 & 24		1 No (One Number)	
p	3.00 Nos [Three Numbers only]	20mm x 15mm dia PVC Tee	23 & 24		1 No (One Number)	
q	4.00 Nos [Four Numbers only]	20mm x 15mm Reducer Elbow	23 & 24		1 No (One Number)	
54	6.00 Nos [Six Numbers only]	Supplying and fixing in position 15mm dia brass CP screw down tap / Pillar tap (heavy duty) of approved make conforming to BIS specifications and quality including cost of shellac, thread, etc., complete complying with standard specification and including cutting and threading wherever necessary. (Taps should be got approved by the Executive Engineer before use on the works)	23 & 24		1 No (One Number)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
55		Supplying and fixing in position first quality and approved variety of Gun metal Gate Valve / Wheel Valve with BIS make of the following dia including cost of shellac, thread balls, etc., complete complying with standard specifications (for both internal and external water supply arrangements). The valves to be used on work shall be got approved by the Executive Engineer before use on work.				
a	1.00 Nos [One Numbers only]	25 mm dia	23 & 24		1 No (One Number)	
b	1.00 Nos [One Numbers only]	40mm dia	23 & 24		1 No (One Number)	
56	1.00 Nos [One Numbers only]	Supplying and filling following sizes of ISS 40 mm metal for filtration pits and percolation pits	23 & 24		1 M ³ (One cubic metre)	
57	1.00 Nos [One Numbers only]	Supplying and filling following sizes of ISS 20 mm metal for filtration pits and percolation pits	23 & 24		1 M ³ (One cubic metre)	

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

Contractor

1	2	3	4	4	5	6
58	1.00 Nos [One Numbers only]	Supplying and fixing PVC ventilating shaft of 110mm dia (having working pressure 4 kg. / sq.cm) with 3 metre height including cost of PVC cylindrical cowl of best approved quality etc., complete complying with standard specifications and as directed by the departmental officers	23 & 24		1 No (One Number)	
59	155.71 M ² [One Hundred and Fifty Five point Seven One Square Metre Only]	Providing pre construction anti termite treatment for the building work at different stages as furnished below conforming to IS 6313 (part II) ,2001etc complete and as directed by the departmental officer. Chloropyriphos 1%(by weight) in aqueous emulsion	23 & 24		1 M ² (One square metre)	
60		Earth work Open well excavation complying with relevant clauses of T.N.D.S.S well sinking and with lead upto 10 metre in sand, silt or loose soil, Wet sand or silt not under water, light black cotton soil, sandy loam and ordinary soil Firtst depth of 2 metre.	23 & 24			
a	5.72 M ³ [Five point Seven Two Cubic metre only]	First depth of 2 metre.	23 & 24		1 M ³ (One cubic metre)	
b	5.72 M ³ [Five point Seven Two Cubic metre only]	Second depth of 2 metre.	23 & 24		1 M ³ (One cubic metre)	

Contractor

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram

1	2	3	4	4	5	6
c	5.72 M ³ [Five point Seven Two Cubic metre only]	Third depth of 2 metre.	23 & 24		1 M ³ (One cubic metre)	
d	5.72 M ³ [Five point Seven Two Cubic metre only]	Fourth depth of 2 metre.	23 & 24		1 M ³ (One cubic metre)	
e	5.72 M ³ [Five point Seven Two Cubic metre only]	Fifth depth of 2 metre.	23 & 24		1 M ³ (One cubic metre)	
61	34.00 Nos [Thirty Four Numbers only]	Erection of Ring well below water level including all incidental charges using special tools and plants such as air compressor helmet etc. complete and including bailing out water.			1 No (One Number)	
62	1.00 Nos [One Numbers only]	Supply of 1.00HP jet motor with ISI Mark All Items rate serial no 394	23 & 24		1 No (One Number)	
63	1.00 Nos [One Numbers only]	Supplying and fixing in position of best Indian make PVC Water Tank of 1000 litres capacity conforming to ISI standards as directed by the departmental officers including cost of material and conveyance charges of material to work site etc., complete complying with standard specifications.	23 & 24		1 No (One Number)	
Sub Total						
Provision for CGST (6%) + SGST (6%)						
No. of Items: 63 [Sixty Three items Only]						
Total Rupees Nil						

Contractor

Executive Engineer, PWD.,
Buildings [C&M] Division,
Ramanathapuram