

Validate

Print

Help

Item Rate BoQTender Inviting Authority: **EXECUTIVE OFFICER, TOWN PANCHAYAT SANKARNAGAR TIRUNELVELI DISTRICT**Name of Work: **Black Topping The Road at Ganapathay Mills 1st and 3rd cross street,East side 1st and 2nd cross street,West side 4th cross street and Chidhambaram Nagar in Sankar Nagar Town Panchayat**

Contract No:

| | | | | | | | |
|--|---|----------|--------|-------------------------|---|-------------------------------------|-----------------------|
| Name of the Bidder/ Bidding Firm / Company : | | | | | | | |
| <div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div> | | | | | | | |
| NUMBER # | TEXT # | NUMBER # | TEXT # | NUMBER | NUMBER # | NUMBER # | TEXT # |
| Sl. No. | Item Description | Quantity | Units | Estimated Rate in Rs. P | BASIC RATE In Figures To be entered by the Bidder Rs. P | TOTAL AMOUNT Without Taxes in Rs. P | TOTAL AMOUNT In Words |
| 1 | 2 | 4 | 5 | 6 | 13 | 53 | 55 |
| 1 | Picking the existing surface 3 to 5 cm deep removal of picked up staff to the side berms and using the useful metal to the road hand packing to camber sectioning levelling etc.,complete as per including labour charges for picking and other tools and plants etc., complete as per standard specifications. 404 of MORTH | 72.00 | m3 | | | | 0 INR Zero Only |
| 2 | Construction of Granular Sub-base by providing close graded material,mixing in a machanical plant at OMC,carriage of mixed material to work site,spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to acheive the desired density,Complete as per clause 401. | 239.00 | m3 | | | | 0 INR Zero Only |
| 3 | Providing and laying ,spreading and compacting graded stone aggregate to wet mix macadam (WMM) Grade I specification including premixing the material with water at OMC in mechanical mix plant carriage to mixed material by tipper to site laying in uniform layers with paver in sub base / base course on well prepared surface and compacting with vibratory roller to achive the desired density complete as per clasue 404 of MORTH specifications. | 239.00 | m3 | | | | 0 INR Zero Only |
| 4 | Providing and laying Prime coat of 7kgs/10 sqm over the WMM surface treated with primer using 7kgs of bituminous Emulsion for 10 square meter area including cost of bituminous binder, including labour charges for applying the required quantity of bituminous binder as Prime coat manually etc., complete as per 503 of MORTH Specifications | 1587.00 | m2 | | | | 0 INR Zero Only |

| | | | | | | | |
|-----------------------------|---|----------------------|----|--|--|-------------|-----------------|
| 5 | Providing and laying tack coat of 2.5 kgs/10 sqm over the WMM surface treated with binder using 2.5 kgs of bituminous Emulsion for 10 square meter area including cost of bituminous binder, including labour charges for applying the required quantity of bituminous binder as tack coat manually etc., complete as per 503 of MORTH Specifications | 1587.00 | m2 | | | | 0 INR Zero Only |
| 6 | Providing and laying 50 mm compacted thick dense bituminous macadam using 0.24 cum of 26.5-13.2 mm graded metal and 0.25 cum of 13.2-2.36 mm graded metal and 0.23 cum of 2.36 mm & below metal with 53.20 kgs of 60/70 bitumen for premixing per 10 sqm including cost and conveyance of all materials to C M P site, heating the bitumen and aggregates to required temperature and mixing them in required temperature in central hot mix plant 20- 30 tonnes capacity conveying the mix by tipper trucks to paver site,spreading the mix in required temperature for uniform thickness of 50 mm with mechanical paver to the specified grades and cross sections and compaction by 80-100 KN power roller to the required density etc.including labour charges for loading bitumen in to bitumen tank and metal to feeder unit,labour for attending to paver site etc., including hire charges and fuel charges for 20-30t C M P with bitumen boiler,tipper trucks,paver finisher, power rollers and all other tools and plants required,including all other incidental charges etc.,complete using C M P clause 505 of MORTH Rev-5 specifications. | 80.00 | m3 | | | | 0 INR Zero Only |
| 7 | Providing and laying Bituminous concrete to 30mm thick using 0.13 cum of 19.00-9.50 mm graded metal and 0.17 cum of 9.50-2.36 mm graded metal and 0.26 cum of 2.36 mm & below metal with 50.30 kgs of 60/70 bitumen & including cost and conveyance of all materials to C M P site, heating the bitumen and aggregates to required temperature and mixing them in required temperature in central hot mix plant 20- 30 tonnes capacity conveying the mix by tipper trucks to paver site,spreading the mix in required temperature for uniform thickness of 40 mm with mechanical paver to the specified grades and cross sections and compaction by 80-100 KN power roller to the required density etc., including labour charges for loading bitumen in to bitumen tank and metal to feeder unit,labour for attending to paver site etc., including hire charges and fuel charges for 20-30t C M P with bitumen boiler,tipper trucks,paver finisher, power rollers and all other tools and plants required,including all other incidental charges etc.,complete using C M P clause 507 of MORTH Rev-5 specifications. | 48.00 | m3 | | | | 0 INR Zero Only |
| Total in Figures | | | | | | 0.00 | INR Zero Only |
| Quoted Rate in Words | | INR Zero Only | | | | | |