

SALEM CITY MUNICIPAL CORPORATION

TENDER SCHEDULE

Name of Contractor :

EMD Details **Rs.11,000/-**

Tender Date **01.06.2022**

Name of Work **Construction of Drain and Formation of Cement Concrete Lane Near Kannara Street in Div.30 of Zone-II**

Est. No. **E3/Est No : 487/D/2021-2022**

Estimate Cost **Rs.11,00,000/-**

1. The Quantities here given are those upon the lump sum tender cost of work is based, but they are subject to alterations, omissions, deductions or additions as provided for the conditions of the contract and do not necessarily show the actual quantities of work to be done. The unit rates are those governing payment for extracts or deductions for omissions according to the contract, as set forth in the preliminary specifications of the (Madras Detailed Standard Specifications) Tamil Nadu building practice and other conditions or specifications of the contract.

2. It is to be expressly understood that the measured work is to be taken nett (not with standing any custom or practice to the contrary) according to the actual quantities when in place and finished according to the drawing or as may be ordered from time to time by the Corporation Engineer and the cost calculated by measurement of weight, of the respective prices, with out additional charge for any necessary contingent works connected herewith. The Rates quoted are for works in 'situ' and complete in every respect.

3. The work must be completed with in Days/Month from the date of receipt of acceptance of this tender.

SIGNATURE OF THE CONTRACTOR

Item No	Probable Quantity		Description of Work	Rate		Unit in	Amount in
	Figures	Units		Words	Figures	Words	Figure
1	120.00	m3	Earth work excavation for foundation in ordinary soil, light black cotton sandy loam and dry silt including shoring, strutting, baling or pumping out water wherever necessary and refilling the sides of foundation with excavated earth in layers of 15cm thick and depositing the surplus earth at places as directed by the departmental officers with initial lead and lift			m3	
2	30.00	m3	Collection, supply and filling of sand from approved quarry to work site and stocking to the Departmental gauge for premeasurement as directed by the Departmental Engineer, to required depth not more than 15cm depth including cost and Conveyance of sand to site and all labour charges for filling etc., Complete complying with Standard Specification			m3	
3	43.00	m3	Plain cement concrete 1:4:8 mix (One cement four sand and eight aggregate) using 40mm size ISS gauge HBBG metal including mixing, laying, consolidating, curing, cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification			m3	

SIGNATURE OF THE CONTRACTOR

4			Supplying and erecting centering to sides and soffits including supports and strutting for drainage sides and culvert body wall sides using M.S Sheets of size 90cm x 60cm and B.G 10stifened with welded mild steel angles of size 25mm x 25mm x 3mm for boarding laid over(silver oak joists) of size 10cm x 6.50cm spread at about 90cm including all labour charges and cost and conveyance of all materials to site etc. complete Complying with Standard Specification				
	305.00	m2	For Drain side walls - below 1m			m2	
5	19.00	m2	Supplying and erecting centering to sides and soffits including supports and strutting for drainage sides and culvert body wall sides using M.S Sheets of size 90cm x 60cm and B.G 10stifened with welded mild steel angles of size 25mm x 25mm x 3mm for boarding laid over(silver oak joists) of size 10cm x 6.50cm spread at about 90cm including all labour charges and cost and conveyance of all materials to site etc. complete Complying with Standard Specification			m2	

SIGNATURE OF THE CONTRACTOR

6			Plain cement concrete 1:2:4 mix (One cement two sand and four aggregate) using 20mm size ISS gauge HBBG metal including mixing, laying, consolidating, curing, cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification				
	45.00	m3	For Drain side walls & Culvert side walls			m3	
7	30.00	m3	Plain cement concrete 1:1½:3 mix (One cement one and half sand and three aggregate) using 20mm size ISS gauge HBBG metal including mixing, laying, consolidating, curing, cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification			m3	
8	12.00	m2	Supply and fixing of Bitumen Felt 15mm thick Pad for CC Road joints etc. complete as directed by the departmental officers			m2	

SIGNATURE OF THE CONTRACTOR

9	56.00	m2	Plastering with cement mortar 1:3 mix, 20mm thick including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing etc. complete . complying with			m2	
10	4.50	m3	Reinforced cement concrete 1:1½:3 mix (One cement one and half sand three aggregate) using 20mm ISS gauge HBBG metal from the approved quarry including mixing, laying, consolidating, curing cost and conveyance of all materials to site and all labour charges etc., complete as per standard			m3	
11	405.00	Kg	Supply and fabrication and placing in position of TMT steel rods to required size and length as directed by the departmental officers including cost of binding wire, cutting, bending and tying with proper position etc., including cost and conveyance of all materials to site and all labour charges etc., complete Complying with Standard Specification			Kg	

SIGNATURE OF THE CONTRACTOR