

SALEM CITY MUNICIPAL CORPORATION

TENDER SCHEDULE

Name of Contractor :

EMD Details **Rs.3,000/-**

Tender Date **31.05.2022**

Name of Work **Providing Laying of 150mm DI Main Line and House Service Connection(PVC line to D.I. Main) at Bharathi Nagar in Division No: 7, Zone-II.**

Est. No. **E2/Est No: 479/WS/2021-2022**

Estimate Cost **Rs.3,00,000/-**

1. The Quantities here given are those upon the lump sum tender cost of work is based, but they are subject to alterations, omissions, deductions or additions as provided for the conditions of the contract and do not necessarily show the actual quantities of work to be done. The unit rates are those governing payment for extracts or deductions for omissions according to the contract, as set forth in the preliminary specifications of the (Madras Detailed Standard Specifications) Tamil Nadu building practice and other conditions or specifications of the contract.

2. It is to be expressly understood that the measured work is to be taken nett (not with standing any custom or practice to the contrary) according to the actual quantities when in place and finished according to the drawing or as may be ordered from time to time by the Corporation Engineer and the cost calculated by measurement of weight, of the respective prices, with out additional charge for any necessary contingent works connected herewith. The Rates quoted are for works in 'situ' and complete in every respect.

3. The work must be completed with in Days/Month from the date of receipt of acceptance of this tender.

SIGNATURE OF THE CONTRACTOR

| Item No | Probable Quantity | | Description of Work | Rate | | Unit in | Amount in |
|---------|-------------------|-------|---|-------|---------|---------|-----------|
| | Figures | Units | | Words | Figures | Words | Figure |
| 1 | 63.00 | m3 | Towards Labour Charges for cutting open road for laying water mains or sewer etc., complete. | | | m3 | |
| 2 | | | Earth work excavation and Depositing on Bank with initial Lead of 10m and Lift of 2m in Narrow Trenches for Laying of Pipes for Water Supply and Sewerage Works in the Sand, Silt or other Loose Soil, Wet Sand or Silt not under Water Light Black Cotton Soil, Sandy Loom and Ordinary Soil as Directed by Departmental Officers etc. | | | | |
| | 234.00 | Rm | a). Laying of 25mm Dia PVC | | | Rm | |

SIGNATURE OF THE CONTRACTOR

| | | | | | | | |
|---|--------|-----|--|--|--|-----|--|
| 3 | | | Supply and Delivery of the following Water Supply Specials etc., complete. | | | | |
| | 350.00 | Rm | 20mm G.I. Pipe | | | Rm | |
| | 350.00 | Rm | 25mm PVC Pipe | | | Rm | |
| | 60.00 | Nos | 1/2" G.I. Feruval Brass | | | Nos | |
| | 75.00 | Kg | 20mm G.I. Union | | | Kg | |

SIGNATURE OF THE CONTRACTOR

| | | | | | | | |
|--|-------|-------|----------------------|--|--|-------|--|
| | 5.00 | Liter | Solvent Cement | | | Liter | |
| | 75.00 | Kg | 1/2"x3/4" G.I. Elbow | | | Kg | |
| | 75.00 | Kg | 3/4" G.I. Nipple | | | Kg | |
| | 5.00 | Nos | 6" PVC TEE 6KSC | | | Nos | |
| | 2.00 | Nos | 6" PVC End Cup 6KSC | | | Nos | |

SIGNATURE OF THE CONTRACTOR

| | | | | | | | |
|---|---------|----|---|--|--|----|--|
| | 100.00 | Rm | 6" PVC 6 KSCPipe | | | Rm | |
| 4 | | | Conveyance & Laying of Main pipe line including all cost and conveyance etc., complete | | | | |
| | 1050.00 | Rm | a). Laying of 25mm Dia PVC | | | Rm | |
| 5 | | | Refilling with excavated earth (other than Sand) Complying with the Standard Specification for Foundation and Basement including all cost and conveyance etc., complete | | | | |
| | 216.00 | Rm | a). Laying of 25mm Dia PVC | | | Rm | |

SIGNATURE OF THE CONTRACTOR