

[Validate](#)[Print](#)[Help](#)

Item Rate BoQ

Tender Inviting Authority: Executive Officer Town Panchayat Sambavarvadakarai

Name of Work: Construction of Retaining Wall 4th Ward Kombumadasamy Kovil Street , 8th Ward Melarathaveethi Mel Paguthi Street, 9th Ward Chirsthavar Streets For Canal Sides in Sambavarvadakarai Town Panchayat.

Contract No: 239/2021/A1

Name of the Bidder/ Bidding Firm /							
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8	9
1	Earth work excavation and depositing on the bank with initial lead and lift of 10 metres and initial lift of 2 metres in hard stiff clay stiff block cotton hard red earth murram, gravel stoney earth and earth mixed with small size boulders and hard gravelly soils (SS 20 B) etc., complete as per standard specification - 1m3 For Drainage	141.00	cum			0.00	INR Zero Only
2	Plain cement concrete Using 1:4:8 mix (One cement , four Sand and Eight aggregates) using 40 mm ISS HBG metal including cost and conveyance of all materials to work site and all labour charges for mixing, laying,consolidating and curing etc complete as per the standard specifications. TNDSS NO: 28 V, VI (S2) V,VI (S5A) VII	29.00	cum			0.00	INR Zero Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	7	8	9
3	Supplying and erecting centering to sides and soffits including supports and strutting with necessary cross bracing for plain surface such as RCC slabs rectangular beams all beams lintels etc., centering for soffits upto 3 meter height using mild steel sheet of size 90 cm x 60 cm x 10 mm gauge with MS angles of size 25mm x 25mm x 3mm laid over silver oak (CW) joists of size 10cm x 6cm spaced upto 90cm c/c and casurina props or 10 cm to 13 cm dia spaced at 0.750 cm c/c complying with standard specifications as per TNDSS NO : 30 & 86.	500.00	sqm			0.00	INR Zero Only
4	Plain Cement Concrete 1:3:6 Mix (one part cement, three part M-Sand and six part of aggregate) using 40mm size ISS HBG metal machine crushed from approved quarry including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing etc., complete as per TNDSS NO: 28 & VI (S2) VI (S5A) VII standard specifications as directed by Engineer incharge.	229.00	cum			0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					